

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE 0014		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	200	200		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	66	66		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	675	675		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	675	675		
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2224	2224		
*78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	278	278		
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8	8		
78300100	PAVEMENT MARKING REMOVAL	SO FT	660	660		
X7010208	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	2	2		
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	36	36		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE 0014		
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SO YD	1018	1018		
Z0012112	BRIDGE DECK FLY ASH OR GGBF SLAG CONCRETE OVERLAY, 2 3/4"	SO YD	1018	1018		
Z0012130	BRIDGE DECK SCARIFICATION 3/4"	SO YD	1018	1018		
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SO YD	2	2		
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	30	30		

\*SPECIALTY ITEM

FILE NAME -	USER NAME - steffennek	DESIGNED -	REVISED -
c:\p\work\p\uidot\steffennek\0307594\0307594-1.dwg	74589-shi-sqa.dgn	DRAWN -	REVISED -
Default	PLOT SCALE - 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE - 10/23/2012	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET 2 OF 2 SHEETS STA. TO STA.

D7 BRIDGE REPAIRS 2013-1

F.A.I. RIE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
TO	-	EFFINGHAM	33	4
CONTRACT NO. 74589			ILLINOIS FED. AID PROJECT	