

TRAFFIC CONTROL DEVICES

STATION TO STATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
	FOOT	FOOT	EACH	EACH
STAGE I				
EB 2738+62.50 TO 2740+25.00	162.5	0.0	1.0	0.0
EB 2740+25.00 TO 2742+00.00	175.0	0.0	0.0	0.0
STAGE II				
EB 2738+62.50 TO 2740+25.00	0.0	162.5	0.0	1.0
EB 2740+25.00 TO 2742+00.00	0.0	175.0	0.0	0.0
STAGE I				
WB 2740+75.00 TO 2742+50.00	175.0	0.0	0.0	0.0
WB 2742+50.00 TO 2744+12.50	162.5	0.0	1.0	0.0
STAGE II				
WB 2740+75.00 TO 2742+50.00	0.0	175.0	0.0	0.0
WB 2742+50.00 TO 2744+12.50	0.0	162.5	0.0	1.0
TOTALS	675.0	675.0	2.0	2.0

PAVING SCHEDULE

STATION TO STATION	LENGTH	WIDTH	AREA	HMA SURFACE REMOVAL, (1 1/2")	POLYMERIZED HMA SURFACE COURSE, MIX "D", N90	BITUMINOUS MATERIAL (PRIME COAT)
	FOOT	FOOT	SO FT	SO YD	TON	GALLON
SN 025-0016 (EB)						
2740+49.00 TO 2740+69.00	20.0	24.0	480.0	53.3	5	6
2741+90.00 TO 2742+10.00	20.0	24.0	480.0	53.3	5	6
SN 025-0017 (WB)						
2740+65.00 TO 2740+85.00	20.0	24.0	480.0	53.3	5	6
2742+06.00 TO 2742+26.00	20.0	24.0	480.0	53.3	5	6
TOTALS				213.3	20	24

• 07 BRIDGE REPAIRS 2013-1

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
ct:\pw\work\p\dot\stef\mk\d0307594\074589-sht-schedules.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 10/23/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET 2 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	•	EFFINGHAM	33	7
CONTRACT NO. 74589			ILLINOIS FED. AID PROJECT	