RESURFACING SCHEDULE

LOCATION STATION TO STATION	ROADWAY	HOT-MIX ASPHALT BASE COURSE, 10" (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS (TON)	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90 (TON)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80 (TON)	P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT (SPECIAL) (SQ YD)	AGGREGATE SHOULDERS, TYPE B (TON)	AGGREGATE WEDGE SHOULDER, TYPE B (TON)	HOT-MIX ASPHALT SHOULDERS (TON)	SHOULDER RUMBLE STRIPS, 16 INCH (FOOT)	HOT-MIX ASPHALT SHOULDER CURB (FOOT)	PROTECTIVE COAT (SQ YD)
STA 1239+97.00 TO STA 1242+13.00	I-255 SB	265.70		4.08										17.22
STA 1242+13.00 TO STA 1244+00.00	I-255 SB		0.86	101.22	0.31		140.08	32.21		10.05	38.91	297.68		14.99
STA 1244+00.00 TO STA 1292+00.00	I-255 SB	1275.49	22.50	21.02	7.30	25.67	5416.27	60.20	40.15	505.82	2577.17	8803.44	961	92.88
STA 1292+00.00 TO STA 1303+00.00	I-255 SB		3.08	25.44	0.94	89.60	647.40	60.48		93.07	363.09	1548.10		60.48
STA 1303+00.00 TO STA 1318+00.00	I-255 SB	561.87	5.30	91.92	1.56	22.40	1148.64	32.49		154.34	728.44	2415.00		32.49
STA 1317+98.45 TO STA 1357+00.00	I-255 SB		19.16	56.64	6.66		4968.39	47.36		458.96	1886.08	7442.05	308	63.69
STA 1357+00.00 TO STA 1390+80.00	I-255 SB	174.09	12.12	1.52	3.93	49.47	2876.58	33.02	9.45	316.51	1377.85	4963.63	400	33.02
STA 1390+80.00 TO STA 1394+05.00	I-255 SB													
STA 1242+13.00 TO STA 1244+00.00	I-255 NB		0.60	99.22	0.18		81.24	31.88		10.15	39.30	300.14		31.89
STA 1244+00.00 TO STA 1292+00.00	I-255 NB		20.74	18.00	6.86	16.80	5101.12	67.47	33.58	463.64	2275.92	8221.42	1108	100.14
STA 1292+00.00 TO STA 1303+00.00	I-255 NB	297.75	3.76	19.98	1.18	81.62	826.31	60.04	40.02	79.62	432.40	1321.05		60.04
STA 1303+00.00 TO STA 1318+00.00	I-255 NB		4.20	82.20	1.27	50.40	922.54	32.16		113.64	526.27	2118.60	308	48.51
STA 1317+98.45 TO STA 1357+00.00	I-255 NB	391.60	17.14	62.36	5.61	59.73	4141.27	43.78		458.46	1929.90	7342.97	140	60.12
STA 1357+00.00 TO STA 1390+80.00	I-255 NB	401.79	13.36	1.52	4.50	69.32	3283.74	39.99	35.47	291.54	1374.81	4520.64	441	39.99
STA 1390+80.00 TO STA 1394+05.00	I-255 NB													
STA 100+00.00 TO STA 112+01.51	COLLINSVILLE RD RAMP 7		2.32	10.94	0.70		454.52		78.50		289.39		202	49.02
STA 102+30.00 TO STA 160+94.00	I-55 RAMP 1		15.86	75.84	0.13		3558.99		838.84	207.88	2047.85	8474.20		
STA 200+00.00 TO STA 225+13.00	I-55 RAMP 2		4.54	21.84	0.16		991.77		538.77		624.79			
STA 300+00.00 TO STA 315+54.92	I-55 RAMP 3		2.70	12.88	0.58		605.42		304.02		357.41			
STA 400+00.00 TO STA 414+16.24	I-55 RAMP 4		2.56	12.28	0.57		563.98		302.96		351.25			
STA 500+00.00 TO STA 517+32.00	I-55 RAMP 5		3.20	15.46	0.94		698.98		390.31		449.20			
STA 600+00.00 TO STA 617+75.00	I-55 RAMP 6		3.28	15.78	0.96		716.14		397.11		456.89			
STA 700+00.00 TO STA 736+19.00	I-55 ROADWAY A		9.88	47.44	2.89		2155.78		379.56	217.95	1375.60	6791.42		
STA 801+89.00 TO STA 867+04.06	I-55 ROADWAY B		18.04	86.48	5.56		4111.48		809.91	263.55	2287.58	9862.89		26.48
STA 4+07.14 TO STA 21+43.00	HORSESHOE RAMP 1		3.22	15.38	0.92		687.28		382.18		454.15			
STA 1+54.00 TO STA 13+97.54	HORSESHOE RAMP 2		2.18	10.44	0.67		499.10		192.98		248.47		345	20.28
STA 3+14.84 TO STA 22+82.00	HORSESHOE RAMP 3		3.56	17.04	1.06		790.32		392.25		475.35		120	13.47
STA 1+39.00 TO STA 24+90.71	HORSESHOE RAMP 4		4.46	21.32	1.25		932.53		551.76		653.93			
	SUBTOTAL	3368.29	198.62	948.24	56.7	465.01	46319.87	541.08	5717.82	3645.18	23622.00	74423.23	4333	764.71
	PAY TOTAL	3369	198.7	948	56.7	465	46320	542	5718	3646	23622	74424	4333	765

REMOVAL SCHEDULE

LOCATION STATION TO STATION	ROADWAY	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SQ YD)	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT (SQ YD)	TEMPORARY RAMP (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL, 1" (SQ YD)	CURB REMOVAL (FOOT)	COMBINATION CURB AND GUTTER REMOVAL (FOOT)	CONCRETE BARRIER REMOVAL (FOOT)	PAVED SHOULDER REMOVAL (SQ YD)	MEDIAN REMOVAL (SQ YD)	PAVED SHOULDER REMOVAL (SPECIAL) (SQ YD)	BRIDGE APPROACH SHOULDER REMOVAL (SQ YD)
STA 1239+75.00 TO STA 1242+13.00	I-255 SB								266			
STA 1242+13.00 TO STA 1244+00.00	I-255 SB	472		63								34
STA 1244+00.00 TO STA 1292+00.00	I-255 SB			105		961			1275		36	63
STA 1292+00.00 TO STA 1303+00.00	I-255 SB			83								63
STA 1303+00.00 TO STA 1318+00.00	I-255 SB			42					562			34
STA 1317+98.45 TO STA 1357+00.00	I-255 SB			50		308					18	50
STA 1357+00.00 TO STA 1390+80.00	I-255 SB		498	135		400			174			36
STA 1242+45.00 TO STA 1244+00.00	I-255 NB	311		42								33
STA 1244+00.00 TO STA 1292+00.00	I-255 NB			83		1108					36	70
STA 1292+00.00 TO STA 1303+00.00	I-255 NB			96					298			63
STA 1303+00.00 TO STA 1318+00.00	I-255 NB			42		308					18	34
STA 1317+98.45 TO STA 1357+00.00	I-255 NB			50		140			392		18	47
STA 1357+00.00 TO STA 1390+80.00	I-255 NB		498	144		441			402			43
STA 100+00.00 TO STA 112+01.51	COLLINSVILLE RD RAMP 7	62	176	90		202	322	855		681	53	
STA 102+30.00 TO STA 160+94.00	I-55 RAMP 1		425	170	22258							
STA 200+00.00 TO STA 225+13.00	I-55 RAMP 2			39	6411							
STA 300+00.00 TO STA 315+54.92	I-55 RAMP 3				1390							
STA 400+00.00 TO STA 414+16.24	I-55 RAMP 4				2302							
STA 500+00.00 TO STA 517+32.00	I-55 RAMP 5	115		39								
STA 600+00.00 TO STA 617+75.00	I-55 RAMP 6	115		39								
STA 700+00.00 TO STA 736+19.00	I-55 ROADWAY A	178		59								
STA 801+89.00 TO STA 867+04.06	I-55 ROADWAY B	178	510	227							29	
STA 4+07.14 TO STA 21+43.00	HORSESHOE RAMP 1	116		38								
STA 1+54.00 TO STA 13+97.54	HORSESHOE RAMP 2	116		38		345					22	
STA 3+14.84 TO STA 22+82.00	HORSESHOE RAMP 3	116		38		120						
STA 1+39.00 TO STA 24+90.71	HORSESHOE RAMP 4	116		38							14	
	TOTAL	1895	2107	1750	32361	4333	322	855	3369	681	244	570

EROSION CONTROL SCHEDULE

LOCATION STATION	SIDE	INLET AND PIPE PROTECTION (EACH)	PERIMETER EROSION BARRIER (FOOT)
I-255			
1243+42	LT	1	
1243+92	RT	1	
1245+41	LT	1	
1245+91	RT	1	
1249+00	RT	1	
1249+02	LT	1	
1253+00	MED	1	
1255+01	LT	1	
1260+50	RT	1	
1283+00	MED	1	
1290+83	LT	1	
1291+36	RT	1	
1294+31	LT	1	
1294+84	RT	1	
1296+50	MED	1	
1301+00	MED	1	
1301+71	LT	1	
1302+88	RT	1	
1305+77	LT	1	
1307+88	RT	1	
1309+00	MED	1	
1311+00	RT	1	
1352+08	LT	1	
1352+98	RT	1	
1354+38	RT	1	
1354+68	RT	1	
1354+86	LT	1	
1355+16	LT	1	
1360+04	RT	1	
1360+36	RT	1	
1360+53	LT	1	
1360+82	LT	1	
1381+10	MED	1	
I-255 SB			6386.00
I-255 NB			5988.75
COLLINSVILLE RD RAMP 7			
101+87	RT	1	
105+00	RT	1	
111+50	RT	1	
I-55 ROADWAY B			
816+12	LT	1	
817+18	RT	1	
I-55 ROADWAY B			752.75
I-55 RAMP 1			
I-55 RAMP 1			965.25
HORSESHOE RAMP 2			
8+49	RT	1	
11+47	RT	1	
HORSESHOE RAMP 3			
5+95	RT	1	
BLACK LANE			2325.00
SUBTOTAL		41	16417.75
TOTAL		41	16418

NOTE; PERIMETER EROSION BARRIER TO BE PLACED AT LOCATIONS AS DIRECTED BY THE ENGINEER.