

PATCHING SCHEDULE

LOCATION					CLASS A PATCHES, TYPE II, 10 INCH	CLASS A PATCHES, TYPE III, 10 INCH	CLASS A PATCHES, TYPE IV, 10 INCH	CLASS B PATCHES, TYPE II, 8 INCH	CLASS B PATCHES, TYPE II, 10 INCH	CLASS B PATCHES, TYPE III, 10 INCH	CLASS B PATCHES, TYPE II, 13 INCH	CLASS B PATCHES, TYPE III, 13 INCH	CLASS B PATCHES, TYPE IV, 13 INCH	PATCHING REINFORCEMENT	PAVEMENT FABRIC	SAW CUTS	TIE BARS 3/4"	DOWEL BARS 1 1/2"
STATION	ROADWAY	LANE	LENGTH (FT)	WIDTH (FT)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(FT)	(EACH)	(EACH)
153+20	I-55/70 RAMP 1	1	6	12								8.0				49		20
153+20	I-55/70 RAMP 1	2	6	12								8.0				49		20
153+75	I-55/70 RAMP 1	1	6	12								8.0				49		20
153+75	I-55/70 RAMP 1	2	6	12								8.0				49		20
160+75	I-55/70 RAMP 1	1	6	12								8.0				49		20
160+75	I-55/70 RAMP 1	2	6	12								8.0				49		20
187+15	I-55/70 RAMP 2	N/A	10	16									17.8			69		28
196+25	I-55/70 RAMP 2	N/A	30	8										26.7		85	15	12
199+50	I-55/70 RAMP 2	N/A	6	8								5.3				37		12
200+60	I-55/70 RAMP 2	N/A	6	8								5.3				37		12
200+80	I-55/70 RAMP 2	N/A	6	8								5.3				37		12
203+80	I-55/70 RAMP 2	N/A	6	16								10.7				61		28
204+50	I-55/70 RAMP 2	N/A	6	16								10.7				61		28
4+14	HORSESHOE LAKE RD RAMP 2	N/A	6	16				10.7								61		28
5+50	HORSESHOE LAKE RD RAMP 2	N/A	6	16				10.7								61		28
11+10	HORSESHOE LAKE RD RAMP 2	N/A	6	16				10.7								61		28
11+60	HORSESHOE LAKE RD RAMP 2	N/A	6	16				10.7								61		28
3+50	HORSESHOE LAKE RD RAMP 3	N/A	6	16				10.7								61		28
6+15	HORSESHOE LAKE RD RAMP 3	N/A	6	16				10.7								61		28
6+87	HORSESHOE LAKE RD RAMP 3	N/A	6	16				10.7								61		28
8+65	HORSESHOE LAKE RD RAMP 3	N/A	6	16				10.7								61		28
10+10	HORSESHOE LAKE RD RAMP 3	N/A	6	16				10.7								61		28
6+55	HORSESHOE LAKE RD RAMP 4	N/A	6	16				10.7								61		28
8+00	HORSESHOE LAKE RD RAMP 4	N/A	6	16				10.7								61		28
SUBTOTAL THIS SHEET					0	0	0	117.7	0	0	85.3	17.8	26.7	0	44.5	1352	15	560
SUBTOTAL FROM SHEET 1					351.1	65.8	986.7	0	286.0	16	0	0	0	1403.6	16.0	6636	445	760
SUBTOTAL ALL SHEETS					351.1	65.8	986.7	117.7	286.0	16.0	85.3	17.8	26.7	1403.6	60.5	7988	460	1320
12% ANTICIPATED FAILURES					42.1	7.9	118.4	14.1	34.3	1.9	10.2	2.1	3.2	168.4	7.3	959	55	158
PAY TOTAL					393	74	1105	132	320	18	96	20	30	1572	68	8947	515	1478

PATCHING (SPECIAL) SCHEDULE

LOCATION					CLASS A PATCHES, TYPE II, 10 INCH (SPECIAL)
STATION	ROADWAY	LANE	LENGTH (FT)	WIDTH (FT)	(SQ YD)
1247+02	NB I-255	2	12	6	8
1247+02	NB I-255	3	12	6	8
1290+06	NB I-255	1	12	6	8
1290+06	NB I-255	2	12	6	8
1290+06	NB I-255	3	12	6	8
1308+37	NB I-255	1	12	6	8
1308+37	NB I-255	2	12	6	8
1308+37	NB I-255	3	12	6	8
1353+40	NB I-255	1	12	6	8
1353+40	NB I-255	2	12	6	8
1353+40	NB I-255	3	12	6	8
1353+40	NB I-255	4	12	6	8
1363+18	NB I-255	1	12	6	8
1363+18	NB I-255	2	12	6	8
1363+18	NB I-255	3	12	6	8
1363+18	NB I-255	4	12	6	8
1246+72	SB I-255	1	12	6	8
1246+72	SB I-255	2	12	6	8
1246+72	SB I-255	3	12	6	8
1246+72	SB I-255	4	12	6	8
1289+75	SB I-255	1	12	6	8
1289+75	SB I-255	2	12	6	8
1289+75	SB I-255	3	12	6	8
1307+32	SB I-255	1	12	6	8
1307+32	SB I-255	2	12	6	8
1307+32	SB I-255	3	12	6	8
1353+89	SB I-255	1	12	6	8
1353+89	SB I-255	2	12	6	8
1353+89	SB I-255	3	12	6	8
1353+89	SB I-255	4	12	6	8
1361+82	SB I-255	1	12	6	8
1361+82	SB I-255	2	12	6	8
1631+82	SB I-255	3	12	6	8
1247+02	SB I-255	1	12	6	8
TOTAL					272

PARTIAL DEPTH PATCHING SCHEDULE

LOCATION		PARTIAL DEPTH REMOVAL 3"	PARTIAL DEPTH PATCHING
STATION TO STATION	ROADWAY	(SQ YD)	(TON)
STA 1242+13.00 TO STA 1390+80.00	I-255 SB	17244	2897
STA 1242+45.00 TO STA 1390+80.00	I-255 NB	16331	2744
STA 100+00.00 TO STA 112+01.51	COLLINSVILLE RD RAMP 7	585	98
STA 102+30.00 TO STA 160+94.00	I-55 RAMP 1	4011	674
STA 200+00.00 TO STA 225+13.00	I-55 RAMP 2	1117	188
STA 300+00.00 TO STA 315+54.92	I-55 RAMP 3	676	114
STA 400+00.00 TO STA 414+16.24	I-55 RAMP 4	629	106
STA 500+00.00 TO STA 517+32.00	I-55 RAMP 5	785	132
STA 600+00.00 TO STA 617+75.00	I-55 RAMP 6	804	135
STA 700+00.00 TO STA 736+19.00	I-55 ROADWAY A	2413	405
STA 801+89.00 TO STA 867+04.06	I-55 ROADWAY B	4628	778
STA 4+07.14 TO STA 21+43.00	HORSESHOE RAMP 1	771	130
STA 1+54.00 TO STA 13+97.54	HORSESHOE RAMP 2	561	94
STA 3+14.84 TO STA 22+82.00	HORSESHOE RAMP 3	886	149
STA 1+39.00 TO STA 24+90.71	HORSESHOE RAMP 4	1045	176
TOTAL		52486	8820

NOTE: AREAS OF PARTIAL DEPTH PATCHING ARE ESTIMATED BASED ON 25% OF TOTAL SURFACE AREA AT LOCATIONS AS DIRECTED BY THE ENGINEER.

SHOULDER REMOVAL AND REPLACEMENT SCHEDULE

LOCATION					HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL)
STATION	LT/RT	ROADWAY	LENGTH (FT)	WIDTH (FT)	(SQ YD)
MAINLINE					
1265+78	RT	NORTHBOUND	22	10	24.4
1266+19	RT	NORTHBOUND	32	10	35.6
1266+71	RT	NORTHBOUND	34	10	37.8
1267+48	RT	NORTHBOUND	104	10	115.6
1269+59	RT	NORTHBOUND	116	10	128.9
1270+72	RT	NORTHBOUND	25	10	27.8
1319+77	RT	NORTHBOUND	29	10	32.2
1322+28	RT	NORTHBOUND	64	10	71.1
1323+90	RT	NORTHBOUND	58	10	64.4
1327+52	RT	NORTHBOUND	17	10	18.9
1328+91	RT	NORTHBOUND	14	10	15.6
1336+15	LT	NORTHBOUND	38	10	42.2
1336+65	RT	NORTHBOUND	19	10	21.1
1338+27	RT	NORTHBOUND	48	10	53.3
1340+06	RT	NORTHBOUND	69	10	76.7
1341+63	RT	NORTHBOUND	54	10	60.0
1343+50	RT	NORTHBOUND	67	10	74.4
1345+11	RT	NORTHBOUND	48	10	53.3
1346+27	RT	NORTHBOUND	46	10	51.1
1347+04	RT	NORTHBOUND	24	10	26.7
1348+74	RT	NORTHBOUND	46	10	51.1
1264+25	LT	SOUTHBOUND	148	10	164.4
1267+67	LT	SOUTHBOUND	155	10	172.2
1369+36	LT	SOUTHBOUND	122	10	135.6
1283+82	RT	SOUTHBOUND	42	10	46.7
1329+94	RT	SOUTHBOUND	93	10	103.3
1330+85	LT	SOUTHBOUND	66	10	73.3
1332+25	RT	SOUTHBOUND	15	10	16.7
1332+68	LT	SOUTHBOUND	31	10	34.4
1334+63	RT	SOUTHBOUND	41	10	45.6
1335+64	RT	SOUTHBOUND	86	10	95.6
1335+97	LT	SOUTHBOUND	14	10	15.6
1336+49	LT	SOUTHBOUND	31	10	34.4
1337+92	RT	SOUTHBOUND	16	10	17.8
1341+75	LT	SOUTHBOUND	63	10	70.0
1343+04	RT	SOUTHBOUND	56	10	62.2
1343+24	LT	SOUTHBOUND	16	10	17.8
1344+69	RT	SOUTHBOUND	21	10	23.3
1345+12	LT	SOUTHBOUND	21	10	23.3
1347+25	LT	SOUTHBOUND	26	10	28.9
MISC. ROADWAY					
863+10	RT	I-55/70 ROADWAY B	10	10	11.1
865+40	RT	I-55/70 ROADWAY B	10	10	11.1
867+00	RT	I-55/70 ROADWAY B	20	10	22.2
5+15	RT	HORSESHOE LAKE RD RAMP 3	40	10	44.4
SUBTOTAL					2652.1
PAY TOTAL					2652