

GUIDE SIGN SCHEDULE												
LOCATION	WIDTH	HEIGHT	SIZE		MESSAGE	REMOVE SIGN PANEL, TYPE 3	REMOVE GROUND MOUNTED SIGN SUPPORT	REMOVE CONCRETE FOUNDATION GROUND MOUNT	SIGN PANEL, TYPE 3	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	CONCRETE FOUNDATIONS	
			WIDTH	HEIGHT		SQ FT	EACH	EACH	SQ FT	POUNDS	CU YD	
RAMP 1												
18+00	204	84	17.'	7.'	COLL/GRAN	119	2	2	119	1672	4.18	
RAMP 3												
18+00	204	84	17.'	7.'	COLL/GRAN	119	2	2	119	1672	4.18	
RAMP 7												
343+50	186	192	15.5'	16.'	MPHS/CHI	248	2	2	248	1672	4.18	
ROADWAY B												
806+94	240	132	20.'	11.'	MEM	220			220			
	198	126	16.5'	10.5'	I270	173.25			173.25			
1242+62	SB	222	138	18.5'	11.5'	COLL	212.75		212.75			
1256+79	SB	186	138	15.5'	11.5'	COLL	178.25		178.25			
1268+00	NB	324	216	27.'	18.'	CHI/IND	301	3	486	5642	8.92	
1280+70	NB	246	132	20.5'	11.'	HLR	225.5		225.5			
		252	150	21.'	12.5'	STL	262.5		262.5			
		300	150	25.'	12.5'	CHI, IND	312.5		312.5			
1290+04	SB	414	132	34.5'	11.'	CHI, IND	379.5		379.5			
		300	150	25.'	12.5'	MEM	312.5		312.5			
1294+48	NB	288	120	24.'	10.'	STL	240		240			
1308+00	SB	324	210	27.'	17.5'	CHI, IND	311.75	3	472.5	7574	11.15	
1323+00	SB	414	132	34.5'	11.'	MEM	379.5		379.5			
		264	156	22.'	13.'	STL	286		286			
1341+00	SB	324	180	27.'	15.'	STL	275	4	405	5434	8.92	
1346+98	NB	246	102	20.5'	8.5'	HLR	174.25		174.25			
1359+76	NB	414	132	34.5'	11.'	I270	379.5		379.5			
		288	102	24.'	8.5'	HLR	204		204			
1381+94	SB	198	180	16.5'	15.'	STL, IND	247.5		247.5			
		288	102	24.'	8.5'	HLR	204		204			
1394+97	SB	246	126	20.5'	10.5'	HLR	215.25	2	215.25	2508	6.27	
TOTALs						5980.5	18	21	6456.25	26174	47.8	