

PAVING SCHEDULE										
STATION			BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	HOT-MIX ASPHALT SHOULDERS	AGGREGATE WEDGE SHOULDER, TYPE B			
			TON	TON	TON	TON	TON			
EB	52+84	TO	53+62	0.11	0.50	47.9	16.99	5.16		
EB	53+62	TO	53+67				1.09			
EB	55+44	TO	55+49				16.33			
EB	55+49	TO	56+35	0.12	0.55	50.9	1.09	5.66		
WB	52+90	TO	53+65	0.14	0.63	58.4	1.09	4.98		
WB	53+65	TO	53+70				18.73			
WB	55+40	TO	55+45				1.04			
WB	55+45	TO	56+20	0.11	0.50	46.7	15.56	4.98		
TOTAL				0.5	3.0	204	72	21		

STAGING PAVING SCHEDULE								
STATION				HOT-MIX ASPHALT BASE COURSE 8 3/4"	PAVED SHOULDER REMOVAL			
				SQ YD	SQ YD			
STAGE 1								
EB	53+00	TO	53+65	57.78	57.78			
WB	55+39	TO	56+00	47.44	47.44			
EB	55+44	TO	55+84	35.56	35.56			
STAGE 2								
EB	53+00	TO	53+67	44.67	44.67			
EB	55+45	TO	55+85	26.67	26.67			
TOTAL				212	212			

STAGING SCHEDULE						
STAGE	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	TEMPORARY PAVEMENT MARKING LINE - 6"	
	FOOT	FOOT	EACH	EACH	FOOT	
STAGE I	775		2		775	
STAGE II		762.5		2	762.5	
TOTAL	775	762.5	2	2	1537.5	

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT					
LOCATION	STATION TO	STATION	SURFACE		
			SQ YD		
EAST BOUND WEST END	52+84.00	TO 53+25.00	173.1		
EAST BOUND EAST END	55+94.00	TO 56+35.00	173.1		
WEST BOUND WEST END	52+90.00	TO 53+30.00	222.2		
WEST BOUND EAST END	55+80.00	TO 56+20.00	177.8		
SUB-TOTAL			746.2		
TOTAL			747		

PAVEMENT MARKING SCHEDULE																
		THERMOPLASTIC PAVEMENT MARKING			TEMPORARY PAVEMENT MARKING			WORK ZONE	RAISED REFLECTIVE PAVEMENT	RAISED REFLECTIVE PAVEMENT MARKER	SHORT TERM PAVEMENT MARKING	GUARDRAIL MARKERS TYPE A	GUARDRAIL MARKERS TYPE C			
		EDGE LINE SOLID 4" WHITE	EDGE LINE SOLID 4" YELLOW	CENTERLINE SKIP-DASH 4" WHITE	EDGE LINE SOLID 4" WHITE	EDGE LINE SOLID 4" YELLOW	CENTERLINE SKIP-DASH 4" WHITE	PAVEMENT MARKING REMOVAL	SO FT	EACH	EACH	FOOT	EACH	EACH		
EB																
STA	35+78	TO	STA	55+44	1966.0	1966.0	491.5	1966.00	1966.00	491.50	1654.5	10	10	540	6	6
WB																
STA	53+70	TO	STA	73+38	1968.0	1968.0	492.0	1968.00	1968.00	492.00	1656	10	10	540	6	6
SUB-TOTAL					3934.0	3934.0	983.5	3934.0	3934.0	983.5	3310.5	20	20	1080	12	12
GRAND TOTAL					8,852			8,852			3311	20	20	1080	12	12

NOTE: GUARDRAIL MARKERS TYPE A AND TYPE C ARE TO BE INSTALLED ON THE PARAPET WALLS OF THE STRUCTURES.

TEMPORARY RAMP SCHEDULE				
LOCATION	WIDTH FOOT	LENGTH FOOT	TEMPORARY RAMP SQ YD	
EAST BOUND STAGE 1 WEST END OF STRUCTURE				
STA	52+84	18.583	5	11
STA	53+62	18.583	8	17
STA	53+70	18.583	8	17
EAST BOUND STAGE 1 EAST END OF STRUCTURE				
STA	55+41	18.583	8	17
STA	55+49	18.583	8	17
STA	56+35	18.583	5	11
EAST BOUND STAGE 2 WEST END OF STRUCTURE				
STA	52+84	14.083	5	8
STA	53+62	14.083	8	13
STA	53+70	14.083	8	13
EAST BOUND STAGE 2 EAST END OF STRUCTURE				
STA	55+41	14.083	8	13
STA	55+49	14.083	8	13
STA	56+35	14.083	5	8
WEST BOUND STAGE 1 WEST END OF STRUCTURE				
STA	52+90	24.771	5	14
STA	53+65	24.771	8	23
STA	53+73	24.771	8	23
WEST BOUND STAGE 1 EAST END OF STRUCTURE				
STA	55+37	16.771	8	15
STA	55+45	16.771	8	15
STA	55+20	16.771	5	10
WEST BOUND STAGE 2 WEST END OF STRUCTURE				
STA	52+90	14.792	5	9
STA	53+65	14.792	8	14
STA	53+73	14.792	8	14
WEST BOUND STAGE 2 EAST END OF STRUCTURE				
STA	55+37	14.792	8	14
STA	55+45	14.792	8	14
STA	55+20	14.792	5	9
TOTAL				332

1 REVISED SHEET 1-4-13

FILE NAME *	USER NAME * #USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			789	125-1HG-1	MADISON	29	7	
		CHECKED -	REVISED -			SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA.		CONTRACT NO. 76F54			
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					