

SUMMARY OF QUANTITIES

100% STATE

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004	0014	0014
50300300	PROTECTIVE COAT	SQ YD	394		202	192
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4500		2430	2070
50800515	BAR SPLICERS	EACH	88		44	44
52000110	PREFORMED JOINT STRIP SEAL	FOOT	180		94	86
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	1525		784	741
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	149		149	
67100100	MOBILIZATION	L SUM	1	0.34	0.33	0.33
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	0.34	0.33	0.33
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1		
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	2		1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1		1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1080	1080		

12

FILE NAME =	USER NAME = challendeske	DESIGNED -	REVISED -
ci:\pwork\puidot\challengeske\d8292482	0876F54-sh1-500.dgn	DRAWN -	REVISED -
	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -
	PLOT DATE = 11/2/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE	SHEET 2 OF 3 SHEETS	STA.	TO STA.	F.A.P. RTE. 789	SECTION 128-IHB-I	COUNTY MADISON	TOTAL SHEETS 29	SHEET NO. 4	
CONTRACT NO. 76F54								ILLINOIS FED. AID PROJECT	