

PAVING SCHEDULE									
STATION				BITUMINOUS	AGGREGATE	HOT-MIX ASPHALT	HOT-MIX	AGGREGATE	
				MATERIALS	MATERIALS	SURFACE COURSE,	ASPHALT	WEDGE SHOULDER,	
				(PRIME COAT)	(PRIME COAT)	MIX "C", N70	SHOULDERS	TYPE B	
				TON	TON	TON	TON	TON	
EB	52+84	TO	53+62	0.11	0.50	47.9	16.99	5.16	
EB	53+62	TO	53+67				1.09		
EB	55+44	TO	55+49				16.33		
EB	55+49	TO	56+35	0.12	0.55	50.9	1.09	5.66	
WB	52+90	TO	53+65	0.14	0.63	58.4	1.09	4.98	
WB	53+65	TO	53+70				18.73		
WB	55+40	TO	55+45				1.04		
WB	55+45	TO	56+20	0.11	0.50	46.7	15.56	4.98	
TOTAL				0.5	3.0	204	72	21	

STAGING PAVING SCHEDULE						
STATION				HOT-MIX	PAVED	
				ASPHALTY BASE	SHOULDER	
				COURSE 8 3/4"	REMOVAL	
				SQ YD	SQ YD	
STAGE 1						
EB	53+00	TO	53+65	57.78	57.78	
WB	55+39	TO	56+00	47.44	47.44	
EB	55+44	TO	55+84	35.56	35.56	
STAGE 2						
EB	53+00	TO	53+67	44.67	44.67	
EB	55+45	TO	55+85	26.67	26.67	
TOTAL				212	212	

STAGING SCHEDULE					
STAGE	TEMPORARY	RELOCATE	IMPACT ATTENUATORS	IMPACT ATTENUATORS	TEMPORARY
	CONCRETE	CONCRETE	TEMPORARY	RELOCATE	PAVEMENT
	BARRIER	BARRIER	(NON-REDIRECTIVE),	(NON-REDIRECTIVE),	MARKING
	FOOT	FOOT	TEST LEVEL 3	TEST LEVEL 3	LINE - 6"
	FOOT	FOOT	EACH	EACH	FOOT
STAGE I	775		2		775
STAGE II		762.5		2	562.5
TOTAL	775	762.5	2	2	1337.5

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT					
LOCATION	STATION TO STATION			SURFACE	
				SQ YD	
EAST BOUND WEST END	52+84.00	TO	53+25.00	173.1	
EAST BOUND EAST END	55+94.00	TO	56+35.00	173.1	
WEST BOUND WEST END	52+90.00	TO	53+30.00	222.2	
WEST BOUND EAST END	55+80.00	TO	56+20.00	177.8	
SUB-TOTAL -				746.2	
TOTAL -				747	

PAVEMENT MARKING SCHEDULE																
STATION				THERMOPLASTIC PAVEMENT MARKING			TEMPORARY PAVEMENT MARKING			WORK ZONE	RAISED	RAISED	SHORT	GUARDRAIL	GUARDRAIL	
				EDGE LINE	EDGE LINE	CENTERLINE	EDGE LINE	EDGE LINE	CENTERLINE	PAVEMENT	REFLECTIVE	REFLECTIVE	TERM	MARKERS	MARKERS	
				SOLID	SOLID	SKIP-DASH	SOLID	SOLID	SKIP-DASH	MARKING	PAVEMENT	PAVEMENT	PAVEMENT	TYPE A	TYPE C	
				4" WHITE	4" YELLOW	4" WHITE	4" WHITE	4" YELLOW	4" WHITE	REMOVAL	MARKER	MARKER	MARKING			
				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH	FOOT	EACH	EACH	
EB																
STA	35+78	TO	STA	55+44	1966.0	1966.0	491.5	1966.00	1966.00	491.50	368.6	25	25	540	6	6
WB																
STA	53+70	TO	STA	73+38	1968.0	1968.0	492.0	1968.00	1968.00	492.00	369.0	25	25	540	6	6
SUB-TOTAL					3934.0	3934.0	983.5	3934.0	3934.0	983.5	737.6	50	50	1080	12	12
GRAND TOTAL					8,852			8,852			738	50	50	1080	12	12

NOTE: GUARDRAIL MARKERS TYPE A AND TYPE C ARE TO BE INSTALLED ON THE PARAPET WALLS OF THE STRUCTURES.

TEMPORARY RAMP SCHEDULE				
LOCATION	WIDTH	LENGTH	TEMPORARY	
			FOOT	RAMP
	FOOT	FOOT	SQ YD	
EAST BOUND STAGE 1 WEST END OF STRUCTURE				
STA	52+84	18.583	5	11
STA	53+62	18.583	8	17
STA	53+70	18.583	8	17
EAST BOUND STAGE 1 EAST END OF STRUCTURE				
STA	55+41	18.583	8	17
STA	55+49	18.583	8	17
STA	56+35	18.583	5	11
EAST BOUND STAGE 2 WEST END OF STRUCTURE				
STA	52+84	14.083	5	8
STA	53+62	14.083	8	13
STA	53+70	14.083	8	13
EAST BOUND STAGE 2 EAST END OF STRUCTURE				
STA	55+41	14.083	8	13
STA	55+49	14.083	8	13
STA	56+35	14.083	5	8
WEST BOUND STAGE 1 WEST END OF STRUCTURE				
STA	52+90	24.771	5	14
STA	53+65	24.771	8	23
STA	53+73	24.771	8	23
WEST BOUND STAGE 1 EAST END OF STRUCTURE				
STA	55+37	16.771	8	15
STA	55+45	16.771	8	15
STA	55+20	16.771	5	10
WEST BOUND STAGE 2 WEST END OF STRUCTURE				
STA	52+90	14.792	5	9
STA	53+65	14.792	8	14
STA	53+73	14.792	8	14
WEST BOUND STAGE 2 EAST END OF STRUCTURE				
STA	55+37	14.792	8	14
STA	55+45	14.792	8	14
STA	55+20	14.792	5	9
TOTAL				332