1-18-13 LETTING ITEM 054

FOR INDEX OF SHEETS, SEE SHEET NO. 2

STATE OF ILLINOIS

**DEPARTMENT OF TRANSPORTATION** 

**DIVISION OF HIGHWAYS** 

**PROPOSED** HIGHWAY PLANS

**FAP ROUTE 789 (IL 143)** SECTION 125-1HB-I **BRIDGE REHABILITATION MADISON COUNTY** 

C-98-047-12

PROJECT LOCATION SN 060-0191 & 060-0192 STA, 54 + 60,95 LAT: 38.8333 LONG: -89.9932

LOCATION OF SECTION INDICATED THUS: -

125-148-1

D-98-041-12

ILLINOIS CONTRACT NO. 76F54

STATE OF ILLINOIS

PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

ENGINEERING SCALES, REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES, IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123

PROJECT ENGINEER: PATTI LeBEAU (618)346-3179 PROJECT MANAGER: REBECCA THARP (618)346-3323

CONTRACT NO. 76F54



N/A

2011 = 9150 (ACTUAL) 2032 = 11,300 (ESTIMATED)

SU = 2.2% MU = 1.0%

GROSS LENGTH = 180 FT. = 0.0341 MILE

NET LENGTH = 180 FT. = 0.0341 MILE

#### GENERAL NOTES

- 1 ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
  - AT&T ILLINOIS
  - . BUCKEYE PARTNERS L.P. -- WOOD RIVER PIPELINE
  - . CHARTER COMMUNICATIONS, INC.
  - . NORTHEAST CENTRAL COUNTY PUBLIC WATER DISTRICT
  - . SOUTHWESTERN ELECTRIC COOPERATIVE, INC.

MEMBERS OF J.U.L.I.E. (800-892-0123 OR 811) AND ARE INDICATED BY AN . NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

- 2 THE CONTRACTOR AND THE ENGINEER SHALL BE AWARE THAT NO SURVEY WAS PERFORMED FOR THIS PROJECT.
  THE STATIONING AND TOPOGRAPHY SHOWN IN THE PLANS WAS CREATED USING MICROFILM AND FIELD MEASUREMENTS.
  BOTH SHALL BE ASSUMED TO BE APPROXIMATE. THE CONTRACTOR SHALL VERIFY DIMENSIONS AND CONDITIONS IN THE
  FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- 3 A QUANTITY OF 1537.5 FOOT OF "TEMPORARY PAVEMENT MARKING LINE 6" HAS BEEN INCLUDED IN THE PLANS FOR PAINTING THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER.
- 4 THE PROPOSED PAVEMENT MARKING SHALL MATCH THE LOCATIONS OF THE EXISTING PAVEMENT MARKING, AS DIRECTED BY THE ENGINEER.
- 5 ACCESS SHALL BE MAINTAINED TO ALL PROPERTIES UNLESS OTHERWISE NOTED IN THE PLANS.
- 6 ALL TURF AREAS DISTURBED BY THE CONTRACTOR SHALL BE SEEDED WITH THE APPROPRIATE EROSION CONTROL AS DIRECTED BY THE ENGINEER AT THE CONTRACTOR'S EXPENSE.
- 7 THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS CONTRACT.

MIXTURE USE	WIDENING	SURFACE
AC/PG	PG 64-22	PG 64-22
RAP % (MAX)	SEE SPEC.	SEE SPEC.
DESIGN AIR VOIDS	4.0% @ Ndes=70	4.0% @ Ndes=70
MIX COMPOSITION		
(GRADATION MIXTURE)	IL 19.0	IL 9.5
FRICTION AGG	MIXTURE "B"	MIXTURE "C"

\*\*TOP LIFT SHOULDERS - DESIGN THIS MIX AT 2.0% VOIDS AND ADD ASPHALT TO REDUCE VOIDS TO 1.5%.

PLAN QUANTITIES FOR BITUMINOUS CONCRETE SURFACE COURSE ITEMS ARE CALCULATED USING A UNIT WEIGHT OF 112 lb/sq yd/in (59.8kg/sq m/25mm THICKNESS)

8 THE DEPARTMENT STRONGLY ENCOURAGES THE PRIME CONTRACTOR AND THEIR APPROVED SUB-CONTRACTORS
TO HIRE MINORITY, WOMEN AND DISADVANTAGED INDIVIDUALS FROM ITS FEDERALLY FUNDED HIGHWAY CONSTRUCTION
CAREERS TRAINING PROGRAM (HCCTP) TO HELP MEET WORKFORCE AND TRAINEE GOALS, THIS PROGRAM IS TRAINING
MINORITIES, WOMEN AND DISADVANTAGED INDIVIDUALS IN HIGHWAY CONSTRUCTION-RELATED SKILLS, E.G., MATH FOR
THE TRADES, JOB READINESS, TECHNICAL SKILLS COURSEWORK (CARPENTRY, CONCRETE FLATWORK, BLUEPRINT READING,
SITE PLANS, SITE WORK, TOOLS USE, ETC.) AND OSHA 10 HOUR CERTIFICATION, TO PREPARE THEM FOR A CAREER IN THE
HIGHWAY CONSTRUCTION TRADES. GRADUATES ARE WELL-TRAINED AND READY TO BECOME PRODUCTIVE ENTRY-LEVEL
CONSTRUCTION WORKERS. CONTACT THE DISTRICT 8 EEO OFFICE AT 618-346-3360 AND/OR THE HCCTP COORDINATOR AT
618-874-6528 TO LEARN MORE ABOUT THE PROGRAM AND FOR ASSISTANCE IN MEETING WORKFORCE AND TRAINEE GOALS.

#### INDEX OF SHEETS

	CTANDADDC AND	COLBITT	ACSITO
2	GENERAL NOTES.	INDEX	OF SHEETS
1	COVER SHEET		

3-6 SUMMARY OF QUANTITIES

SCHEDULES

8-9 TYPICAL SECTIONS

10 PRE-STAGE 1 WIDENING 11 PRE-STAGE 2 WIDENING

12 TRAFFIC CONTROL DETAILS

13 DETAILS

14-29 STRUCTURE PLANS

COMMITMENTS

NONE

STANDARDS

000001-06 001001-02 001006 635006-03 635011-02 701101-03 701411-08 701421-05 701422-05 701423-06 701426-05 701456-02 701901-03 704001-07 780001-03 781001-03

FILE NAME :	USER NAME : challandeske	DESIGNED -	REVISED ~
c:\pw_work\px;dot\challandaska\d8292482	0076F54-sht-gennote.dgn	DRAWN -	REVISEO -
	PLOT SCALE # 100,8000 1/ 10.	CHECKED -	REVISED -
	PLOT DAYE . 11/2/2012	DATE -	REVISEO -

STATE	0F	ILLINOIS	
DEPARTMENT (	)F 1	RANSPORTATION	

	GEN	ERAL	NOT	ES, IN	DEX	OF	SHEETS,		
	STA	NDAF	RDS	AND	CON	MIT	MENTS		
SCALE: NONE	SHEET 1	0	F 1	SHE	ETS	STA.		TO	ST

······································		<del></del>	<u> </u>	100% STATE  CONSTRUCTION TYPE CODE					
	SUMMARY OF QUANTITIES		TOTAL	00 <b>0</b> 4	0014	0014			
CODE NO	Nati	UNIT	QUANTITIES						
·									
35501319	HOT-MIX ASPHALT BASE COURSE, 8 3/4"	SQ YD	212	212					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5	0.5	-				
					-				
40600300	AGGREGATE (PRIME COAT)	TON	3	3					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT	SQ YD	747	747					
	JOINT				· · · · · · · · · · · · · · · · · · ·				
····									
40600990	TEMPORARY RAMP	SQ YD	332	332					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0,	TON	91	91					
	N70								
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX	TON	369	204	85	80			
	"C", N70			·					
44004250	PAVED SHOULDER REMOVAL	SQ YD	212	212					
						,			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	21	21					
48203100	HOT-MIX ASPHALT SHOULDERS	TON	72	72					
E0103400	CONCOCTE DEMOVAL	01: VB			72.0				
30102400	CONCRETE REMOVAL	CU YD	62.3		33.9	28.			
50157300	PROTECTIVE SHIELD	SQ YD	785		411	374			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	67.9		39.1	28.			

DESIGNED -

CHECKED -

USER NAME \* chollondoske 0876F54-sht-S00.dgn PLOT SCALE \* 180.8868 '/ in.

PLDT DATE \* 11/2/2012

REVISED -

REVISED -REVISED -

REVISED -

CTATE OF ULINOIS		SI	JMMARY	OF QUAN	ITITIES		F.A.P RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION							789	125-1H8-I	MADISON CONTRACT	29 NO.	3 76F54
	SCALE: NONE	SHEET 1	0F 3	SHEETS S	TA,	TO STA.		ILLENOIS FEO. A			

FILE NAME =

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

<del></del>		·		100	STATE	CODE
	SUMMARY OF QUANTITIES		URBAN TOTAL	0004	0014	0014
CODE NO	ITEM	UNIT	QUANTITIES	-		
		·				
50300300	PROTECTIVE COAT	SQ YD	394		202	192
	· ·					-
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4500		2430	2070
50800515	BAR SPLICERS	EACH	88		44	44
			The state of the s			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	180		94	86
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	1525		784	741
				-		
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	149		149	
					-	
67100100	MOBILIZATION	L SUM	1	0.34	0.33	0.3
			The state of the s			
70100310	TRAFFIC CONTROL AND PROTECTION,	L SUM	1	0.34	0.33	0.3
	STANDARD 701421					
70100320	TRAFFIC CONTROL AND PROTECTION.	L SUM	1	1		
	STANDARD 701422					
70100325	TRAFFIC CONTROL AND PROTECTION,	EACH	2		1	1
	STANDARD 701423					
70100420	TRAFFIC CONTROL AND PROTECTION,	EACH	ų.,			
	STANDARD 701411					
			***************************************		The same same	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1080	1080		
					-	

REVISED -REVISED -

REVISED -

DESIGNED -

CHECKED -

USER NAME = challondeske

108292482 0876F54-9ht-500.dgn PLOT SCALE = 188.8888 '/ In. PLOT DATE + 11/2/2812

SUMMARY OF QUANTITIES						F.A.P RTE.	SECTION	COUNTY	TOTAL	SHEET NO.		
								789	128-1H8-I	MADISON	29	4
	γ									CONTRACT	NO.	76F54
SCALE: NONE	SHEET	2	ĢF	3	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				

FILE NAME :

TOTAL	TOTAL OUNTT TOTAL OUNTT OUNTT OUNTT OUNTT OUNTT STALL OOO4 OO14 OO14 OO14 OO14 OO14 OO14 OO		CLIMANADY OF OLIANITITICS	<del> </del>	URBAN	CONSTRUCTION TYPE CODE					
70300220 TEMPORARY PAVEMENT MARKING - LINE 4" FOOT 8852 8852  70300240 TEMPORARY PAVEMENT MARKING - LINE 6" FOOT 1537.5 1537.5  70301000 WORK ZONE PAVEMENT MARKING REMOVAL SO FT 3071 3071  70400100 TEMPORARY CONCRETE BARRIER FOOT 775 775  70400200 RELOCATE TEMPORARY CONCRETE BARRIER FOOT 762.5 762.5  70600250 IMPACT ATTENUATORS. TEMPORARY (NON- EACH 2 1 1 REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS. RELOCATE (NON- EACH 2 1 1 REDIRECTIVE), TEST LEVEL 3  78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS. TYPE A EACH 12 6	T0300220 TEMPORARY PAVEMENT MARKING - LINE 4" FOOT 8852 8852  70300240 TEMPORARY PAVEMENT MARKING - LINE 6" FOOT 1537.5 1537.5  70301000 WORK ZONE PAVEMENT MARKING REMOVAL S0 FT 3071 3071  70400100 TEMPORARY CONCRETE BARRIER FOOT 775 775  70400200 RELOCATE TEMPORARY CONCRETE BARRIER FOOT 762.5 762.5  70600250 IMPACT ATTENUATORS, TEMPORARY (NON- EACH 2 1 1 REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON- EACH 2 1 1 REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON- EACH 2 1 1 REDIRECTIVE), TEST LEVEL 3  70600350 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  705000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  705000200 GUARDRAIL MARKERS, TYPE A EACH 10 10 10 10 10 10 10 10 10 10 10 10 10	CODE NO	SUMMARY OF QUANTITIES		TOTAL	0004	0014	0014			
TOGO0220 TEMPORARY PAVEMENT MARKING - LINE 4" FOOT 8852 8852  TOGO0240 TEMPORARY PAVEMENT MARKING - LINE 6" FOOT 1537.5 1537.5 1537.5 170301000 WORK ZONE PAVEMENT MARKING REMOVAL SQ FT 3071 3071 3071 70400100 TEMPORARY CONCRETE BARRIER FOOT 775 775 775 775 775 775 775 775 775 77	TOSO0220 TEMPORARY PAVEMENT MARKING - LINE 4" FOOT 8852 8852  TOSO0240 TEMPORARY PAVEMENT MARKING - LINE 6" FOOT 1537.5 1537.5 1537.5 170301000 WORK ZONE PAVEMENT MARKING REMOVAL SO FT 3071 3071 3071 70400100 TEMPORARY CONCRETE BARRIER FOOT 775 775 775 775 775 775 775 775 775 77	CODE NO	11 Cm	Olari	UDATTILIS		<del> </del>				
70301000 WORK ZONE PAVEMENT MARKING REMOVAL  70400100 TEMPORARY CONCRETE BARRIER  70400200 RELOCATE TEMPORARY CONCRETE BARRIER  70600250 IMPACT ATTENUATORS, TEMPORARY (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATT	70301000 WORK ZONE PAVEMENT MARKING REMOVAL  70400100 TEMPORARY CONCRETE BARRIER  70400200 RELOCATE TEMPORARY CONCRETE BARRIER  70400200 IMPACT ATTENUATORS, TEMPORARY (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  788000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER  FACH  10  10  178200410 GUARDRAIL MARKERS, TYPE A  FACH  12  6	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8852	8852					
70301000 WORK ZONE PAVEMENT MARKING REMOVAL  70400100 TEMPORARY CONCRETE BARRIER  70400200 RELOCATE TEMPORARY CONCRETE BARRIER  70600250 IMPACT ATTENUATORS, TEMPORARY (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATT	70301000 WORK ZONE PAVEMENT MARKING REMOVAL  70400100 TEMPORARY CONCRETE BARRIER  70400200 RELOCATE TEMPORARY CONCRETE BARRIER  70400200 IMPACT ATTENUATORS, TEMPORARY (NON-  REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON-  REDIRECTIVE), TEST LEVEL 3  788000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER  FACH  10  10  178200410 GUARDRAIL MARKERS, TYPE A  FACH  12  6										
70400100 TEMPORARY CONCRETE BARRIER FOOT 775 775  70400200 RELOCATE TEMPORARY CONCRETE BARRIER FOOT 762.5 762.5  70600250 IMPACT ATTENUATORS, TEMPORARY (NON- EACH 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	70400100 TEMPORARY CONCRETE BARRIER FOOT 775 775  70400200 RELOCATE TEMPORARY CONCRETE BARRIER FOOT 762.5 762.5  70600250 IMPACT ATTENUATORS, TEMPORARY (NON- EACH 2 1 76000350 IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3 1 76000350 IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3 8852 8852 78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852 78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10 10 78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6 10 10 10 10 10 10 10 10 10 10 10 10 10	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1537.5	1537.5					
70400200 RELOCATE TEMPORARY CONCRETE BARRIER FOOT 762.5 762.5  70600250 IMPACT ATTENUATORS, TEMPORARY (NON- EACH 2 1 1	70400200 RELOCATE TEMPORARY CONCRETE BARRIER FOOT 762.5 762.5  70600250 IMPACT ATTENUATORS, TEMPORARY (NON- EACH 2 1 7 7 7 8 8 8 9 9 9 9 9 9 9 9 9 9 9 9 9 9	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3071	3071					
70600250 IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3  78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6	TOGO0250 IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3  TOGO0350 IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3  TREDIRECTIVE), TEST LEVEL 3  TREDIRECTIVE 3  TREDIRECTIVE 3  TREDIRECTIVE 3  TREDIRECTIVE 3  TREDIRECTIVE 3  TREDIRECTIVE 3  TREDIRE	70400100	TEMPORARY CONCRETE BARRIER	FOOT	775	775		·			
70600250 IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3  78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER  78200410 GUARDRAIL MARKERS, TYPE A  EACH 12 6	TOGO0250 IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3  TOGO0350 IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3  TREDIRECTIVE), TEST LEVEL 3  TREDIRECTIVE 3  TREDIRECTIVE 3  TREDIRECTIVE 3  TREDIRECTIVE 3  TREDIRECTIVE 3  TREDIRECTIVE 3  TREDIRE	70400200	DELOCATE TEMPODADY COMEDETE DADDIED	COOT	702.5	702.5					
REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON- EACH 2 1  REDIRECTIVE), TEST LEVEL 3  78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6	REDIRECTIVE), TEST LEVEL 3  70600350 IMPACT ATTENUATORS, RELOCATE (NON- EACH 2 1 1 REDIRECTIVE), TEST LEVEL 3  78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6 6	10400200	RELOCATE TEMPORARY CONCRETE BARRIER	7001	162.5	162.3					
70600350 IMPACT ATTENUATORS, RELOCATE (NON- EACH 2 1 REDIRECTIVE), TEST LEVEL 3  78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6	70600350 IMPACT ATTENUATORS, RELOCATE (NON- EACH 2 1  REDIRECTIVE), TEST LEVEL 3  78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6  78200430 GUARDRAIL MARKERS, TYPE C EACH 12 6	70600250	IMPACT ATTENUATORS, TEMPORARY (NON-	EACH	2		1	1			
REDIRECTIVE), TEST LEVEL 3  78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6	REDIRECTIVE), TEST LEVEL 3  78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6	· · · · · · · · · · · · · · · · · · ·									
78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6	78000200 THERMOPLASTIC PAVEMENT MARKING - LINE <b>4"</b> FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6	70600350	IMPACT ATTENUATORS. RELOCATE (NON-	EACH	2		1	1			
78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6	78000200 THERMOPLASTIC PAVEMENT MARKING - LINE <b>4"</b> FOOT 8852 8852  78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6  78200430 GUARDRAIL MARKERS, TYPE C EACH 12 6		REDIRECTIVE). TEST LEVEL 3								
78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6	78100100 RAISED REFLECTIVE PAVEMENT MARKER EACH 10 10  78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6  78200430 GUARDRAIL MARKERS, TYPE C EACH 12 6	78000000	THEOLOGIA ACTTO CANGERDAT HADRIANG I TAIC A"	5007	0050	0050	-				
78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6	78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6 78200430 GUARDRAIL MARKERS, TYPE C EACH 12 6	18000200	THERMOFEASTIC PAVEMENT MARKING - CINE T	7001	2000	6652					
78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6	78200410 GUARDRAIL MARKERS, TYPE A EACH 12 6 78200430 GUARDRAIL MARKERS, TYPE C EACH 12 6										
	78200430 GUARDRAIL MARKERS, TYPE C EACH 12 6	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10					
78200430 GUARDRAIL MARKERS, TYPE C EACH 12 6		78200410	GUARDRAIL MARKERS, TYPE A	EACH	12		6	6			
	78300100 PAVEMENT MARKING REMOVAL SQ FT 2951 2951	78200430	GUARDRAIL MARKERS, TYPE C	EACH	12		6	6			
78300100 PAVEMENT MARKING REMOVAL SQ FT 2951 2951		78300100	PAVEMENT MARKING REMOVAL	SQ FT	2951	2951					

* SPECIALTY IT	EM
----------------	----

	. — . — — — , , , , , , , , , , , , , ,	; <b>7</b>		
FILE NAME 2	USER NAME = chollandoska	DESIGNED -	REVISED -	Ī
c:\pv.work\pvido\$\challandeske\d9292482	0876F54-#ht-\$09.dgn	DRAWN ~	REVISED -	i
	PLOT SCALE * 188.8888 1/ 10.	CHECKED -	REVISED ~	ĺ
	PLOT DATE • 11/2/2012	DATE ~	REVISED -	1

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

	SUMMARY	OF QUANTITIES		F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		•		789	125-1HB-[	MADISON	29	5
·····	·					CONTRACT	NO.	76F54
SCALE: NONE	SHEET 3 OF 3	SHEETS! STA.	TO STA.		ILLINOIS FED. AL	D PROJECT		

<del> </del>	010111011		URBAN	CON	STRUCTION TYPE	CODE
· · · · · · · · · · · · · · · · · · ·	SUMMARY OF QUANTITIES	T	TOTAL	0004	0014	0014
CODE NO	ITEM	UNIT	QUANTITIES			
78300200	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10		
	REMOVAL					
			A CONTRACTOR OF THE CONTRACTOR			
x5030530	FLOOR DRAIN EXTENSION	EACH	8	-	4	4
		The state of the s				<del></del>
X7010216	TRAFFIC CONTROL AND PROTECTION,	L SUM	. 1	1		
	(SPECIAL)			destroyer and the later of the		<del></del>
						<del></del>
Z0015802	PLUG EXISTING DECK DRAINS	EACH	15		7	8
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	52		44	8
				····		•
20016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	435		261	174
····						
						<del></del>
			,			
*				ya nakapatan		<del></del>
				<del></del>		
<del></del>						
the Control of the Co						<del></del>
					PERMANANTAN	
······································						
·		ļ				<del></del>

 FILE NAME =	USER NAME = challendaske	DESIGNED -	REVISED -	
 c:\px_work\pwidet\challandaska\d8292402	0878F54-sht=\$00,dgn	DRAWN -	REVISEO -	
	PLOT SCALE * 100.0000 1/ ja.	CHECKED -	REVISED -	
	PLOT DATE * 11/2/2012	DATE -	REVISED -	

STATI	E OF	ILLINOIS
DEPARTMENT	OF	TRANSPORTATION

<del></del>	·····	SI	IMM	ARY	OF QU	ANTITIE	s	F.A.P RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
								789	125-1HB-1	MADISON	29	6
,										CONTRACT	NO. 7	76F54
CALE: NONE	SHEET	3	OF	3	SHEETS	STA.	TO STA.		ILLINOIS FED. A	O PROJECT		

					PAVING SCHED	JLE	•	
				BITUMINOUS	AGGREGATE	HOT-MIX ASPHALT	HOT-MIX	AGGREGATE
				MATERIALS	MATERIALS	SURFACE COURSE,	ASPHALT	WEDGE SHOULDER.
	STAT	ION		(PRIME COAT)	(PRIME COAT)	MIX "C", N70	SHOULDERS	TYPE B
			1.	TON	TON	TON	TON	TON
EB	52+84	TO	53+62	0.11	0.50	47.9	16.99	5.16
£8	53+62	TO	53+67				1.09	
EB	55+44	TO	55+49				16,33	
E8	55+49	TO	56+35	0.12	0.55	50.9	1.09	5.66
WB	52+90	TO	53+65	0.14	0.63	58.4	1.09	4.98
WB.	53+65	TO	53+70				18.73	
WB	55+40	TO	55+45				1.04	
WB	55+45	TO	56+20	0.11	0.50	46.7	15.56	4.98
			TOTAL	0.5	3.0	204	72	21

				IG SCHEDULE	
			-	.HOT-MIX	PAVED
				ASPHALT BASE	SHOULDER
	STAT	ION		COURSE 8.3/4"	REMOVAL
STAG	E 1			SQ YD	SQ YD
E8	53+00	TO	53+65	57.78	57.78
WB	55+39	TO	56+00	47.44	47.44
EB	55+44	TO	55+84	35.56	35.56
STAG	E 2				-
E8	53+00	ТО	53+67	44.67	44.67
EB	55+45	TO	55+85	26.67	26.67
			TOTAL	212	212

		;	STAGING SCHEDULE		
		RELOCATE	IMPACT ATTENUATORS	IMPACT ATTENUATORS	TEMPORARY
	TEMPORARY	TEMPORARY	TEMPORARY	RELOCATE	PAVEMENT
	CONCRETE	CONCRETE	(NON-REDIRECTIVE).	(NON-REDIRECTIVE),	MARKING
STAGE	BARRIER	BARRIER	TEST LEVEL 3	TEST LEVEL 3	LINE - 6"
	FOOT	FOOT	- EACH	EACH	FOOT
STAGE I	775		2		775
STAGE II		762.5		2	562.5
TOTAL	775	762.5	2	2	1337.5

	HQ1'~	MIX AS	PHALT	SUR	FACE REMOV	AL ~	BUTT JOIN	1
	LO	CATION			STATION	TO S	MOITATE	SURFACE
								SQ YD
1	EAST	BOUND	WEST	END	52+84.00	TO	53+25.00	173.1
	EAST	BOUND	EAST	END	55+94.00	TO	56+35.00	173.1
1	WEST	DANDB	WEST	END	52+90.00	TO	53+30.00	222.2
1	WEST	80UN0	EAST	END	55+80.00	TO	56+20.00	177.8
						SUB	-TOTAL -	746.2
				Ī			TOTAL -	747

						•			PAVEMENT I	MARKING SCHEDL	ILE .					
					THERMOPL	ASTIC PAVEM	ENT MARKING	TEMPOR	ARY PAVEMEN	IT MARKING	WORK ZONE	RAISED	RAISED	SHORT	GUARDRAIL	GUARDRAIL
				ĺ	EDGE LINE	EDGE LINE	CENTERLINE	EDGE LINE	EDGE LINE	CENTERLINE	PAVEMENT	REFLECTIVE	REFLECTIVE	TERM	MARKERS	MARKERS
					SOLID	SOLID	SKIP-DASH	SOLIO	SOLID	SKIP-DASH	MARKING	PAVEMENT	PAVEMENT	PAVEMENT	TYPE A	TYPE C
					4" WHITE	4" YELLOW	4" WHITE	4" WHITE	4" YELLOW	4" WHITE	REMOVAL	MARKER	MARKER	MARKING		
					FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH	FOOT	EACH	EACH
£8		T														
STA	35+78	TO	STA	55+44	1966.0	1966.0	491.5	1966.00	1966.00	491.50	368,6	25	25	540	6	6
WB																
STA	53+70	TO	STA	73+38	1968.0	1968.0	492.0	1968.00	1968.00	492,00	369.0	25	25	540	6	6
			5	UB-TOTAL	3934.0	3934.0	983.5	3934.0	3934.0	983.5	737.6	50	50	1080	12	12
	<del></del>		GRA	ND TOTAL		8,852			8,852	h	738	50	50	1080	12	12

NOTE: GUARDRAIL MARKERS TYPE A AND TYPE C ARE TO BE INSTALLED ON THE PARAPET WALLS OF THE STRUCTURES.

TEMPORARY RAMP SCHEDULE									
				TEMPORARY					
LO	CATION	HTOIW	LENGTH	RAMP					
		FOOT	FOOT	SQ YD					
EAST E	OUND STA	GE 1 WEST	END OF S	TRUCTURE					
STA	52+84	18.583	5	11					
STA	53+62	18.583	8	17					
STA	53+70	18.583	8	17					
EAST B	OUND STA	GE 1 EAST	END OF ST	TRUCTURE					
STA	55+41	18.583	8	17					
STA	55+49	18.583	8	17					
STA	56+35	18.583	5	11					
EAST B	<del></del>		END OF S	TRUCTURE					
STA	52+84	14.083	5	8					
STA	53+62	14.083	8	13					
STA	53+70	14.083	8	13					
EAST 8	OUND STA	GE 2 EAST	END OF S	TRUCTURE					
STA	55+41	14.083	8	13					
STA	55+49	14.083	8	13					
STA	56+35	14.083	- 5	8					
WEST E	OUND STA	GE 1 WEST	END OF S	TRUCTURE					
STA	52+90	24.771	5	14					
STA	53+65	24.771	8	23					
STA	53+73	24.771	8	23					
WEST E	OUND STA	GE 1 EAST	END OF S	TRUCTURE					
STA	55+37	16.771	8	15					
STA	55+45	16.771	8	15					
STA	55+20	16.771	5	10					
WEST E		GE 2 WEST	END OF S	TRUCTURE					
STA	52+90	14.792	5	9					
STA	53+65	14.792	8	14					
STA			8	14					
WEST B	OUND STA	GE 2 EAST	END OF S	TRUCTURE					
STA	55+37	14.792	8	14					
STA	55+45	14.792	8	14					
	55+20	14.792	5	9					
T	JATC			332					

L			
FILE NAME =	USER NAME > challandeské	DESIGNED ~	REVISED -
c:\px.work\pwidos\challandeshe\d8292482	0876F54-aht-schadula.dgn	DRAWN -	REVISED -
	PLOT SCALE . 188.8088 '/ in.	CHECKED -	REVISED -
	PLOT DATE * 11/2/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ł					SCHEDUL	ES		F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1								789	125-1HB-I	MADISON	29	7
1_										CONTRACT	NO.	76F54
[	SCALE: NONE	SHEET	1	OF	1 SHEET	S STA.	TO STA.		ILLINOIS FED. A		,	

FILE NAME =	USER NAME = challandeske	DESIGNED -	REVISED -					TVPIC	AI SE	CTIONS		F.A.P	SECTION	COUNTY	TOTAL	SHEET
c:\pw_work\pwidot\challandeske\d0292402	D876F54-sht-typical.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS						STRUCTION		789	125-1HB-I	MADISON	29	8
	PLOT SCALE = 100:0 ':" / in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION			run	STAGE	CUN	SINUCIIUN				CONTRAC	ST NO.	76F54
	PLOT DATE = 11/2/2012	DATE -	REVISED -		SCALE: NONE	SHEET 1	OF	)F 1	SHEETS	STA.	TO STA.		ILLINOIS FED	AID PROJECT		


LEGEND (FOR THIS SHEET ONLY) EXISTING CONTINUOUSLY REINFORCED PCC PAVEMENT - 7"
EXISTING STABILIZED SHOULDER
EXISTING STABILIZED SUB-BASE - 4"
EXISTING SUB-BASE, TYPE "C" - 4"
EXISTING AGGREGATE SHOULDER, TYPE "A"
EXISTING HOT-MIX OVERLAY 21/2" AND VARIES
PROPOSED PAVED SHOULDER REMOVAL
PROPOSED HOT-MIX ASPHALT BASE COURSE, 81/2"

STRUCTURE OMISSIONS: WB: STA. 53+67.18 TO STA. 55+46.59 EB: STA. 53+67.98 TO STA. 55+42.89

\*\*EB LT - STA. ±53+00 TO STA. ±53+65 STA. ±55+45 TO STA. ±55+84 RT - STA. ±53+00 TO STA. ±53+67 STA. ±55+45 TO STA. ±55+85

\*WB RT - STA. ±55+39 TO STA. ±55+98

STATION ±30+96 TO STATION ±81+37



¢ ROADWAY

¢ EB LANES

12'-0''

8'-0"

\*\*

4 7 6 2 5


1'-6''

12'-0"

SLOPE VARIES

6′-0′′

1'-6"



STATE OF ILLINOIS

**DEPARTMENT OF TRANSPORTATION** 

FILE NAME =

DESIGNED -

DRAWN

CHECKED

DATE

USER NAME = challandeske

PLOT SCALE = 100:0 ':" / in.

PLOT DATE = 11/2/2012

c:\pw\_work\pwidot\challandeske\d0292402\D876F54-sht-typical.dgn

REVISED

REVISED

REVISED

REVISED

COUNTY TOTAL SHEET NO.

MADISON 29 9

CONTRACT NO. 76F54

SECTION

125-1HB-I

789

TO STA.


TYPICAL SECTIONS


SCALE:


SHEET

FOR OVERLAY

SHEETS STA.







#### **PARTIAL EXIT RAMP CLOSURE**

#### **SYMBOLS**

⊨ SIGN

TYPE III BARRICADE


O DRUM WITH STEADY BURNING LIGHT

WORK AREA

FLAGGER WITH TRAFFIC CONTROL SIGN


NOT TO SCALE

	FILE NAME =	USER NAME = challandeske	DESIGNED -	REVISED -			TRAFFIC CONTROL DETAILS		F.A.P.	SECTION	COUNTY	TOTAL SHEET SHEET NO.
	c:\pw_work\pwidot\challandeske\d0292402	D876F54-sht-detail.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS				789	125-1HB-I	MADISON	29 12
		PLOT SCALE = 40.0000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION				-		CONTRACT	NO. 76F54
l	Default	PLOT DATE = 11/2/2012	DATE -	REVISED -		SCALE: NONE	SHEET 1 OF 1 SHEETS STA.	TO STA.		ILLINOIS FED. AI	D PROJECT	



### \*COST OF SAWCUT TO BE INCLUDED IN HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

#### ELEVATION VIEW




#### PLAN VIEW

#### HOT-MIX ASPHALT SURFACE REMOVAL -BUTT JOINT SEE SCHEDULE FOR STATIONS



HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

Default	PLOT DATE = 11/2/2012	DATE -	REVISED -		SCALE: NONE	SHEET 1 OF 1	SHEETS STA.	TO STA.		ILLINOIS FED. A	ID PROJECT	
	PLOT SCALE = 40.00000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION							CONTRACT NO.	. 76F54
c:\pw_work\pwidot\challandeske\d0292402\	.D876F54-sht-detail.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS					789	125-1HB-I	MADISON 29	e 13
FILE NAME =	USER NAME = challandeske	DESIGNED -	REVISED -	07477 07 11111010			DETAILS		RTE.	SECTION	COUNTY SHEET:	TS NO.
· · · · · · · · ·	THE PARTY OF THE P	DECTORED	DEVICED									AL CHEET!



ORAWN -

CHECKED

PASSED

#### GENERAL NOTES

Reinforcement bars designated (E) shall be epaxy coated.

Prior to pouring the new concrete deck, all heavy or loose rust, loose mill scale, and other loose or potentially detrimental foreign material shall be removed from the surfaces in contact with concrete. Tightly adhered point may remain unless otherwise noted. Removal shall be accomplished by methods that will not damage the steel and the cost will be included in the pay item covering removal of the existing concrete.

The deck surface shall have its final finish tined according to Article 420.09(e)(I) of the Standard Specifications. Cost included with Concrete Superstructures.

Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bld

The existing structural steel coating contains lead. The Contractor shall take appropriate precautions to deal with the presence of lead on this project.

All structural steel shall conform to AASHTO Classification M 270 Grade 36, unless otherwise noted.

Joint opening shall be adjusted according to Article 520.04 of the Standard Specs, when the deck is poured at an ambient temperature other than 50° F.

Existing reinforcement bars extending into removal area shall be cleaned. straightened and incorporated into the new construction. Any reinforcement bars that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost Included with Concrete Removal.



#### TOTAL BILL OF MATERIAL


ITEM	UNIT	TOTAL
Concrete Removal	Cu. Yd.	62.3
Concrete Superstructure	Cu. Yd.	67.9
Protective Shield	Sq. Yd.	785
Bar Splicers	Each	88
Floor Drain Extension	Each	8
Plug Existing Deck Drains	Each	15
Preformed Joint Strip Seal	Foot	180
Waterproofing Membrane System	Sa. Yd.	1525
HMA Surface Course, Mix "C" N70	Ton	165
Deck Slab Repair (Partial)	Sq. Yd.	435
Deck Slab Repair (Full Depth, Type II)	Sa. Yd.	52
Reinforcement Bars, Epoxy Coated	Pound	4500
Controlled Low-Strength Material	Cu. Yd.	149
Protective Coat	Sq. Yd.	394
Traffic Control and Protection (Special)	L. Sum	

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION


**GENERAL PLAN & ELEVATION** IL 143 over SIU N. Access Road, SN 060-0191 & 0192 SHEET NO. 1 OF 16 SHEETS


SECTION COUNTY 789 125-1HB-1 Madison CONTRACT NO. 76F54



(Looking East)

DESIGNED - AYV	EXAMINED		DATE -		CROSS SECTION	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET SHEETS NO.
CHECKED -		ENGINEER OF STRUCTURAL SERVICES		STATE OF ILLINOIS	SN 060-0191 (WB)	789	125-1HB-I	Madison	
DRAWN - AYV	PASSED		REVISED	DEPARTMENT OF TRANSPORTATION	2M 000-0131 (AAD)			CONTRAC	T NO. 76F54
CHECKED -		ENGINEER OF BRIDGES AND STRUCTURES	REVISED		SHEET NO. 2 OF 16 SHEETS		ILLINOIS FED. A	ID PROJECT	





1'-0" Hatchblock  $20'-6l_2$ " Stage II Removal \_\_ © Bridge Const. 3′-6" 22'-1½" Stage I Removal –€ W.B. Pav′t 1'-0" Hatchblock -Bk. of Abut. (typ.) 3′-6" 1'-0" 1'2" typ.

Note:

See sheet 8 of 16 for Sections A-A & B-B.

During removal & replacement of portions of the wingwalls, the contractor shall remove & replace the name plate. Cost included with Concrete Removal.


CONCRETE REMOVAL


(W. Abutment)


CONCRETE REMOVAL


(E. Abutment)


DESIGNED - AYV	EXAMINED		DATE -		CONCRETE REMOVAL (WB)	F.A.P.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CHECKED -	_	ENGINEER OF STRUCTURAL SERVICES		STATE OF ILLINOIS	SN 060-0191	789	125-1HB-I	MADISON		
DRAWN - AYV	PASSED		REVISED	DEPARTMENT OF TRANSPORTATION		_		CONTRAC	T NO. 7	6F54
CHECKED -		ENGINEER OF BRIDGES AND STRUCTURES	REVISED		SHEET NO. 4 OF 16 SHEETS		ILLINOIS FED.	AID PROJECT		











Full Depth																																																Type I	Type II	Type	Type II	Type II	Type II	Type II					
Depth	Ь	Д	۵ م	ב ם		Д	<u> </u>		. 🕰	۵	<b>a</b>	۵ م	ב	. 🕰	Д	Д	ב	ב מ	ב מ		. 🕰	_	Ф	Ъ	۵ م	ב מ	L	Ь	<u>م</u> ا	ב ם	L	Д	<u>a</u> i	ը ը	. 🕰	<b>a</b> (	<u> </u>	L	۵ ۵	ב מ	. 🕰	۵ ر	ב	ட	۵ ر	<u>م</u> م	. 🕰	ш	ш	- L	ш	LL L	ц	. ш	L L	ш	. ш	ш	ц
(sy)	1.33	2.78	2.67	1.0.0	3.89	8.00	2.78	5.33	11.00	1.17	0.17	2.33	2.78	16.33	3.47	4.00	0.17	00.1	2.08	4.33	11.67	8.67	2.78	0.67	10.00	5.53 000	1.78	5.33	6.11	9.89	0.11	5.00	5.33	7.33	15.33	1.33	1.56	1.33	1.11	3.43	14.00	2.22	2.22 0 44	1.33	4.00	8.44	13.44	0.22	0.83	1.17	3.78	2.78	0.83	3.47	4.22	2.22	2.56	6.22	3.47
( <del>f</del> .)	4	2	ه ر	0.0	2 2	ဝ	လ	5 0	၂ တ	10.5	1.5	4.2		21	7.8	6	1.5	9 2 3	6.25	19.5	21	13	5	2	9 (	ည ထ	0 4	8	11	ی 7	o <del>-</del>	5	16	11	. 23	4 1	۷ ح	ე ო	2	ر ا	. 9	4	4 4	4	9	4 5	1 +	0.5	1.5 8.25	1.5	4.25	6.25	5. 7.	6.25	← u	5 4 75	<u></u> — (	∞ <	4
(ft.)	3	2	4 4	- 5	2 /-	8	ري ح	t 4	. =	-	<b>—</b>	ഗ	ס ער	7	4	4	~   ~	- c	თ ო	0 4	2 1	9	2	က	1 <sub>5</sub>	ດ ຕ	0 4	9	٠ ي	4 4 7 8 7	ў. —	6	က	9 /	. 9	ကျ	2 0	1 4	2 5	0 4	21	ιςς l	Ω <del>-</del>	က	9 ;	<del>1</del> 4	. #	4	v u	o   _	∞	4 ı	ი 4	2	38	4 r:	23	7	Ω L
	25 Lt	18 Lt	9 C	± 11 2	5 Lt	22 Lt	22 Lt	2 5	22 Lt	12 Lt	1.5 Lt	12 Lt	11 11	21 Lt	7.8 Lt		1.5 Lt	21 LT 7.75 L+	7.75 Lt 21 1+	21 Lt	21 Lt	19 Lt	5 Lt	2 Lt	19 Lt	۲ - ۲ ۲ - ۲	4 c	8 Lt	19 Lt	78 -	10 Rt	11 Rt	11 R	77 4 12 42 13 12 13 13 13 13 13 13 13 13 13 13 13 13 13	12 Rt	4 1 R	# # # # # # # # # # # # # # # # # # #	7 72 72	# c	۲ الا م د	6 Rt	4 4 5 7 7 7	5 4 X X	4 Rt	# i	12 4 4 4 4 4	1 T	0.5 Lt	1.5 Lt 7.75 I+	1.5 Lt	12 Lt	7.75 Lt	1.5 Lt	7.75 Lt	12 Rt	5 Rt 4 75 Rt	12 Rt	## ## ## ## ## ## ## ## ## ## ## ## ##	4 ; Z ç
From	21 Lt	13 Lt	0	0.0 17 Lt	i O	13 Lt	17 Lt	0 0	13 Lt	1.5 Lt	0	7.8 Lt	0: 11 0: 14 0: 14 0: 14 0: 16 0: 17 0: 17 0: 18	0	0	12 Lt	0 +-	17 71	1.5 Lt	1.5 Lt	0	6 Lt	0	0	13 Lt	, Lt	0			19 11 12	- 6 - 6		2	0 0	7	0	0 0	8 2	9 T	0	0	## id	¥ 0	0	0	₹ ∞ c	0	0	0 + + +		7.75 Lt	1.5 Lt	0 0	1.5 Lt	二 森	0 0	1	0	0 47 4
Sta	0+10	0+20	0+24	0+70	0+41	0+53	0+58	0+61	0+20	0+65	0+40	0+70	0+79	0+91	0+95	0+95	96+0	06+0	66+0	1+01	1+06	1+12	1+15	1+18	1+27	1+23	1+27	1+35	1+39	1+46	0+12	0+21	0+28	0+34	0+57	09+0	0+62	0+79	0+81	0+91	1+22	1+10	1+19	1+30	1+36	1+55	1+70	0+28	0+69	0+79	0+66	0+99	1+01	1+41	0+43	0+28	0+00	0+79	1+0.1
Sta	20+0	0+15	0+20	0+24	0+34	0+45	0+53	0+57	0+59	0+64	69+0	0+65	0+79	0+84	0+91	0+91	90+0	C6+0	96+0	66+0	1+01	1+06	1+10	1+15	1+12	1+18	1+23	1+29	1+34	1+42	0+11	0+12	0+25	0+28	0+51	0+57	09+0	0+75	0+79	0+81	1+01	1+05	1+14	1+27	1+30	1+36	1+59	0+24	0+64	0+72	0+91	0+95	0+96	1+36	0+05	0+24	79+0	0+72	06+0
#	_	2	т С	4 ռ	) ဖ	7	ω c	, <del>C</del>	5 = =	12	5	4 <sup>4</sup>	<u>.</u> 6	17	18	19	5 50	1.7	22 82	24 2	25	26	27	28	53	30 24	32	33	34	35	37	38	39	40	42	43	44	46	47	8 4 6	50	51	22	54	55	57 57	58	29	60	62	63	64		29	89	69	2 7 2	72	5/ 5

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

DESIGNED - AYV

DRAWN - AYV

CHECKED -

CHECKED -

EXAMINED

PASSED

ENGINEER OF STRUCTURAL SERVICES

ENGINEER OF BRIDGES AND STRUCTURES

DATE -

REVISED

REVISED

F.A.P. RTE. 789

DECK PATCHING SURVEY (DATA) (WB)

SN 060-0191

SHEET NO. 10 OF 16 SHEETS


SECTION

125-1HB-I

COUNTY


Madison


CONTRACT NO. 76F54



l or II (Full Depth)																																												Type II	Type II	TVP0
Partial Depth	Ъ	Д	<u>а</u>	L	<b>d</b>	<b>a</b>	۵ م	ד כ	ב ב	. 🗅	Д	Ь	م ا	۵ ر	ד ם	L		Д	Ъ	م ا	ם מ	L	Ъ	Д	۵ ر	ב ב	. 🗅	Д	۵ ر	ד פ	Ь	۵ ر	ם מ		Д	۵ (	ם ם		۵	Д	۵ م	<b>L</b> a		. ш	ш	Ь
Area (sy)	1.08	12.00	1.00	1.00	5.33	6.22	1.78	0.0 <i>l</i>	3.30 8.56	2.78	0.22	0.56	4.00	2.22	7.78	0.03	2.78	4.44	1.33	3.33	2.78	1.33	0.30	7.67	1.33	2.78	0.67	3.11	1.00	1.33	2.67	0.89	1.22	0.67	1.33	0.37	0.44 00.8	6.67	2.00	3.33	2.00	2.67	32.40	0.89	4.81	7
Width (ft.)	2	12	ကျ	၁ က	4	∞	4 (	7 0	0 1	. 2	_	5	12	ر ک	4 c	7 /	. 2	10	က	ري ر	ဂ ဂ	7 4	2.7	7.67	12	t 2	2	4	ო ,	4 (7	4	ω 0	3.67	2 0	4	1.67	4 α	12	9	ၑ	က	၇ (၄	12	. 4	4.33	000
Length (ft.)	4.87	6	თ 1	- ო	12	7	4 (	ე ∠	4 =====================================	2	2	_	m ·	4 ,	4 <	t (C	ည လ	4	4	တ ၊	ა <del>(</del>	<u>2</u> ო	· <b>-</b>	ဝ	← l	c 4	က	7	ကျ	ກ ຕ	9	~ (	m (n	ာ က	က	7	- o	о С	က	2	ဖ စ	0 4	24.3	2	10	! (
( <b>(ft)</b>	Lt	ij	= :	<u> </u>	ä	ت ا	<b>=</b> =	<u>ا</u> ا	<b>i</b>	i <del>"</del>	Ľ	Ľ	<b>=</b> :	<b>=</b>	<u>ئ</u> ئ	<u> </u>	í	ĭ	Ħ	<b>=</b> :	<u>ئ</u> ئ	i =	ť	Ħ	<b>=</b> :	<b>=</b>	ř	袏	芒	ž ž	袏	芷	7 ā	ž	袏	ř i	<b>건</b> 8	ž	芷	쮼	ř ă	ž &	ž	===		
<b>d</b> )	2	12	ω <del>ζ</del>	4	12	$\infty$	ω (	7 5	5 5	2	2	2	12	رن د	7 5	7 /	12	19	4	12	7 5	7 /		12	12	5 5	၂ က	4	က	4 0	4	72	27 0	5 2	4	4	4 5	7 2	12	ဖ	72	o 5	7 5	4	4.33	
offs n			-	<u>ت</u> ا ت	ä		<b>=</b>	<u>:</u>  ئ	<b>i</b>	i	Ħ			-	± ا	ĭ	=		Ħ	<b>=</b>  :	± ا	تا ا		3 Lt	-	5	袏						호 호	ž   ž		쮼	ā	=	袏		ž	Ť	2			ì
From	0	0	0	> <del>-</del>	<u></u>	0	4 5	2 0	7 12	0	4	0	0	0	α 5	2 0	^	0	_	_	\ C	2 m	4.3	4.33	0	\ 0		0	0	0	0	4	8.33 8	9	0	2.33	> \	0	ဖ	0	တ င	၁ ဖ	0	0	0	) (
End Sta	0+10	0+19	0+36	0+45	0+65	09+0	0+65	0+08	0+74	0+84	0+86	0+87	06+0	0+94	1+02	1+06	1+08	1+20	1+30	1+32	1+41	1+54	1+55	1+64	1+65	1+70	0+17	0+37	0+50	0+20	0+65	0+56	60+0	0+74	0+84	0+86	78+0	1+06	1+09	1+18	1+21	1+48	1+74	0+86	1+64	
Start Sta	90+0	0+10	0+33	0+40	0+53	0+53	0+61	0400	0+74	0+19	0+84	98+0	0+87	06+0	06+0	1+00	1+03	1+16	1+26	1+26	1+36	1+51	1+54	1+55	1+64	1+65	0+14	0+30	0+47	0+56	0+29	0+55	0+56	0+71	0+81	0+84	0+86	1+01	1+06	1+13	1+15	1+44	1+50	0+84	1+54	
Patch #	_	5	თ <	t ω	9	7	ω (	D) {	2 = ==	12	13	14	15	1,	<u>~</u> &	5 6	202	21	22	23	24 مر	26 26	27	28	53	37	32	33	\$ 15	දු ලි	37	38	£ 200 €	5 4	42	43	44 7	£ 4	47	48	49	27 6	25	53	45	

-IHB-I Madison CONTRACT NO. 76F54





WATERPROOFING STAGING (WB)

Looking East

Stage II Construction

WATERPROOFING STAGING (EB)

Looking East

DESIGNED - AYV

CHECKED 
DRAWN - AYV

PASSED

ENDINER OF PRUCES AND TRUCKES AND TRUCKES REVISED

REVISED

REVISED

REVISED

REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DRAIN DETAILS & WATERPROOFING STAGING
STRUCTURE NO. 060-0191 & 0192

SHEET NO. 13 OF 16 SHEETS

HMA

Surface

Course

Stage II Temporary Concrete Barrier

Stage II Construction


-Waterproofing


Membrane System

Stage I Construction

Lap Waterproofing during-

6" 6"





#### NOTES

Detail I - With Bar Splicer or Couplers:

Connect one (1)  $1'' \times 7' \times 'W''$  steel ? to the top layer of couplers with  $2^{-5}8'' \neq bolts$  screwed to coupler at approximate ? of each barrier panel.

Detail II - With Extended Reinforcement Bars:

Connect one (1) I'' x 7'' x "W" steel P to the concrete slab or concrete wearing surface with 2-5%" \$\phi\$


Expansion Anchors or cast in place inserts spaced between the top layer of reinforcement at approximate \$\mathbb{Q}\$ of each barrier panel.


Cost of anchorage is included with Temporary Concrete Barrier.
The I" x 7" x "W" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready to be placed.

#### SECTIONS THRU SLAB OR DECK BEAM

- \*\*\* Dimension shown is minimum required embedment into concrete.

  If hot-mix asphalt wearing surface is present, minimum embedment shall be in addition to wearing surface depth.
- \*\*\*\* If existing deck beam is to remain in place after stage construction, embedment shall only be into wearing surface and not into existing deck beam concrete.





STEEL RETAINER & 1" x 7" x "W"

\* Required only with Detail II


\*\* Wood blocks may be omitted when required to provide minimum stage traffic lane width. When the wood blocks are omitted, the concrete barrier shall be in direct contact with the steel retainer plate.

"W" = Top bars spacing + 4"

R-27

7-1-10

DESIGNED - A.Y.V.	EXAMINED		DATE -	STATE OF HUMOIO	TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION	F.A. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
CHECKED -		ENGINEER OF STRUCTURAL SERVICES	DEMISED	STATE OF ILLINOIS	STRUCTURE NO. 060-0191 & 0192	789	125-1HB-I	MADISON	
DRAWN - A.Y.V.	PASSED	ENGINEER OF BRIDGES AND STRUCTURES	REVISED	DEPARTMENT OF TRANSPORTATION	SHEET NO. 15 OF 16 SHEETS		TILL INDIS FED. A		T NO. 76F54



#### STANDARD BAR SPLICER ASSEMBLY

		Minim	num Lap Len	gths		
Bar size to be spliced	Table 1	Table 2	Table 3	Table 4	Table 5	Table 6
3, 4	1'-5''	1'-11''	2'-1''	2'-4''	2'-7''	2'-11''
5	1'-9''	2'-5"	2'-7''	2'-11''	3'-3''	3′-8′′
6	2'-1''	2'-11''	3'-1''	3′-6′′	3′-10′′	4′-5′′
7	2'-9''	3'-10''	4'-2"	4'-8''	5′-2′′	5′-10′′
8	3′-8′′	5′-1′′	5′-5′′	6'-2''	6'-9''	7′-8′′
9	4'-7''	6'-5''	6'-10''	7′-9′′	8'-7"	9'-8''

Table 1: Black bar, 0.8 Class C

Table 2: Black bar, Top bar lap, 0.8 Class C

Table 3: Epoxy bar, 0.8 Class C

Table 4: Epoxy bar, Top bar lap, 0.8 Class C


Table 5: Epoxy bar, Class C

Table 6: Epoxy bar, Top bar lap, Class C

Threaded splicer bar length = min. lap length +  $1^{l_2}$ " + thread length


\* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.

Location	Bar size	No. assemblies required	Table for minimum lap length
End of Decks (W.B. W. Abut.)	#6	10	4
End of Decks (except W.B. W. Abut.)	#5	30	4
Hatch Block	#6	16	4
Approach	#5	32	4



### BAR SPLICER ASSEMBLY FOR #5 BAR ON INTEGRAL OR SEMI-INTEGRAL ABUTMENTS


No, required =



#### INSTALLATION AND SETTING METHODS


"A": Set bar splicer assembly by means of a template bolt.
"B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms.

(E): Indicates epoxy coating.



#### STANDARD MECHANICAL SPLICER

Location	Bar size	No. assemblies required



#### NOTES

Splicer bars shall be deformed with threaded ends and have a minimum 60 ksi yield strength.

All reinforcement shall be lapped and tied to the splicer bars.

Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars. See Section 508 of the Standard Specifications.

See approved list of bar splicer assemblies and mechanical splicers for alternatives.

BSD-1

1-27-12

DESIGNED - AYV	EXAMINED		DATE -	
CHECKED -	]	ENGINEER OF STRUCTURAL SERVICES		
DRAWN - AYV	PASSED		REVISED	
CHECKED -		ENGINEER OF BRIDGES AND STRUCTURES	REVISED	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS
STRUCTURE NO. 060-0191 & 0192

SHEET NO. 16 OF 16 SHEETS