

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY 0001 URBAN	BRIDGE 0008 S. N. 082-0385	BRIDGE 0008 S. N. 082-0386	BRIDGE 0008 S. N. 082-6003 & 082-0287
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1200	1200			
28000305	TEMPORARY DITCH CHECKS	FOOT	144	144			
28000400	PERIMETER EROSION BARRIER	FOOT	230	230			
28000500	INLET AND PIPE PROTECTION	EACH	2	2			
28100707	STONE DUMPED RIPRAP, CLASS A4	SO YD	76	76			
28200200	FILTER FABRIC	SO YD	76	76			
28500100	FABRIC FORMED CONCRETE REVETMENT MAT	SO YD	328		328		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	65	65			
50200100	STRUCTURE EXCAVATION	CU YD	414		205	209	
50300225	CONCRETE STRUCTURES	CU YD	131.2		64.8	66.4	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	605.8		299.9	305.9	
50300260	BRIDGE DECK GROOVING	SO YD	978		482	496	
50300300	PROTECTIVE COAT	SO YD	1426		706	720	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		0.5	0.5	



DESIGNED - JJO	REVISED -
DRAWN - JJO	REVISED -
CHECKED - PJM	REVISED -
DATE - 06/26/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 788	SECTION 520-1-2B	COUNTY ST. CLAIR	TOTAL SHEETS 94	SHEET NO. 4
ILLINOIS FED. AID PROJECT				CONTRACT NO. T6F69