

PAVEMENT MARKING SCHEDULE																
LOCATION	TEMPORARY			PERMANENT PAVEMENT MARKING			WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL						
				PAINT												
	24" SINGLE WHITE STOP BAR	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE	24" SINGLE WHITE EDGE LINE					70300280	70300220	70300220	78001110	78001110	78001180
FAS 2869 \ IL 37																
LT. STA 382+53 TO LT. STA 388+96		608			608								200	151		
CL. STA 382+53 TO CLT. STA 388+96			161			161							53	40	9	9
RT. STA 382+53 TO RT. STA 388+96		593			593								196	151		
RT. STA 383+80	10											10	20			
LT. STA 383+75	10											10	20			
SUBTOTAL	20	1201	161		1201	161						20	489	342	9	9
TOTAL	20		1362			1362						20	489	342	9	9

STAGING SCHEDULE										
LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3	TEMPORARY BRIDGE TRAFFIC SIGNALS					
						70400100	70400200	Z0030250	Z0030350	70106500
						FOOT	FOOT	EACH	EACH	EACH
FAS 2869 \ IL 37										
STAGE I										
LT. STA 384+01.00 TO LT. STA 387+61.00	300		2		1					
STAGE II										
RT. STA 384+13.50 TO RT. STA 387+61.00		2875		2						
TOTAL	300	2875	2	2	1					
TOTAL USE	300	288	2	2	1					

20700220 POROUS GRANULAR EMBANKMENT	
LOCATION	CU YD
FAS 2869 \ IL 37	
STAGE I	
LT. STA 385+44.47 TO LT. STA 385+52.58	18
LT. STA 385+52.58 TO LT. STA 385+54.58	5
LT. STA 385+54.59 TO LT. STA 385+79.41	5
LT. STA 385+79.41 TO LT. STA 385+81.41	5
LT. STA 385+81.41 TO LT. STA 385+88.52	18
STAGE II	
RT. STA 385+44.47 TO RT. STA 385+52.58	18
RT. STA 385+52.58 TO RT. STA 385+54.58	5
RT. STA 385+54.59 TO RT. STA 385+79.41	5
RT. STA 385+79.41 TO RT. STA 385+81.41	5
RT. STA 385+81.41 TO RT. STA 385+88.52	18
TOTAL	102

25100630 EROSION CONTROL BLANKET	
LOCATION	SQ YD
FAS 2869 \ IL 37	
LT. STA 383+95 TO LT. STA 385+45	135
RT. STA 383+95 TO RT. STA 385+65	122
LT. STA 385+70 TO LT. STA 386+90	96
RT. STA 385+90 TO RT. STA 386+90	49
TOTAL	402

20100500 TREE REMOVAL ACRES	
LOCATION	ACRE
FAS 2869 \ IL 37	
STAGE I	
RT. STA 385+64 TO RT. STA 386+10	0.004
TOTAL	0.004
TOTAL USE	0.25

28000400 PERIMETER EROSION BARRIER	
LOCATION	FOOT
FAS 2869 \ IL 37	
STAGE I	
LT. STA 383+95 TO LT. STA 385+30	140
RT. STA 383+95 TO RT. STA 385+60	165
LT. STA 385+75 TO LT. STA 387+70	200
RT. STA 386+05 TO RT. STA 387+70	160
TOTAL	665

EROSION CONTROL SCHEDULE		
LOCATION	STONE RIPRAP CLASS A4	FILTER FABRIC
	28100107	28200200
	SQ YD	SQ YD
FAS 2869 \ IL 37		
LT. STA 384+35	8	8
TOTAL	8	8