

GENERAL NOTES

INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	COVER SHEET
2	INDEX OF SHEETS, STANDARDS, SIGNATURES, GENERAL NOTES
3, 4	SUMMARY OF QUANTITIES
5	SN 028-0039 LOCATION, NOTES
6	PORTABLE TEMPORARY BARRIER SYSTEM
7-11	SN 028-0039 STRUCTURE INFORMATION
12	SN 039-0050 LOCATION, NOTES
13-16	SN 039-0050 STRUCTURE INFORMATION
17	SN 041-0032 LOCATION, NOTES
18-26	SN 041-0032 STRUCTURE INFORMATION
27	SN 076-0001 LOCATION, NOTES
*28-33	SN 076-0001 STRUCTURE INFORMATION

* SHEETS 31 THRU 33 HAVE BEEN DELETED

EXTRA TRAFFIC CONTROL DEVICES MAY BE REQUIRED TO CHANNEL TRAFFIC AT COMMERCIAL AND/OR PRIVATE ENTRANCES AS DIRECTED BY THE ENGINEER. ALL TRAFFIC CONTROL DEVICES ARE INCLUDED IN THE COST OF THE TRAFFIC CONTROL AND PROTECTION STANDARD USED AT THE SITE, AND WILL NOT BE PAID FOR SEPARATELY.

THE EXISTING STEEL COATINGS CONTAIN LEAD. THE CONTRACTOR SHOULD TAKE APPROPRIATE PRECAUTIONS TO DEAL WITH THE PRESENCE OF LEAD ON THIS PROJECT.

THE CONTRACTOR IS REQUIRED TO BE SSPC OP1 AND SSPC OP2 CERTIFIED.

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

TRAFFIC CONTROL SIGNS SHALL BE PLACED SO THAT THEY DO NOT INTERFERE WITH EXISTING SIGNS OR FLASHING BEACONS. THE DIMENSIONS BETWEEN SIGNS MAY BE MODIFIED SLIGHTLY SO AS TO AVOID CONFLICTS WITH EXISTING SIDE ROADS, COMMERCIAL ENTRANCES, AND PRIVATE ENTRANCES. THE BUREAU OF OPERATIONS SHOULD APPROVE FINAL PLACEMENT OF TRAFFIC CONTROL SIGNING.

IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16 THE CONTRACTOR SHALL PROTECT THE SURFACE OF ALL BRIDGE DECKS AND BRIDGE APPROACH PAVEMENTS IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 101.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.

THE QUANTITY FOR RELOCATE PORTABLE TEMPORARY BARRIER SYSTEM IS BASED ON RELOCATING THE BARRIER THREE TIMES. ANY PAYMENT FOR ADDITIONAL RELOCATION WILL BE MADE ACCORDING TO ARTICLE 104.02 OF THE STANDARD SPECIFICATIONS.

COMMITMENTS: NONE AS OF OCT. 19, 2012

STANDARDS

701201-04	LANE CLOSURE, 2L, 2W, DAY-ONLY
701400-06	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701402-09	LANE CLOSURE, FREEWAY/EXPRESSWAY WITH BARRIER
701411-08	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS > 45 MPH
701422-05	LANE CLOSURE, MULTILANE, FOR SPEEDS > 45 MPH TO 55 MPH
701901-03	TRAFFIC CONTROL DEVICES

Prepared By:	<i>Joe Zdaniewicz</i> DISTRICT STUDIES & PLANS ENGINEER
Examined By:	<i>James E. Eg</i> DISTRICT LAND ACQUISITION ENGINEER
Examined By:	<i>Carrie Nelson</i> DISTRICT PROGRAM DEVELOPMENT ENGINEER
Examined By:	<i>Karl Kelly</i> DISTRICT OPERATIONS ENGINEER
Examined By:	<i>K. R. [Signature]</i> DISTRICT PROJECT IMPLEMENTATION ENGINEER
Examined By:	<i>Douglas J. [Signature]</i> DISTRICT CONSTRUCTION ENGINEER
Examined By:	<i>Eric [Signature]</i> DISTRICT MATERIALS ENGINEER
Approved By:	<i>Omer Osmani</i> DEPUTY DIRECTOR OF HIGHWAYS, REGION 5 ENGINEER
	DATE: <u>Oct 25</u> 2012

FILE NAME *	USER NAME *	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		INDEX OF SHEETS, STANDARDS, GENERAL NOTES		RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\p\dot\goutneyrk\d0319666\78	goutneyrk	DRAWN -	REVISED -					VAR.	D9 BRIDGE PAINTING 2013-1	VARIOUS	33	2
#MODELNAME#		CHECKED -	REVISED -			SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____						CONTRACT NO. 78341
		DATE -	REVISED -									ILLINOIS FED. AID PROJECT