

78000400	
THPL PVT MK LINE 6	
STA. 9+43	194.0 FT.
STA. 10+50	179.2 FT.
STA. 21+36	142.4 FT.
STA. 33+20	215.0 FT.
STA. 34+20	194.8 FT.
TOTAL	925.0 FT.

78000600	
THPL PVT MK LINE 12	
STA. 9+43	153.0 FT.
STA. 10+50	135.0 FT.
STA. 21+37	108.0 FT.
STA. 33+20	162.0 FT.
STA. 34+20	153.0 FT.
TOTAL	711.0 FT.

78000650	
THPL PVT MK LINE 24	
STA. 9+37 RT	52.4 FT.
STA. 10+60 LT	45.4 FT.
STA. 19+51 RT	40.0 FT.
STA. 21+49 LT	37.0 FT.
STA. 33+16 RT	51.1 FT.
STA. 34+32 LT	49.5 FT.
TOTAL	275.0 FT.

78100100	
RAISED REFL PAVT MKR	
STA. 8+78 - 9+37	9.0 EA.
STA. 10+63 - 20+15	78.0 EA.
STA. 21+49 - 22+50	12.0 EA.
STA. 30+00 - 33+15	23.0 EA.
STA. 34+32 - 37+81	21.0 EA.
TOTAL	143.0 EA.

78300200	
RAISED REFL PAVT MK REM	
STA. 8+78 - 9+37	9.0 EA.
STA. 10+63 - 20+15	78.0 EA.
STA. 21+49 - 22+50	12.0 EA.
STA. 30+00 - 33+15	23.0 EA.
STA. 34+32 - 37+81	21.0 EA.
TOTAL	143.0 EA.

89502210	
MODIFY EXISTING CONTROLLER CABINET	
AVE OF THE CITIES & 41ST ST.	1.0 EA.
TOTAL	1.0 EA.

X7010216	
TRAF CONT AND PROT SPECIAL	
ENTIRE PROJECT	1.0 L.SUM
TOTAL	1.0 L.SUM


X8140115	
HANDHOLE ADJ	
STA. 13+21 RT	1.0 EA.
STA. 16+51 RT	1.0 EA.
STA. 31+72 RT	1.0 EA.
TOTAL	3.0 EA.

XX002119	
SS DI 18	
STA. 20+65 RT	6.0 FT.
TOTAL	6.0 FT.

XX006343	
SEEDING COMPLETE	
STA. 11+53 RT	0.6 S.Y.
STA. 13+19 RT	0.3 S.Y.
STA. 13+21 LT	1.4 S.Y.
STA. 15+97 LT	1.0 S.Y.
STA. 31+62 LT	1.9 S.Y.
STA. 32+19 LT	1.7 S.Y.
STA. 33+02 RT	2.4 S.Y.
STA. 33+29 LT	2.0 S.Y.
STA. 34+03 RT	2.0 S.Y.
STA. 38+38 RT	2.8 S.Y.
STA. 38+96 RT	3.0 S.Y.
TOTAL	19.0 S.Y.

XX007739	
WIRELESS VEH DET SYS	
AVE OF THE CITIES & 41ST ST.	1.0 EA.
HY=VEE/ALDI'S ENTRANCE	1.0 EA.
TOTAL	2.0 EA.

20058300	
SAN SEW T1 8	
STA. 9+08 LT	105.0 FT.
TOTAL	105.0 FT.



CITY OF MOLINE
DEPARTMENT OF PUBLIC WORKS - ENGINEERING DIVISION
3635 4TH AVENUE, MOLINE, IL 61265
(309) 524-2350
CITY ENGINEER - SCOTT HINTON, P.E.

AVE. OF THE CITIES RESURFACING
41ST TO 43RD STREET & 41ST ST. 24TH AVE. TO 22ND AVE.
SEC. 12-00253-00-RS

09-07-12	LCK
Date	Revision

Date	07-02-12	Sheet	5
Scale	1" = 20'	OF	16
Design Engineer	LCK	Contract	85567