

**INDEX OF SHEETS**

**SHEET**

**NUMBER**

**DESCRIPTION**

1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES AND COMMITMENTS
3-7	SUMMARY OF QUANTITIES
8-9	TYPICAL SECTIONS
10-11	SCHEDULE OF QUANTITIES
12	ALIGNMENT, TIES, AND BENCHMARKS
13	REMOVAL PLAN
14-15	PLAN AND PROFILE
16	DETOUR PLAN
17	EROSION & SEDIMENT CONTROL DETAILS
18-21	RIGHT-OF-WAY SHEETS
22	PAVEMENT MARKING PLAN
23-40	STRUCTURAL SHEETS (S.N. 072-3148)
41-46	CROSS SECTIONS
46A	PERMANENT BENCH MARK
47-55	DISTRICT DETAILS

**LIST OF STATE STANDARDS**

**STANDARD**

**DESCRIPTION**

**NUMBER**

000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-07	TEMPORARY EROSION CONTROL SYSTEMS
420401-09	BRIDGE APPROACH PAVEMENT CONNECTOR
482001-02	HMA SHOULDER ADJACENT TO FLEXIBLE PAVEMENT
515001-03	NAME PLATE FOR BRIDGES
601101-01	CONCRETE HEADWALL FOR PIPE DRAIN
630001-10	STEEL PLATE BEAM GUARDRAIL
630301-06	SHOULDER WIDENING FOR TYPE I GUARDRAIL TERMINATORS
631032-08	TRAFFIC BARRIER TERMINAL, TYPE 6A
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
665001-02	WOVEN WIRE FENCE
666001-01	RIGHT-OF-WAY MARKERS
701901-02	TRAFFIC CONTROL DEVICES
780001-03	TYPICAL PAVEMENT MARKINGS
BLR21-9	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS
BLR22-7	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS (2L, 2W RURAL TRAFFIC- ROAD CLOSED TO THRU TRAFFIC)

**DISTRICT DETAILS**

**STANDARD**

**NUMBER**

**DESCRIPTION**

205001-D4	SLOPE STEPS DETAIL
280001-D4	TYPICAL APPLICATION OF SILT FILTER FENCE
281001-D4	RIPRAP DITCH FOR EROSION PROTECTION
630101-D4	GUARDRAIL EROSION CONTROL TREATMENTS
635101-D4	GUARDRAIL AND BARRIER WALL DELINEATION
780001-D4	PAVEMENT MARKINGS, TYPICAL

**COMMITMENTS**

1. THE COUNTY SHALL NOTIFY ALL EMERGENCY, SCHOOL, AND POSTAL SERVICES OF THE ROAD CLOSURE BEFORE CONSTRUCTION.
2. ALL TREE -CLEARING WILL OCCUR BETWEEN OCTOBER 1ST AND MARCH 30TH, OUTSIDE OF THE INDIANA BAT'S MATERNITY PERIOD.
3. THE DITCH IN THE SOUTHWEST QUADRANT WILL BE CLEARED OF TRESS AND BRUSH WITHIN THE PROJECT LIMITS. IN ADDITION, A SMALL BERM WILL BE PROVIDED AT THE TOP OF THE PROPOSED DITCH BACKSLOPE TO PREVENT WATER FROM ENTERING THE ADJACENT PROPERTY OWNER'S FIELD DURING LARGE RAIN EVENTS.

**GENERAL NOTES**

1. MICROSTATION AND GEOPAK FILES OF THIS PROJECT WILL BE MADE AVAILABLE TO THE CONTRACTOR. IF THERE IS A CONFLICT BETWEEN THE ELECTRONIC FILES AND THE PRINTED CONTRACT PLANS AND DOCUMENTS, THE PRINTED CONTRACT PLANS AND DOCUMENTS SHALL TAKE PRECEDENCE OVER THE ELECTRONIC FILES. THE CONTRACTOR SHALL ACCEPT ALL RISK ASSOCIATED WITH USING THE ELECTRONIC FILES AND SHALL HOLD THE DEPARTMENT HARMLESS FOR ANY ERRORS OR OMISSIONS IN THE ELECTRONIC FILES AND THE DATA CONTAINED THEREIN. ERRORS OR DELAYS RESULTING FROM THE USE OF THE ELECTRONIC FILES BY THE CONTRACTOR SHALL NOT RESULT IN AN EXTENSION OF TIME FOR ANY INTERIM OR FINAL COMPLETION DATE OR SHALL NOT BE CONSIDERED CAUSE FOR ADDITIONAL COMPENSATION. THE CONTRACTOR SHALL NOT USE, SHARE, OR DISTRIBUTE THESE ELECTRONIC FILES EXCEPT FOR THE PURPOSE OF CONSTRUCTING THIS CONTRACT. ANY CLAIMS BY THIRD PARTIES DUE TO USE OR ERRORS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL INCLUDE THIS DISCLAIMER WITH THE TRANSFER OF THESE ELECTRONIC FILES TO ANY OTHER PARTIES AND SHALL INCLUDE APPROPRIATE LANGUAGE BINDING THEM TO SIMILAR RESPONSIBILITIES.
2. ALL ELEVATIONS SHOWN ON THE PLANS ARE ESTABLISHED FROM U.S.G.S. MEAN SEA LEVEL DATUM.
3. COMMITMENTS ARE NOT TO BE ALTERED WITHOUT THE WRITTEN APPROVAL OF ALL PARTIES TO WHICH THE COMMITMENT WAS MADE.
4. ACCESS MUST BE MAINTAINED TO ALL EXISTING PROPERTIES DURING CONSTRUCTION PER ARTICLE 107.09 UNLESS ARRANGEMENTS ARE MADE IN WRITING BY THE CONTRACTOR WITH THE PROPERTY OWNERS WITH A COPY TO THE ENGINEER FOR SHORT -TERM CLOSURES.
5. THE CONTRACTOR WILL SUBMIT TO THE ENGINEER A SATISFACTORY PROGRESS SCHEDULE AND CRITICAL PATH SCHEDULE WHICH SHALL SHOW THE PROPOSED SEQUENCE OF WORK AT THE TIME OF THE PRE- CONSTRUCTION CONFERENCE.
6. AT LOCATIONS WHERE CLEARING IS INDICATED ON THE PLANS BEYOND THE LIMITS OF THE PROPOSED EXCAVATION OR EMBANKMENT, THE CONTRACTOR SHALL RESTORE THE DISTURBED EARTH BY BLADING AND SHAPING TO BLEND WITH THE ADJACENT GROUND. THE CLEARING WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF THE EXCAVATION PAY ITEMS IN THE PLANS. PAYMENT FOR RESEEDING OR RESODDING WILL BE AS PROVIDED IN THE PLANS.
7. a) BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL J.U.L.I.E. AT 1-800-892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED FACILITIES. 48 HOURS NOTIFICATION IS REQUIRED.  
b) THE INFORMATION SHOWN ON THESE DRAWINGS CONCERNING THE TYPE AND LOCATION OF UNDERGROUND UTILITIES IS NOT GUARANTEED TO BE ACCURATE OR ALL INCLUSIVE. THE CONTRACTOR IS RESPONSIBLE FOR MAKING HIS OR HER OWN DETERMINATION AS TO THE TYPE AND LOCATION OF UNDERGROUND UTILITIES AS MAY BE NECESSARY TO AVOID DAMAGE HERETO.  
c) THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, LOGAN TOWNSHIP, AND PEORIA COUNTY.
8. PRIOR TO THE USE OF ANY PROPOSED BORROW AREAS, USE AREAS (TEMPORARY ACCESS ROADS, DETOURS, RUNAROUNDS, ETC.) AND/OR WASTE AREAS, THE CONTRACTOR SHALL FILE THE REQUIRED ENVIRONMENTAL RESOURCE REQUEST SURVEYS ACCORDING TO SECTION 107.22 OF THE STANDARD SPECIFICATIONS. THESE SURVEYS ARE REQUIRED IN ORDER FOR THE DEPARTMENT TO CONDUCT CULTURAL AND BIOLOGICAL RESOURCE SURVEYS FOR THE PROPOSED SITE.

**GENERAL NOTES CONT'D.**

9. PRIOR TO ANY WASTE MATERIALS BEING REMOVED FROM THE CONSTRUCTION SITE, THE REQUIRED ENVIRONMENTAL RESOURCE SURVEYS WILL NEED TO BE OBTAINED AND FILED BY THE CONTRACTOR. EXCESS WASTE PRODUCTS REMOVED FROM THE CONSTRUCTION SITE SHALL BE DISPOSED OF AS REQUIRED IN SECTION 202.03 OF THE STANDARD SPECIFICATIONS.

ANY PROTRUDING METAL BARS SHALL BE REMOVED PRIOR TO THE DISPOSAL OF BROKEN CONCRETE AT APPROVED DISPOSAL SITES.

THE REQUIRED ENVIRONMENTAL RESOURCE DOCUMENTATION SHALL INCLUDE THE FOLLOWING:

- BDE FORM 2289 (ENVIRONMENTAL SURVEY REQUEST)
- A LOCATION MAP SHOWING THE SIZE LIMITS AND LOCATION OF THE USE AREA
- SIGNED PROPERTY OWNER AGREEMENT FORM - D4 P10101
- COLOR PHOTOGRAPHS DEPICTING THE USE AREA
- BORROW AREA ENTRY AGREEMENT FORM - D4 P10101.

PLEASE NOTE THAT A MINIMUM OF TWO WEEKS SHALL BE ALLOWED FOR THE DISTRICT TO OBTAIN THE REQUIRED ENVIRONMENTAL CLEARANCES

10. ALL SLOPES STEEPER THAN 3 TO 1 AND OVER 15 FT. (4.5 M) IN HEIGHT SHALL BE RIPPED. THIS SHALL CONSIST OF RIPPING BETWEEN 18 INCHES (450 MM TO 600 MM) DEEP NORMAL TO THE SLOPE. THE INTERVAL OF RIPPING ALONG THE SLOPE SHALL BE 12 FT (3.6 M). THIS WORK SHALL BE DONE AFTER THE SEED BED HAS BEEN PREPARED BUT BEFORE ANY FERTILIZER OR SEED HAS BEEN APPLIED. THE FERTILIZER AND SEED SHALL BE APPLIED WITHIN A 24-HOUR PERIOD AFTER THE RIPPING HAS BEEN DONE. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT WILL BE INCLUDED IN THE COST OF THE VARIOUS ITEMS OF SEEDING INVOLVED.
11. ADD THE FOLLOWING SENTENCE TO THE END OF PARAGRAPH 670.01(I) AND 670.04(E): ALL OF THE TELEPHONE LINES PROVIDED SHALL HAVE UNPUBLISHED NUMBERS.
12. THE ENGINEER SHALL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE VARIOUS BITUMINOUS LIFTS.
13. THE BITUMINOUS MATERIAL PRIME COAT (USED ON AGGREGATE) QUANTITIES HAVE BEEN DETERMINED USING AN APPLICATION RATE OF 0.5 GAL/SY (2.0 L/M<sup>2</sup>). THE POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT) (USED ON THE BINDER COURSE BETWEEN LIFTS) QUANTITIES HAVE BEEN DETERMINED USING A RATE OF 0.05 GAL/SY (0.5 L/M<sup>2</sup>). SEE TABLE ON SHEET NO. 9.
14. FERTILIZER NUTRIENTS SHALL BE APPLIED AT A RATE OF 90 LBS/ACRE. TEMPORARY EROSION CONTROL SEEDING SHALL BE APPLIED AT A RATE OF 100 LBS/ACRE. MULCH SHALL BE APPLIED AT A RATE OF 2 TONS/ACRE.

INFRASTRUCTURE  
 ENGINEERING | CONSULTANTS  
 455 East Street, Suite 105 | Peoria, IL 61611  
 TEL: 309.241.1111 | FAX: 309.241.1112



FILE NAME : #FILES#	DESIGNED - AJP	REVISED -	<b>PEORIA COUNTY HIGHWAY DEPARTMENT</b>	<b>INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES AND COMMITMENTS</b>		F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
USER NAME : IEJ	DRAWN - AJP	REVISED -		1381	10-00005-03-BR	PEORIA	55	2			
PLOT SCALE : 2.0000' / 1" =	CHECKED - BAR	REVISED -		SCALE : N/A		SHEET NO. 1 OF 1 SHEETS		STA. N/A		CONTRACT NO. 89464	
PLOT DATE : 10/20/2012	DATE - 11/02/2012	REVISED -		ILLINOIS FED. AID PROJECT							