

INDEX OF SCHEDULES

		SEE SHEET
1	EARTHWORK	10
2	PAVEMENT	10
3	SEEDING	10
4	TREE REMOVAL AND RELATED ITEMS	10
5	EROSION CONTROL	11
6	GUARDRAIL	11
7	PAVEMENT MARKING	11
8	LUMP SUM ITEMS	11

1. SCHEDULE OF EARTHWORK

FROM	TO	20200100 EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE EXCESS (+) OR SHORTAGE(-) CU YD	20400800 FURNISHED EXCAVATION CU YD	21101615 TOPSOIL FURNISH AND PLACE, 4" SQ YD
SMITHVILLE ROAD							
196+40	199+48	1,936	1,452	629	822		1,570
BRIDGE CONES		18	14	313	-300		0
200+70	203+67	863	647	1,698	-1,052		3,155
TOTAL		2,820	2,112	2,641	-529	530	4,725

2. SCHEDULE OF PAVEMENT ITEMS

FROM	TO	31101810 SUBBASE GRANULAR MATERIAL, TYPE B 12" SQ YD	31102100 SUBBASE GRANULAR MATERIAL, TYPE C 4" SQ YD	40600100 BITUMINOUS MATERIALS (PRIME COAT) GALLON	40600115 POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT) GALLON	40603080 HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 TON
SMITHVILLE ROAD						
196+40.20	199+52.75	232	416	316	64	36
200+55.25	203+66.59	180	454	311	63	28
TOTAL		412	870	627	127	64

2. SCHEDULE OF PAVEMENT ITEMS

FROM	TO	40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 TON	44000100 PAVEMENT REMOVAL SQ YD	44004000 PAVED DITCH REMOVAL FOOT	48203017 HOT-MIX ASPHALT SHOULDERS, 5" SQ YD	X0322584 REVETMENT MAT REMOVAL SQ YD
SMITHVILLE ROAD						
196+40.20	199+52.75	24	258	201	416	128
200+55.25	203+66.59	19	216	0	454	0
TOTAL		43	474	201	870	128

3. SCHEDULE OF SEEDING ITEMS

FROM	TO	25000300 SEEDING, CLASS 3 ACRE	25000400 NITROGEN FERTILIZER NUTRIENT POUND	25000500 PHOSPHORUS FERTILIZER NUTRIENT POUND	25000600 POTASSIUM FERTILIZER NUTRIENT POUND	25100115 MULCH, METHOD 2 ACRE
SMITHVILLE ROAD						
196+40.20	199+52.75	0.53	49	49	49	0.53
200+55.25	203+66.59	0.72	65	65	65	0.72
TOTAL		1.25	114	114	114	1.25

4. SCHEDULE OF TREE REMOVAL

FROM	TO	20100500 TREE REMOVAL, ACRES ACRE
SMITHVILLE ROAD		
196+40.20	199+52.75	0.53
200+55.25	203+66.59	0.33
TOTAL		1.25

NOTES: SEE STRUCTURAL SHEETS 23 - 37 FOR STRUCTURAL QUANTITIES THAT ARE NOT NOTED THE SCHEDULE OF QUANTITIES.