

CONTRACT NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
89585	*	MARSHALL COUNTY	16	3
* SECTION 10-00001-00-SW		ILLINOIS		

CODE NO.	ITEM	ITEM	TOTAL QUANTITY
20101200	TREE ROOT PRUNING	EACH	5
21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SQ YD	1947
25000110	SEEDING, CLASS 1A	ACRE	0.30
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	30
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	30
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	30
35101598	AGGREGATE BASE COURSE, TYPE B 3"	SQ YD	2911
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	139
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	139
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	22106
42400800	DETECTABLE WARNINGS	SQ FT	232
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	374
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	180
44000600	SIDEWALK REMOVAL	SQ FT	18008
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	300
6700000	MOBILIZATION	L.SUM	1
70102620	TRAFFIC CONTROL & PROTECTION, STANDARD 701501-05	L.SUM	1
70102640	TRAFFIC CONTROL & PROTECTION, STANDARD 701801-05	L.SUM	1
72000100	SIGN PANEL, TYPE 1	SQ FT	33
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	235
* 87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 15 FT	EACH	2
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6
* 88500100	PEDESTRIAN PUSH-BUTTON	EACH	2
* X7830078	GROOVING FOR RECESSED PAVEMENT MARKINGS 13"	EACH	235
* XX007021	PEDESTRIAN ACTIVATED CROSSWALK WARNING SYSTEM	EACH	1

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE
KED	11/5/12

SUMMARY OF QUANTITIES

SCALE: AS NOTED DRAWN BY: KED
DATE: 2011 CHECKED BY: SMK
FILE: G:\Drawings\Wenona\10-0001-00-SW Route\03 QTY.dwg