

HMA RESURFACING SCHEDULE

STATION	HMA BASE	HMA BASE	BIT. MATL.	AGGR.	LEVEL BIND.	HMA	HMA	HMA	HMA	HMA	HMA	HMA	STRIP	TEMP.
	CSE. 6 1/2" SQ YD	CSE. WID. 11" SQ YD	PRIME COAT GALLON	PRIME COAT TON	MACHINE METHOD TON	BIND. CSE. IL-19.0 FG, N70 TON	SURF. CSE. MIX C, N70 TON	SHLD. 8" SQ SY	SHLD. TON	SURF. REM. 3/4" SQ YD	SURF. REM. 1 1/2" SQ YD	SURF. REM. BUTT-JT. SQ YD	REFL. CRK. CONT. FOOT	RAMP SQ YD
													2479	
RT. STA. 78+87 (ST. JAMES RD.)	164						14							
LT. STA. 146+67 (N. SCHILLER ST.)	183						15							
RT. STA. 145+67 (S. SCHILLER ST.)	103						9							
LT. STA. 150+21 (PRAIRIETOWN RD.)	123						10							
RT. STA. 150+21 (PRAIRIETOWN RD.)	183						15							
RT. STA. 154+76 (WASHINGTON ST.)	106						9							
LT. & RT. STA. 4+02 - 16+00		895											2444	
LT. STA. 20+34 - 21+21		31											87	
RT. STA. 20+61 - 21+21		22											60	
LT. & RT. STA. 29+72 - 30+10		28											76	
LT. & RT. STA. 37+50 - 54+50		1228											3400	
LT. STA. 56+53 - 57+23		25											70	
RT. STA. 56+69 - 57+13		16											44	
LT. & RT. STA. 63+75 - 150+15		6240											17280	
LEVEL BINDER LIFT			1510	30										
BINDER LIFT			3798	76										
SURFACE LIFT			3968	79										
STA. 13+50 - 22+00					486									
STA. 28+50 - 40+50					819									
STA. 40+00 - 45+00					115									
STA. 45+00 - 53+00					727									
STA. 56+00 - 67+00					673									
STA. 67+14 - 78+63					236									
STA. 4+52 - 23+50						623								
STA. 28+25 - 55+50						912								
STA. 55+75 - 150+50						3204								
STA. 4+02 - 24+35							428							
STA. 2605 - 155+75							2905							
STA. 4+02 - 21+50								3202						
STA. 21+50 - 24+35								90						
STA. 26+05 - 29+00								72						
STA. 29+00 - 54+50								4532						
STA. 54+50 - 56+09								24						
STA. 56+09 - 155+75								16700						
STA. 4+02 - 5+52											636		25	
STA. 5+52 - 23+25									4826					
STA. 23+25 - 24+35										293			8	
STA. 26+05 - 28+50										653			8	
STA. 28+50 - 55+00									7214					
STA. 55+00 - 56+25										333				
STA. 56+25 - 150+25									25589					
STA. 150+25 - 155+75										1467			8	
STA. 21+50 - 23+25 (SHOULDER)									312					
STA. 23+25 - 24+35 (SHOULDER)										196			6	
STA. 26+05 - 28+05 (SHOULDER)										436			6	
STA. 28+50 - 29+00 (SHOULDER)									88					
STA. 54+50 - 55+00 (SHOULDER)									88					
STA. 55+00 - 56+09 (SHOULDER)										194				
TOTALS	862	8485	9276	185	3056	4739	3405	24434	186	38117	3572	636	25940	61

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 5 OF 7 SHEETS

ROUTE NO. E.A.S. 2735	SECTION 03-00053-01-WR	COUNTY MADISON	TOTAL SHEETS 145	SHEET NO. 15
			CONTRACT NO. 97509	