



EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	CHANNEL EXCAVATION	ESTIMATED UNSUITABLE MATERIAL	SUITABLE MATERIAL ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
STA 0+00 TO 4+64.3	416.1	0.0	0.0	312.1	354.0	-41.9
STA 4+64.3 TO 5+35.7	0.0	424.5	212.2	159.2	0.0	159.2
STA 5+35.7 TO 10+00	94.4	0.0	0.0	76.8	530.8	-460.0
1 FIELD ENTRANCE	0.0	0.0	0.0	0.0	7.4	-7.4
TOTAL	510.5	424.5	212.2	542.1	892.2	-350.1

CH	SECTION	COUNTY	TOTAL SHEETS
11	10-00118-03-B4	WHITE	12 3
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	
PROJECT#	BR05-193058	CONTRACT#	89467
JOB NO.	C-99-5 9-11	SEVEN MILE CREEK	

323 W. 3RD. ST.
P.O. BOX 160
MT. CARMEL, IL
62863
PHONE:
(618)-262-6651
(618)-263-3327

405 W. STATE ST.
SUITE
PRINCETON, IN
47670
PHONE:
(812)-388-7611
FAX:
(812)-385-2512

PROFESSIONAL DESIGN - ILM
LAND SURVEY &
PROFESSIONAL
ENGINEERING
CORPORATION
181-000887
(63 032435)(35-002769)

AARON M. McFERRON
NAME
Aaron M. McFerron
SIGNATURE
10-29-12
DATE
10-29-12
EXPIRES

C.H. 11
OVER SEVEN MILE CREEK
WHITE COUNTY, ILLINOIS

SHEET TITLE
CROSS-SECTIONS
SCALE: 1" = 5'
BY: AMM
DATE: 10/29/12
REV:
3 OF 12
SHEETS
SHEET NO.
3

