

CODE NO.	ITEM	UNIT	100% STATE		CONSTRUCTION CODE	
			TOTAL QUANTITY	0005 COLES CO.	0005 SHELBY CO.	
35800100	PREPARATION OF BASE	SQ YD	9700	0	9700	
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	42	0	42	
40300405	POLYMERIZED BITUMINOUS MATERIALS (COVERS AND SEAL COATS)	TON	380	296	84	
40300500	COVER COAT AGGREGATE	TON	1572	1219	353	
40300600	SEAL COAT AGGREGATE	TON	1572	1219	353	
67100100	MOBILIZATION	L SUM	1	0.75	0.25	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.75	0.25	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.75	0.25	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	11888	11888	0	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	123	123	0	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	600	600	0	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	126	126	0	⚠
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	176538	176538	0	
Z0055500	RUMBLE STRIP	SQ FT	806	806	0	

\* SPECIALTY ITEM

⚠ REV. 1-2-2019

REV. - MS

MODEL: Default  
FILE NAME: \\s:\11084\BID\INTEG.ILLINOIS.GOV\PWIDOT\Documents\DOT\_Offices\District 7\Projects\74889\CAD\Drawn\CADsheets\74889-sht-500.dgn

USER NAME = steffenmk	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 10/15/2018	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	D7 SEAL COAT 2019-2	COLES/SHELBY	8	3
			CONTRACT NO. 74889	
ILLINOIS FED. AID PROJECT				