

ILLINOIS DEPARTMENT OF TRANSPORTATION			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0013	CONSTRUCTION TYPE CODE 0010	CONSTRUCTION TYPE CODE 0013	CONSTRUCTION TYPE CODE 0010
CODE NO	ITEM	UNIT		SN 051-0012	SN 051-0013 SN 051-8634	SN 051-0014	SN 051-0015 SN 051-0066
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, FOOT POSTS	6 FOOT	2675.5	763	825	450	637.5
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	12	4		4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	12	2	2	4	4
63200310	GUARDRAIL REMOVAL	FOOT	3059	1082	557	710	710
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1				1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	28	5	5	5	13
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	28	5	5	5	13
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	3	1		1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.25	0.25	0.25	0.25
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1				1

* SPECIALTY ITEM

△ REV. 1-9-2019

REV. - MS

MODEL: Default
FILE NAME: p:\110848E\BID\NTEG_illinois.gov\PWIDOT\Documents\DOT_Offices\District 7\Projects\74177\CaddData\CaddSheets\74177-4B-500.dgn

USER NAME = steffennk	DESIGNED - BRETT WALKER	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 10/23/2018	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 8 OF 12 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	(51-23)B		260	11
			CONTRACT NO. 74177	
ILLINOIS FED. AID PROJECT				

PAVING SCHEDULE			LENGTH	PAVEMENT WIDTH	SHOULDER WIDTH - RT (INCLUDES WIDENING)	SHOULDER WIDTH - LT	BITUMINOUS MATERIALS(TACK COAT)	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N90	HOT-MIX ASPHALT SHOULDERS, 8"	AGGREGATE WEDGE SHOULDERS, TYPE B
STATION	TO	STATION	FEET	FEET	FEET	FEET	POUND	SQ YD	TON	SQ YD	TON
570+50.00		570+80.00	30.0	36.0	12.0	10.6	52.2	120.0	13.4	45.3	9.1
570+80.00		572+78.00	198.0	28.0-36.0	12.0	10.6	380.2	704.0	78.8	299.2	60.1
572+78.00		575+57.00	279.0	28.0	12.0	10.6	418.5	868.0	97.2	421.6	84.7
575+57.00		575+72.00	15.0	28.0	13.0	11.0				22.7	4.6
575+72.00		576+02.00	30.0	28.0	13.0	11.0				45.3	9.1
576+02.00		577+70.00	168.0	28-26	13-15	11-12					
577+70.00		578+00.00	30.0	26.0	15.0	12.0				50.0	9.1
578+00.00		578+15.00	15.0	26.0	15.0	12.0				25.0	4.6
578+15.00		581+92.00	377.0	26-24	15.0	12.0	531.6	1,047.2	117.3	628.3	114.5
TOTALS			1,142				1,382	2,739	307	1,537	296



GUARDRAIL SCHEDULE				STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL, TYPE 6
STATION	TO	STATION		FEET	EACH	EACH
574+22		574+72	RT		1	
574+72		575+50	RT	75		
575+50		575+87	RT			1
574+75		575+25	LT		1	
575+25		575+51	LT	25		
575+51		575+88	LT			1
577+85		578+22	LT			1
578+22		581+85	LT	363		
577+86		578+23	RT			1
578+23		581+22	RT	300		
TOTALS				763	2	4

PAVEMENT MARKING SCHEDULE												
STATION	TO	STATION	LENGTH FEET	PAINT PAVEMENT MARKING - LINE 4" FEET	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4" FEET	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12" FEET	GROOVING FOR RECESSED PAVEMENT MARKING 5" FEET	GROOVING FOR RECESSED PAVEMENT MARKING 13" FEET	SHORT-TERM PAVEMENT MARKING FEET	SHORT-TERM PAVEMENT MARKING REMOVAL SQ FT	TEMPORARY PAVEMENT MARKING - LINE 4" FEET	RAISED REFLECTIVE PAVEMENT MARKER EACH
570+50.00		570+80.00	30	120					32	11	120	
570+80.00		572+78.00	198	792					160	53	792	
572+78.00		575+57.00	279	1116					224	75	1116	
575+57.00		575+72.00	15	60					5	2	60	
575+72.00		576+02.00	30		180	10	180	10	32	11	190	
576+02.00		577+70.00	168		1008	27	1008	27	128	43	1035	
577+70.00		578+00.00	30		180		180		32	11	180	
578+00.00		578+15.00	15	60					5	2	60	
578+15.00		581+92.00	377	1414					270	90	1414	10
TOTALS			1,142	3,562	1,368	37	1,368	37	888	296	4,967	10

REV. 1-9-2019

MODEL: Default
 FILE NAME: P:\ILLINOIS\BID\BIDDING\ILLINOIS\POV\PWIDOT\Documents\BIDDING\Office\BIDDING\74177\CADDData\CAD\Bidders\ID74177\pvc-schedule

USER NAME = steffenmk	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 1/8/2019	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SN 051-0012
SCHEDULES OF QUANTITIES

SCALE: SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	(51-23)B	LAWRENCE	260	17
CONTRACT NO. 74177				
ILLINOIS FED. AID PROJECT				