

M:\2017\17-123-000\_EFK\_Moen\_IDOT\_DUR\_PTB\_181-4\17-123-013\_WD\_13\_Ashland\_Ave-135th\_St\_Brdg\_Rem1 (on\_Plan)\Design\_Plan\Printing\_0NL\1\Transportation\CADD\CADD\_Sheets\0112154-sht-500.dgn

SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES	
					URBAN	
					ROADWAY 0005	BRIDGE 0010
	64300240	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	3	3	
	64301090	ATTENUATOR BASE	SQ YD	24	24	
	<del>66407700</del>	<del>CHAIN LINK GATES, 6' X 14' DOUBLE</del>	<del>EACH</del>	<del>1</del>	<del>1</del>	
	66408200	CHAIN LINK GATES, 6' X 24' DOUBLE	EACH	1	1	
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	950	950	
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4	
*	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	LSUM	1	1	
*	66901002	ON-SITE MONITORING OF REGULATED SUBSTANCES	CAL DA	15	15	
*	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	LSUM	1	1	
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	
	67100100	MOBILIZATION	LSUM	1	1	
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	980	980	
	70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	326	326	
	70300904	PAVEMENT MARKING TAPE, TYPE IV 4"	FOOT	12369	12369	
	70300924	PAVEMENT MARKING TAPE, TYPE IV 24"	FOOT	24	24	

1

\* SPECIALTY ITEM

REV. - MS



USER NAME = DavidL	DESIGNED - BCB	REVISED -
	DRAWN - BCB	REVISED -
PLOT SCALE =	CHECKED - DPA	REVISED -
PLOT DATE = 10/15/2018	DATE - 10/17/14	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

135TH ST (JACKSON ST) OVER ASHLAND AVE (SN 016-1004 REMOVAL)  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. 7 OF 11 SHEETS STA. TO STA.

F.A.U. RTE. 2857	SECTION 146B-BR	COUNTY COOK	TOTAL SHEETS 94	SHEET NO. 10
CONTRACT NO. 60484				
ILLINOIS FED. AID PROJECT				

1 REV 1/8/2019

M:\2017\17-129-000\_EFK\_Moen\_IDOT\_DUR\_PTB\_181-4\17-129-013\_WD\_13\_Ashland\_Ave-135th\_St\_Brdg\_Remj\_Con\_Plan\Design\_For\_Printing\_01\17-Transportation\CADD\CADD\_Sheets\0112154-sht-500.dgn

SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES	
					URBAN	
					ROADWAY 0005	BRIDGE 0010
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	1100	1100	
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	475	475	
	<del>70600235</del>	<del>IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE), TEST LEVEL 2</del>	<del>EACH</del>	<del>2</del>	<del>2</del>	
	70600240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
	70600340	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
	* 72000100	SIGN PANEL - TYPE 1	SQ FT	8.0	8.0	
	* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	12.5	12.5	
	* 72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	16.0	16.0	
	* 72501000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3	
	* 72900100	METAL POST - TYPE A	FOOT	26	26	
	* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5413	5413	
	* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	198	198	
	* 78200006	GUARDRAIL REFLECTORS, TYPE B	EACH	7	7	
	* 78200011	BARRIER WALL REFLECTORS, TYPE C	EACH	15	15	
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	198	198	

①

\* SPECIALTY ITEM

① REV. 1-3-2019

REV. - MS



USER NAME = DavidL	DESIGNED - BCB	REVISED -
	DRAWN - BCB	REVISED -
PLOT SCALE =	CHECKED - DPA	REVISED -
PLOT DATE = 10/12/2018	DATE - 10/17/14	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

135TH ST (JACKSON ST) OVER ASHLAND AVE (SN 016-1004 REMOVAL)  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. 8 OF 11 SHEETS STA. TO STA.

F.A.J. RTE. 2857	SECTION 146B-BR	COUNTY COOK	TOTAL SHEETS 94	SHEET NO. 11
CONTRACT NO. 60484				
ILLINOIS FED. AID PROJECT				