

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	2006-028 DM	VARIOUS	35	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

CONTRACT NO. 60B74

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2-3	LOCATION MAPS
4	INDEX OF SHEETS, STATE STANDARDS, GENERAL NOTES AND SCHEDULE OF QUANTITIES
5	SUMMARY OF QUANTITIES
6-12	DEMOLITION PLANS & SITE CLEANUP PLANS
13-18	LANDSCAPING PLANS
19-25	RIGHT-OF-WAY PLAT OF HIGHWAYS (FOR INFORMATION ONLY)
26-33	BUILDING ASBESTOS LOCATION DETAILS (FOR INFORMATION ONLY)
34	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
35	SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS

STATE STANDARDS

000001-04	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
701101-01	OFF ROAD OPERATIONS, MULTILANE LESS THAN 4.5M (15') AWAY FOR SPEEDS > 45 MPH
701106-01	OFF ROAD OPERATIONS, MULTILANE MORE THAN 4.5M(15') AWAY FOR SPEEDS > 45 MPH
701801-03	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
702001-06	TRAFFIC CONTROL DEVICES

GENERAL NOTES:

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OR BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION REQUIRED)
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, THE CITIES OF JOLIET, LOCKPORT, MCHENRY, CHICAGO, AND VILLAGES OF MUNDELEIN, HAWTHORN WOODS, HANOVER PARK, AND LONG GROVE.
- THE CONTRACTOR WILL NOT BE ABLE TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT THE WRITTEN PERMISSION OF THE DEPARTMENT.
- BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADES USED- ONE (1) WEIGHTED SAND BAG ACROSS EACH BOTTOM RAIL.
- BACKFILL USED FOR ANY HOLES, SUCH AS BASEMENTS, SHALL BE FILLED WITH POROUS GRANULAR EMBANKMENT AND SHALL BE INCLUDED IN THE COST OF BUILDING REMOVAL.
- CONTRACTOR IS RESPONSIBLE FOR OBTAINING A DEMOLITION PERMIT FROM THE CITY OR VILLAGE WHERE THE DEMOLITION WILL TAKE PLACE.
- CONTRACTOR MUST CONTACT THE APPROPRIATE CITY OR VILLAGE FOR CORRESPONDING UTILITY DISCONNECTION REQUIREMENTS.
- ALL TRAFFIC CONTROL SHALL BE INCLUDED IN THE PAY ITEMS FOR BUILDING REMOVAL AND DEBRIS REMOVAL.

SCHEDULE OF QUANTITIES

LOCATION	TOPSOIL FURNISH & PLACE, 4" (SQ YD)	SEEDING, CLASS 2 (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH, METHOD 1 (ACRE)
LOCATION #1	45	0.01	0.9	0.9	0.9	0.01
LOCATION #2	296	0.10	5.4	5.4	5.4	0.10
LOCATION #3	214	0.09	3.6	3.6	3.6	0.09
LOCATION #4	222	0.10	4.5	4.5	4.5	0.10
LOCATION #5	267	0.10	5.4	5.4	5.4	0.10
LOCATION #6	499	0.10	9.0	9.0	9.0	0.10
TOTAL =	1543	0.50	28.8	28.8	28.8	0.50

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**BUILDING DEMOLITION  
VARIOUS LOCATIONS**  
**INDEX OF SHEETS STATE STANDARDS  
GENERAL NOTES AND  
SCHEDULE OF QUANTITIES**

SCALE: VERT.  
HORIZ.  
DATE 11/8/2006

DRAWN BY AA  
CHECKED BY