

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2005-025 RS	LAKE	120	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
* PARK ROADS		IDNR File No. 2-03-025A D91-191-04		

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY	JUNCTION CHAMBER	LIGHTING		
				I000	Y007	Y030-1E		
60200105	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3	3				
60200205	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60201340	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 24 FRAME AND GRATE	EACH	5	5				
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2				
60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1				
60266600	VALVE BOXES TO BE ADJUSTED	EACH	3	3				
60500050	REMOVING CATCH BASINS	EACH	1	1				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	462	462				
61000215	PORTLAND CEMENT CONCRETE SHOULDERS	SQ YD	73	73				
63200310	GUARDRAIL REMOVAL	FOOT	26		26			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9				
67100100	MOBILIZATION	L SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1				
78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	563	563				
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	13598	13558	40			
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	1665	1665				
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	690	690				
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	299	299				
* 81000300	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	3000			3000		
* 81400115	HANDHOLE TO BE ADJUSTED	EACH	1	1				
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3000			3000		
* 81700105	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 12	FOOT	3500			3500		
* 81700115	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 8	FOOT	3500			3500		
* 81800740	AERIAL CABLE, 3-1/C NO. 8, ALUMINUM, WITH MESSENGER WIRE	FOOT	150			150		
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	130			130		

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY	JUNCTION CHAMBER	LIGHTING		
				I000	Y007	Y030-1E		
* 84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	13			13		
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	13			13		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	75	75				
* A2006616	TREE, QUERCUS IMBRICARIA (SHINGLE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	9	9				
* A2016614	TREE, QUERCUS ELLIPSOIDALIS (HILL'S OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	5	5				
X0300247	REMOVE WOOD POST	EACH	30	30				
X0300894	PIPE CULVERT REMOVAL 18"	FOOT	130	130				
X0301339	REMOVE EXISTING PARKING BLOCKS	EACH	40	40				
X0321083	PLASTIC CAR BUMPER	EACH	225	225				
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	3	3				
* X0321566	MULCH, SPECIAL	SQ YD	18929	18929				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	25.7	25.7				
X0322720	CAST IRON STEPS	EACH	4		4			
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	3	2	1			
X0323359	WASHING AND CLEANING	L SUM	1	1				
X0323388	TRAFFIC COUNTER	EACH	3	3				
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	500		500			
X0324010	SKIRTED STEEL GRATING COVER	EACH	1		1			
X0325225	BRICK PAVEMENT REMOVAL AND REPLACEMENT	SQ FT	50	50				
X0325232	SWING GATE DOUBLE, 22'	EACH	6	6				
X0325444	TEMPORARY CONCRETE BARRIER (INSTALL ONLY)	FOOT	48	48				
X0448400	PIPE CULVERT REMOVAL 12"	FOOT	210	210				
X0795800	COARSE AGGREGATE	TON	24		24			
X2010300	TREE REMOVAL (UNDER 6 UNITS DIAMETER)	UNIT	101	101				
* X2110104	TOPSOIL FURNISH AND PLACE, 4" (SPECIAL)	SQ YD	19014	18929	85			
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1700	1700				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
NORTH POINT MARINA

Rev.

10/31/2006 10:45:00 AM