

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
342	(G&I) 1-N-1	LAKE	70	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		90% FED 10% STATE URBAN 1000-IA				
55101400	STORM SEWER REMOVAL 30"	FOOT	10	10				
552A0800	STORM SEWERS JACKED IN PLACE, CLASS A 21"	FOOT	156	156				
60107600	PIPE UNDERDRAINS 4"	FOOT	35	35				
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2				
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1				
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	2	2				
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	2	2				
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1				
60255700	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1				
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60500060	REMOVING INLETS	EACH	1	1				
60603300	GUTTER OUTLET	EACH	1	1				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 24	FOOT	777	777				
60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2. 24	FOOT	991	991				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8				
67100100	MOBILIZATION	L SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	13	13				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1809	1809				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	471.9	471.9				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7074	7074				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2503	2503				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		90% FED 10% STATE URBAN 1000-IA	90% FED. 6.7% STATE 3.3% COUNTY TRAFFIC Y031-1F	OPTICOM VILLAGE OF GURNEE 100% Y031-3D		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	108	108				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	121	121				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3805	3805				
72000200	SIGN PANEL - TYPE 2	SQ FT	31.75		31.75			
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	471.9	471.9				
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7074	7074				
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2503	2503				
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	108	108				
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	121	121				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	85	85				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	18	18				
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	624		624			
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	165		165			
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	65		65			
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	280		280			
81400100	HANDHOLE	EACH	3		3			
81400200	HEAVY-DUTY HANDHOLE	EACH	3		3			
81400300	DOUBLE HANDHOLE	EACH	1		1			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	934		934			
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1			
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	800			800		
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3231		3231			

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

10/14/2006 10:14:20 AM C:\p0101003\p0101003.dwg