64563

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5564	111-M-1	WHITESIDE	78	20
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

EXIST. CURVE 200
PI STA. = 1536+10.60
Δ = 24° 03' 51" (LT)
D = 0° 52' 01"
R = 6,608.56'
T = 1,408.57'
L = 2,775.60'
E = 148.45'
e = -----
T.R. = -----
S.E. RUN = -----
P.C. STA. = 1522+02.03
P.T. STA. = 1549+77.63

COM ED

CHARLES E. SHUMAN

CONTAMINATED SOIL LOCATION

REMOVE EXISTING CULVERTS

56'-PIPE CULVERTS, CLASS D, TYPE 1, 18"
2 EACH END SECTIONS 18"

56'-PIPE CULVERTS, CLASS D, TYPE 1, 15"
2 EACH END SECTIONS 15"

TEMPORARY EASEMENT

TEMP EASEMENT

PROPOSED R.O.W.

IMPROVEMENT BEGINS
STA 1531+30

EXIST ROW

CONSTRUCTION LIMITS

1' STUB

8' BITUMINOUS SHOULDERS

50' BITUMINOUS TAPER

CE+22

CE+36

2.5' Excavation
1071-3C

3' Excavation
1071-3B

1' Fill
1071-3A

35'

18" CMP

18" CONCRETE

13'

14'

US RTE 30

MATCH LINE STA. 1537+50

SECTION BEGINS
STA 1532+23.50

FE+00

56'-PIPE CULVERTS, CLASS D, TYPE 1, 15"
2 EACH END SECTIONS 15"

4' BITUMINOUS SHOULDERS

COM ED

WILLIAM G. MANFIELD, ET AL

X = TREE REMOVAL

0 50' 100'

PLAN
SURVEYED BY
PLOTTED
CHECKED
NOTE BOOK
NO.
DATE

PROFILE
SURVEYED BY
PLOTTED
CHECKED
NOTE BOOK
NO.
DATE

STA 1531+30 TO 1537+50
EARTH EX = 1385 CU YDS
EMBANKMENT = 716 CU YDS
WASTE = 323 CU YDS

+0.30%

+0.50%

SPECIAL DITCH RIGHT

SPECIAL DITCH LEFT

	1531+50	1532+00	1532+50	1533+00	1533+50	1534+00	1534+50	1535+00	1535+50	1536+00	1536+50	1537+00	1537+50
EXIST	643.86	643.92	643.97	644.01	644.02	644.04	644.05	644.07	644.08	644.09	644.11	644.14	644.16
PROP		643.92		644.04	644.17	644.25	644.26	644.28	644.29	644.30	644.32	644.35	644.37
	644.19	644.23	644.28	644.34	644.39	644.42	644.46	644.49	644.53	644.57	644.62	644.67	
	644.40	644.44	644.49	644.54	644.60	644.63	644.66	644.70	644.74	644.78	644.83	644.87	

655 650 645 640 635 630

DATE-TIME
DGN-SPEC
*REF-02
*REF11
*REF
*REF

US 30