

# SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
..30..	37-148R-1	HENRY	133	17
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

**42300300 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH**

SQ. YD.	LOCATION
155	STA. 39+75.46 PE-LT
155	TOTAL

**44000100 PAVEMENT REMOVAL**

SQ. YD.	LOCATION
1467	STA. 35+90 TO 42+50
711	STA. 60+50 TO 63+70
392	STA. 100+13 TO 100+85
97	STA. 101+13 TO 101+85
2667	TOTAL

PE-LT  
CARROLL ST - STAGE I  
CARROLL ST - STAGE II

**44000700 APPROACH SLAB REMOVAL**

SQ. YD.	LOCATION
88.9	STA. 50+26 TO 50+66
88.9	STA. 52+82 TO 53+22
178	TOTAL

**44004300 PAVEMENT BREAKING**

SQ. YD.	LOCATION
1725	STA. 42+50 TO 50+26
1618	STA. 53+22 TO 60+50
3343	TOTAL

**44201709 CLASS D PATCHES, TYPE III, 5"**

SQ. YD.	LOCATION
16.67	STA. 101+48 7.5' WIDE - CARROLL ST
16.67	TOTAL

**50100300 REMOVAL OF EXISTING STRUCTURES NO. 1**

EACH	LOCATION
1	STA. 51+74.40 POPPY GARDEN ROAD BRIDGE OVER I-80
1	TOTAL

**50100400 REMOVAL OF EXISTING STRUCTURES NO. 2**

EACH	LOCATION
1	STA. 461+11.67 36" GRATED END SECTION I-80 RT
1	TOTAL

**50100500 REMOVAL OF EXISTING STRUCTURES NO. 3**

EACH	LOCATION
1	STA. 462+25 36" GRATED END SECTION I-80 LT
1	TOTAL

**50102600 CONCRETE REMOVAL**

EACH	LOCATION
1	STA. 461+32 TO 461+66 I-80 CONCRETE PAD FOR SAND BARRELS
1	STA. 461+81 TO 462+15 I-80 CONCRETE PAD FOR SAND BARRELS
2	TOTAL

**50104400 CONCRETE HEADWALL REMOVAL**

EACH	LOCATION
1	STA. 461+26.25 85' LT I-80
1	STA. 462+35.46 93' RT I-80
2	STA. 60+59 LT & RT
4	TOTAL

**50105210 REMOVE EXISTING CULVERTS**

FOOT	LOCATION
73	STA. 60+58.59 30" CMP - AR CULVERT
87	STA. 100+41.28 30" CMP - AR CULVERT
124	STA. 461+12 TO 462+36 36" I-80 RT
100	STA. 461+26 TO 462+26 36" I-80 LT
384	TOTAL

**542A1075 PIPE CULVERTS, CLASS A, TYPE 2 30"**

FOOT	LOCATION
82	STA. 60+58.59 AR CULVERT
82	TOTAL

**542A1915 PIPE CULVERTS, CLASS A, TYPE 3 30"**

FOOT	LOCATION
106	STA. 46+00 AR CULVERT
106	TOTAL

**542A4021 PIPE CULVERTS, CLASS A, TYPE 6 36"**

FOOT	LOCATION
182	STA. 461+08 TO 462+90 I-80 RT
180	STA. 460+85 TO 462+65 I-80 LT
362	TOTAL

**542C1075 PIPE CULVERTS, CLASS C, TYPE 2 30"**

FOOT	LOCATION
10	STA. 100+41.28 CARROLL ST. - STAGE I
75	STA. 100+41.28 CARROLL ST.
85	TOTAL

PLOT DATE = Mon Dec 02 09:34:15 2008  
 PLOT SCALE = 50:0000 / IN.  
 USER NAME = reneka.j

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY

**SCHEDULE OF QUANTITIES**