

| F.A.P. RTE.               | SECTION   | COUNTY                    | TOTAL SHEETS | SHEET NO. |
|---------------------------|-----------|---------------------------|--------------|-----------|
| 635                       | (105)BR-2 | KANKAKEE                  | 25           | 4         |
| STA. _____                |           | TO STA. _____             |              |           |
| FED. ROAD DIST. NO. _____ |           | ILLINOIS FED. AID PROJECT |              |           |

| SUMMARY OF QUANTITIES |  |       |                | ← 80% FED 20% STATE → |      |
|-----------------------|--|-------|----------------|-----------------------|------|
| CODE NO.              | ITEM   | UNIT  | TOTAL QUANTITY | CONSTR TYPE CODE      |      |
|                       |  |       |                | ROADWAY I000          | Y007 |
| 70300100              | SHORT-TERM PAVEMENT MARKING                                    | FOOT  | 200.0          | 200.0                 |      |
| 70300220              | TEMPORARY PAVEMENT MARKING- LINE 4"                            | FOOT  | 1290.0         | 1290.0                |      |
| 70300240              | TEMPORARY PAVEMENT MARKING - LINE 6"                           | FOOT  | 162.0          | 162.0                 |      |
| • 70300520            | PAVEMENT MARKING TAPE, TYPE III 4"                             | FOOT  | 1252.0         | 1252.0                |      |
| 70301000              | WORK ZONE PAVEMENT MARKING REMOVAL                             | SQ FT | 458.0          | 458.0                 |      |
| 70400100              | TEMPORARY CONCRETE BARRIER                                     | FOOT  | 286.0          | 286.0                 |      |
| 70400200              | RELOCATE TEMPORARY CONCRETE BARRIER                            | FOOT  | 170.0          | 170.0                 |      |
| • 78001110            | PAINT PAVEMENT MARKING - LINE 4"                               | FOOT  | 1290.0         | 1290.0                |      |
| • 78001130            | PAINT PAVEMENT MARKING - LINE 6"                               | FOOT  | 162.0          | 162.0                 |      |
| • 78100100            | RAISED REFLECTIVE PAVEMENT MARKER                              | EACH  | 8.0            | 8.0                   |      |
| 78300100              | PAVEMENT MARKING REMOVAL                                       | SQ FT | 215.0          | 215.0                 |      |
| 78300200              | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL                      | EACH  | 8.0            | 8.0                   |      |
| X0324043              | GRATING FOR CONCRETE HEADWALL                                  | EACH  | 2.0            |                       | 2.0  |
| 35501320              | HOT-MIX ASPHALT BASE COURSE 9"                                 | SQ YD | 543.0          | 543.0                 |      |
| 35501332              | HOT-MIX ASPHALT BASE COURSE 12"                                | SQ YD | 185.0          | 185.0                 |      |
| 40603345              | HOT-MIX ASPHALT SURFACE COURSE, MIX'D, N90                     | TON   | 210.0          | 210.0                 |      |
| 40600645              | LEVELING BINDER (MACHINE METHOD), N90                          | TON   | 105.0          | 105.0                 |      |
| X7200201              | WIDTH RESTRICTION SIGNING                                      | L SUM | 1.0            | 1.0                   |      |
| ■ Z0030250            | IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3 | EACH  | 2.0            | 2.0                   |      |
| ■ Z0030350            | IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3  | EACH  | 2.0            | 2.0                   |      |
| Z0000990              | AGGREGATE FOR TEMPORARY ACCESS                                 | TON   | 10.0           | 10.0                  |      |
| △ X0325671            | PRECAST BOX CULVERT END SECTION 11' X 4'                       | EACH  | 2.0            |                       | 2.0  |

• SPECIALTY ITEMS  
 ■ SFTY-3N

△ REVISED 11/8/2007

# SUMMARY OF QUANTITIES