

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
B40	139 BR-1	KANKAKEE	69	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

SUMMARY OF QUANTITIES

←BHF→
X081-2A
←F→

CODE NUMBER	PAY ITEM	UNIT	PROJECT QUANTITY 80% / 20% Exp. St.	139 BR-1		139 BR-2	
				ROADWAY	BRIDGE	ROADWAY 1000	BRIDGE Y007
70100460	TRAFFIC CONTROL AND PROTECTION STANDARD 701306	L SUM	1	1	0.5		0.5
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	70	70	50		20
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	1		
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	6		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3152	3152	3152		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	26	26	26		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1102	1102	1102		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	517	517	517		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	517	517	517		
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	2626	626	1272		1354
* 78001130	PAINT PAVEMENT MARKING-LINE 6"	FOOT	405	405	235		170
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16	16	8		8
78200410	GUARDRAIL MARKERS, TYPE A	EACH	18	18	18		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	4		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	450	450	450		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16	16	8		8
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1			1
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1			1	
50104650	SLOPE WALL REMOVAL	SQ YD	800			800	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	48			48	
⊙ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2		
⊙ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2		

⊙ SFTY-3N
* SPECIALTY ITEM

PLOT DATE = 10/25/2006
FILE NAME = #FILE#
USER NAME = #USER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SCALE: VERT. DRAWN BY C. SUNTKEN
 HORIZ. CHECKED BY M. ZELINSKAS
DATE 10/13/2006