

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	139 BR-1	KANKAKEE	69	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SCHEDULE OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	PROJECT QUANTITY	139 BR-1	
				ROADWAY 1000	BRIDGE X081-2A
20200100	EARTH EXCAVATION	CU YD	175	175	
20400800	FURNISHED EXCAVATION	CU YD	85	85	
21101615	TOPSOIL FURNISH AND PLACE 4"	SO YD	970	970	
21400100	GRADING AND SHAPING DITCHES	FOOT	160	160	
25000300	SEEDING, CLASS 3	ACRES	0.2	0.2	
25000400	NITROGEN FERTILIZER NUTRIENTS	POUND	18	18	
25000500	PHOSPHORUS FERTILIZER NUTRIENTS	POUND	18	18	
25000600	POTASSIUM FERTILIZER NUTRIENTS	POUND	18	18	
25100115	MULCH, METHOD 2	ACRE	0.20	0.2	
28000300	TEMPORARY DITCH CHECKS	EACH	5	5	
28000400	PERIMETER EROSION BARRIER	LIN FT	1200	1200	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
28000109	STONE RIPRAP, CLASS A5	SO YD	1008		1008
28200200	FILTER FABRIC	SO YD	1008		1008
31600710	HOT-MIX ASPHALT BASE COURSE WIDENING, 10	SO YD	946	946	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	294	294	
40600300	AGGREGATE (PRIME COAT)	TON	5.2	5.2	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	163	163	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	347	347	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	209	209	
40001000	PAVEMENT REMOVAL	SO YD	239	239	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	200	200	
50102400	CONCRETE REMOVAL	CU YD	6		6
50100225	CONCRETE STRUCTURES	CU YD	8		8
50300260	BRIDGE DECK GROOVING	SO YD	422		422
50300300	PROTECTIVE COAT	SO YD	444		444
50300205	CONCRETE WEARING SURFACE, 5"	SO YD	444		444
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SO FT	3988		3988
50500445	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3839		3839
50800200	REINFORCEMENT BARS, EPOXY COATED	POUND	6970		6970
50800515	BAR SPLICERS	EACH	113		113
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	208		208
51500100	NAME PLATES	EACH	1		1

# SCHEDULE OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	PROJECT QUANTITY	139 BR-1	
				ROADWAY 1000	BRIDGE X081-2A
52000110	PREFORMED JOINT STRIP SEAL	FOOT	95		95
52100520	ANCHOR BOLTS, 1"	EACH	6		6
53000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	LIN FT	375	375	
63100007	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4
64100157	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4		4
63000410	GUARDRAIL REMOVAL	LIN FT	425	425	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4		4
67100100	MOBILIZATION	LUMP SUM	0.5	0.5	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	LUMP SUM	1		1
70100450	TRAFFIC CONTROL AND PROTECTION STANDARD 701201	LUMP SUM	0.5	0.5	
70100460	TRAFFIC CONTROL AND PROTECTION STANDARD 701306	LUMP SUM	0.5	0.5	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	LUMP SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	50		50
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1
70106700	TEMPORARY RUMBLE STRIP	EACH	6		6
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3152	3152	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	26	26	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1102	1102	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	517	517	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	517	517	
71001100	PAINT PAVEMENT MARKING-LINE 4"	FOOT	1272	1272	
78001150	PAINT PAVEMENT MARKING-LINE 6"	FOOT	235	235	
78000400	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	8	8	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	18	18	
78200000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SO FT	450	450	
78800200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	8	1
X1003104	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		800
X1004098	SLOPE WALL REMOVAL	SO YD	800		48
20001900	ASBESTOS BEARING PAD REMOVAL	EACH	48		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	

PLOT DATE : 10/25/2006  
 FILE NAME : #FILEL#  
 PLOT SCALE : #SCALE#  
 USER NAME : #USER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**PROJECT  
SUMMARY OF QUANTITIES**

SCALE: VERT.      DRAWN BY C. SUNTKEN  
 HORIZ.              DATE 10/13/2006      CHECKED BY M. ZELINSKAS