CONTRACT NO. 66543

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	139 BR-1	KANKAKEE	69	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

LOCATION	STAGE	SIDE	LENGTH
193+12.28 TO 199+47.73	STAGE 1	LEFT	636
191+60 TO 201+00	STAGE 1	RIGHT	940
191+60 TO 201+00	STAGE 2	LEFT	940
193+12.28 TO 199+47.73	STAGE 2	RIGHT	636
TOTAL			3152

70300280 TEMPORARY PAVEMENT MARKING - LINE 24"

LOCATION	STAGE	LENGTH
191+60	STAGE 1	13
201+00	STAGE 1	13
TOTAL		26

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	STAGE	SIDE	LENGTH
193+12.28 TO 199+47.73	STAGE 1	LEFT	212
191+60 TO 201+00	STAGE 1	RIGHT	313
191+60 TO 201+00	STAGE 2	LEFT	313
193+12.28 TO 199+47.73	STAGE 2	RIGHT	212
191+60	STAGE 2		26
201+00	STAGE 2		26
TOTAL			1102

70400100 TEMPORARY CONCRETE BARRIER

LOCATION	LENGTH
193+71.63 TO 198+88.38	516.75
TOTAL	516.75

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	LENGTH
193+71.63 TO 198+88.38	516.75
TOTAL	516.75

78001110 PAINT PAVEMENT MARKING-LINE 4"

LOCATION	SIDE	LENGTH
193+12.28 TO 199+47.73	LEFT	636
193+12.28 TO 199+47.73	RIGHT	636
TOTAL		1272

78001130 PAINT PAVEMENT MARKING-LINE 6"

LOCATION	SIDE	LENGTH
191+60 TO 201+00	CENTER	235

78100100 RAISED REFLECTIVE PAVEMENT MARKERS EACH 8

78200410 GUARDRAIL MARKERS, TYPE A EACH 18

78201000 TERMINAL MARKER - DIRECT APPLIED EACH 4

78300100 PAVEMENT MARKING REMOVAL

LOCATION	SIDE	SQ FT
191+60 TO 193+12.28	CENTER	13
199+47.73 TO 201+00	CENTER	13
193+12.28 TO 199+47.73	LEFT	212
193+12.28 TO 199+47.73	RIGHT	212
TOTAL		450

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH 8

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3 EACH 2

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3 EACH 2

PLOT DATE = 10/25/2006
FILE NAME = K:\DEPT\\6691\D9305205\QUANT_FROM DUBUQUE.DGN.dgn
PLOT SCALE = *SCALE*
USER NAME = _USER_

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: VERT. HORIZ.
DATE 10/25/2006

DRAWN BY C. SUNTKEN
CHECKED BY M. ZELINSKAS

FAP ROUTE (US 45/52) SECTION BR-1 KANKAKEE CO.