

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	SUBTOTAL HANCOCK COUNTY	ROADWAY	STRUCTURE	STRUCTURES	ROADWAY	LIGHTING
						SN 034-2007	SN 034-0511 EB		
						IL 336 EB & WB	SN 034-0512 WB		
						OVER TRIBUTARY OF EAST FORK LA MOINE RIVER	IL 336 OVER EAST FORK LA MOINE RIVER		
	80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL McDONOUGH CO	80% FEDERAL 20% STATE RURAL McDONOUGH CO				
					CONSTRUCTION TYPE CODE				
					I000-2A	X028-2A	X081-2A	I000-2A	Y030-1E
30201250	PROCESSING MODIFIED SOIL 24"	SQ YD	8592					8592	
30201500	LIME	TON	3272.0	734.5	734.5			2537.5	
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	14339.0	5377.0	5377.0			8962.0	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1492					1492	
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	22254	5710	5710			16544	
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	12442					12442	
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	1259					1259	
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SQ YD	9506	2878	2878			6628	
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	32.7					32.7	
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	98.2					98.2	
40300500	COVER COAT AGGREGATE	TON	408					408	
40300600	SEAL COAT AGGREGATE	TON	204					204	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	72.2	19.1	19.1			53.1	
40600300	AGGREGATE (PRIME COAT)	TON	104	26	26			78	
40600895	CONSTRUCTING TEST STRIP	EACH	3	0.75	0.75			2.25	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	107					107	
40600990	TEMPORARY RAMP	SQ YD	260	66	66			194	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	552	552	552				
42001300	PROTECTIVE COAT	SQ YD	292					292	
44000100	PAVEMENT REMOVAL	SQ YD	51372	9531	9531			41841	
44000400	GUTTER REMOVAL	FOOT	528					528	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	94					94	
44002800	ISLAND PAVEMENT REMOVAL	SQ YD	12					12	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	453					453	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	12732	3264	3264			9468	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	53196	14079	14079			39117	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1	1				
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1			1		
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1	1				
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1					1	
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1					1	
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1					1	
50100900	REMOVAL OF EXISTING STRUCTURES NO. 7	EACH	1					1	
50101000	REMOVAL OF EXISTING STRUCTURES NO. 8	EACH	1					1	
50101100	REMOVAL OF EXISTING STRUCTURES NO. 9	EACH	1					1	

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 2 OF 8

SCALE: VERT. N/A
HORIZ. N/A
DATE 11/7/05

DRAWN BY BDS
CHECKED BY SRD