

SUMMARY OF QUANTITIES

| PAY ITEM NUMBER | PAY ITEM DESCRIPTION | UNIT | TOTAL QUANTITY | SUBTOTAL HANCOCK COUNTY | ROADWAY | STRUCTURE | STRUCTURES | ROADWAY | LIGHTING |
|-----------------|--|-------|----------------|-------------------------|---|---|--|---|---|
| | | | | | | SN 034-2007 IL 336 EB & WB OVER TRIBUTARY OF EAST FORK LA MOINE RIVER | SN 034-0511 EB SN 034-0512 WB IL 336 OVER EAST FORK LA MOINE RIVER | | |
| | | | | | 80% FEDERAL 20% STATE RURAL HANCOCK CO | 80% FEDERAL 20% STATE RURAL HANCOCK CO | 80% FEDERAL 20% STATE RURAL HANCOCK CO | 80% FEDERAL 20% STATE RURAL McDONOUGH CO | 80% FEDERAL 20% STATE RURAL McDONOUGH CO |
| | | | | | CONSTRUCTION TYPE CODE I000-2A | X028-2A | X081-2A | I000-2A | Y030-1E |
| 50101200 | REMOVAL OF EXISTING STRUCTURES NO. 10 | EACH | 1 | | | | | 1 | |
| 50102400 | CONCRETE REMOVAL | CU YD | 48.1 | 48.1 | | 48.1 | | | |
| 50105220 | PIPE CULVERT REMOVAL | FOOT | 1256 | 129 | 129 | | | 1127 | |
| 50200100 | STRUCTURE EXCAVATION | CU YD | 431 | 431 | | | 431 | | |
| 50300150 | NEOPRENE EXPANSION JOINT 2" | FOOT | 108.5 | 108.5 | | | 108.5 | | |
| 50300155 | NEOPRENE EXPANSION JOINT 2 1/2" | FOOT | 108.5 | 108.5 | | | 108.5 | | |
| 50300225 | CONCRETE STRUCTURES | CU YD | 708.2 | 708.2 | | | 708.2 | | |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 735.4 | 735.4 | | | 735.4 | | |
| 50300260 | BRIDGE DECK GROOVING | SQ YD | 2201 | 2201 | | | 2201 | | |
| 50300265 | SEAL COAT CONCRETE | CU YD | 1577.3 | 591.5 | 591.5 | | | 985.8 | |
| 50300300 | PROTECTIVE COAT | SQ YD | 2201 | 2201 | | | 2201 | | |
| 50300310 | ELASTOMERIC BEARING ASSEMBLY, TYPE I | EACH | 36 | 36 | | | 36 | | |
| 50300320 | ELASTOMERIC BEARING ASSEMBLY, TYPE II | EACH | 12 | 12 | | | 12 | | |
| 50401105 | FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 54 IN. | FOOT | 2932 | 2932 | | | 2932 | | |
| 50500405 | FURNISHING AND ERECTING STRUCTURAL STEEL | POUND | 1100 | 1100 | | | 1100 | | |
| 50800105 | REINFORCEMENT BARS | POUND | 177060 | 177060 | 90 | 66310 | 110660 | | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 279940 | 279940 | | 2000 | 277940 | | |
| 51500100 | NAME PLATES | EACH | 3 | 3 | | 1 | 2 | | |
| 54001000 | BOX CULVERT END SECTIONS | EACH | 2 | 2 | 2 | | | | |
| 54002080 | EXPANSION BOLTS 3/4 INCH X 18 INCH | EACH | 110 | 110 | | 110 | | | |
| 54003000 | CONCRETE BOX CULVERTS | CU YD | 300.7 | 300.7 | | 300.7 | | | |
| 54010606 | PRECAST CONCRETE BOX CULVERT 6' X 6' | FOOT | 283 | 283 | 283 | | | | |
| 542A0229 | PIPE CULVERTS, CLASS A, TYPE 1 24" | FOOT | 109 | | | | | 109 | |
| 542A0235 | PIPE CULVERTS, CLASS A, TYPE 1 30" | FOOT | 43 | | | | | 43 | |
| 542A0259 | PIPE CULVERTS, CLASS A, TYPE 1 54" | FOOT | 95 | | | | | 95 | |
| 542A1069 | PIPE CULVERTS, CLASS A, TYPE 2 24" | FOOT | 938 | 128 | 128 | | | 810 | |
| 542A1081 | PIPE CULVERTS, CLASS A, TYPE 2 36" | FOOT | 234 | | | | | 234 | |
| 542A1093 | PIPE CULVERTS, CLASS A, TYPE 2 48" | FOOT | 349 | | | | | 349 | |
| 542A1909 | PIPE CULVERTS, CLASS A, TYPE 3 24" | FOOT | 252 | 130 | 130 | | | 122 | |
| 542A1933 | PIPE CULVERTS, CLASS A, TYPE 3 48" | FOOT | 98 | | | | | 98 | |
| 542A2761 | PIPE CULVERTS, CLASS A, TYPE 4 36" | FOOT | 93 | | | | | 93 | |
| 542A2779 | PIPE CULVERTS, CLASS A, TYPE 4 54" | FOOT | 118 | | | | | 118 | |
| 542D0220 | PIPE CULVERTS, CLASS D, TYPE 1 15" | FOOT | 170 | | | | | 170 | |
| 542D0223 | PIPE CULVERTS, CLASS D, TYPE 1 18" | FOOT | 240 | | | | | 240 | |
| 542D0277 | PIPE CULVERTS, CLASS D, TYPE 1 72" | FOOT | 176 | 176 | 176 | | | | |

* SPECIALTY ITEMS

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 3 OF 8

SCALE: VERT. N/A
HORIZ. N/A
DATE 11/7/05

DRAWN BY BDS
CHECKED BY SRD

Plot Date: 8/20/2006
Plot Time: 12:46:40 PM
Plotted By: sdcnphue
Pen Table: ldot.tbl
Filename: I:\03033\cadd\1\constr\sheet\plmas\004_summary.dgn