

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	SUBTOTAL HANCOCK COUNTY	ROADWAY	STRUCTURE	STRUCTURES	ROADWAY	LIGHTING
						SN 034-2007 IL 336 EB & WB OVER TRIBUTARY OF EAST FORK LA MOINE RIVER	SN 034-0511 EB SN 034-0512 WB IL 336 OVER EAST FORK LA MOINE RIVER		
					80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL HANCOCK CO	80% FEDERAL 20% STATE RURAL McDONOUGH CO	80% FEDERAL 20% STATE RURAL McDONOUGH CO
					CONSTRUCTION TYPE CODE				
					I000-2A	X028-2A	X081-2A	I000-2A	Y030-1E
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2942	638	638			2304	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16860	13645	13645			3215	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	73320	15708	15708			57612	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	24966	8739	8739			16227	
70500100	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	212.5	212.5	212.5				
70500615	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2	2	2				
70500665	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	2				
* 72000100	SIGN PANEL - TYPE 1	SQ FT	813	60	60			753	
* 72000200	SIGN PANEL - TYPE 2	SQ FT	254	34	34			220	
* 72000300	SIGN PANEL - TYPE 3	SQ FT	448	64	64			384	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	14					14	
73000100	WOOD SIGN SUPPORT	FOOT	1937.5	249	249			1688.5	
73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	1					1	
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	9323	2120	2120			7203	
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	639.6	93.6	93.6			546	
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	74572	16960	16960			57612	
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	3205	430	430			2775	
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	347					347	
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	75					75	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	538	93	93			445	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6	6		6			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	24	24	24				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6	6				
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1						1
* 81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	190						190
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1510						1510
* 81600215	UNIT DUCT, 2*8XLP, 1*8 XLP GROUND 3/4" POLYETHYLENE	FOOT	1780						1780
* 82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	9						9
* 82500605	LIGHTING CONTROLLER PHOTOCCELL RELAY	EACH	1						1
* 83054100	LIGHT POLE, STEEL GALVANIZED, 45 FT. M.H., TENON MOUNT	EACH	7						7
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	52						52
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	32						32
* A2002016	TREE, AESCULUS GLABRA (OHIO BUCKEYE), 2" CALIPER, B & B	EACH	55	5	5			50	
* A2002816	TREE, CATALPA SPECIOSA (NORTHERN CATALPA), 2" CALIPER, B & B	EACH	55	10	10			45	
* A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, B & B	EACH	80	30	30			50	

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET 6 OF 8

SCALE: VERT. N/A
HORIZ. N/A
DATE 11/1/05

DRAWN BY BDS
CHECKED BY SRD

Plot Date: 8/20/2006
Plot Time: 12:46:40 PM
Plotted By: sdradue
File Path: I:\30333\cd01\construction\plans\04_summary.dgn
Printer: HP DesignJet 5000

SPY-3C