

F.A.P. RTEL	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(34-6,55-1)	HANCOCK/MCDONOUGH	433	22
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
STATE CONTRACT NO. 68206				

PAVEMENT MARKING

LOCATION	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B		EPOXY PAVEMENT MARKING						TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"	SHORT-TERM PAVEMENT MARKING STAGE 3 WB EDGES ONLY	WORK ZONE PAVEMENT MARKING REMOVAL STAGE 3 WB ONLY	RAISED REFLECTIVE PAVEMENT MARKER EACH	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) EACH	DELINEATORS EACH
	LINE 6" SKIP DASH WHITE	LINE 4" DOUBLE YELLOW	LINE 4" YELLOW	LINE 4" WHITE	LINE 8" WHITE	LINE 12" WHITE	LINE 24" WHITE	LETTERS & SYMBOLS							
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT							
STA 1354+40.00 TO STA 1405+25.00								93.6	13645	15708	638	4544	93	6	28
STA 1400+50.00 TO STA 1442+90.00	2120		8480	8480	430							4195			
SUBTOTAL HANCOCK COUNTY	2120		8480	8480	430			93.6	13645	15708	638	8739	93	6	28
STA 1442+90 TO STA 22+22.15	1538		6150	6150	215	47	46.8		12300	492		3236	52		36
STA 22+22.15 TO STA 48+99.10	1339		5354	5354	910	116	156.0		10708	428		2817	102		12
STA 48+99.10 TO STA 75+57.07	1329		5316	5316	725	46	124.8		10632	426		2797	90		12
STA 75+57.07 TO STA 115+72.45	2008		8030	8030	385	92	93.6		16060	642		4225	124		20
STA 115+72.45 TO STA 128+00.00	614		2456	2456	215	46	46.8		4912	196		1292	40		6
STA 128+00.00 TO STA 143+60.00									3215			1071			
IL 61	375	1500		1500	325		75	78.0			120	789	37		
IL 61 DETOUR										3000					
SUBTOTAL HANCOCK COUNTY	7203	1500	27306	28806	2775	347	75	546.0	3215	57612	2304	16227	445	0	86
PROJECT TOTAL	9323	1500	35786	37286	3205	347	75	639.6	16860	73320	2942	24966	538	6	114

PIPE UNDERDRAIN OUTLETS

WESTBOUND				STATION	EASTBOUND			
OUTSIDE		INSIDE			INSIDE		OUTSIDE	
OFFSET	ELEVATION	OFFSET	ELEVATION		OFFSET	ELEVATION	OFFSET	ELEVATION
				1405+25.00	8.27	532.10	68.96	532.07
68.01	531.30	9.23	531.33	1408+40.34	9.23	531.33	68.01	531.30
70.11	530.80	1.00*	529.04	1410+02.80	1.00*	529.04	70.11	530.80
66.67	531.65	10.57	531.69	1411+65.34	10.25	531.63	66.67	531.65
65.77	532.34	11.46	532.37	1413+00.00	10.25	532.17	65.77	532.34
65.65	534.86	10.06	534.64	1418+00.00	11.59	534.90	65.65	534.86
65.45	537.40	11.78	537.43	1423+00.00	11.78	537.43	65.45	537.40
65.33	539.92	11.91	539.95	1428+00.00	11.91	539.95	68.71	539.35
65.90	542.53	-	-	1433+19.81	-	-	-	-
-	-	11.33	542.70	1433+46.67	-	-	-	-
-	-	-	-	1433+82.26	11.33	542.88	-	-
-	-	-	-	1434+12.12	-	-	73.37	541.76
62.77	543.44	12.16	543.09	1434+20.00	12.16	543.09	72.67	541.79
67.15	547.73	12.13	546.34	1438+00.00	11.23	546.33	64.60	544.87
71.30	558.55	7.00	557.00	1443+00.00	6.56	557.00	69.59	555.56
70.64	571.03	7.65	569.48	1448+00.00	8.06	569.64	68.91	568.04
69.60	581.95	7.00	581.77	1+50.00	7.00	581.77	69.89	581.53
72.28	592.03	6.56	593.38	6+50.00	7.00	593.38	70.41	595.63
69.35	604.89	6.56	606.29	11+50.00	7.00	606.29	70.63	607.91
66.99	618.67	10.25	618.70	16+50.00	10.25	618.70	66.99	618.67
67.05	630.29	7.00	629.92	21+20.00	0.00	629.92	67.05	630.29
67.05	634.87	5.04 (RT)*	629.00	23+05.00	7.04*	629.00	67.05	634.87
67.05	643.40	2.42	641.98	26+50.00	10.18	643.43	67.05	643.40
66.86	655.11	10.38	655.14	31+50.00	10.38	655.14	66.86	655.11
66.67	659.91	10.57	659.95	36+50.00	10.57	659.95	66.67	659.91
65.90	662.04	11.33	662.07	41+50.00	9.80	661.82	67.43	661.79
65.90	664.04	13.23	663.85	46+50.00	2.10	663.86	73.05	663.85
65.90	666.04	1.88	665.86	51+50.00	14.25	666.10	65.90	666.04
66.73	667.87	10.50	667.91	56+42.50	10.50	667.91	66.73	667.87
68.01	668.18	9.23	668.21	58+05.00	9.23	668.21	68.01	668.18
69.35	668.28	7.89	668.31	59+67.50	7.89	668.31	69.35	668.28
69.35	668.28	7.89	668.31	62+92.50	7.89	668.31	69.35	668.28
68.01	668.18	9.23	668.21	64+55.00	9.23	668.21	68.01	668.18
66.67	667.87	10.57	667.91	66+17.50	10.57	667.91	66.67	667.87
65.96	666.35	11.27	666.38	70+30.00	11.27	666.38	65.96	666.35
65.90	664.60	7.00*	661.87	74+70.00	5.00 (LT)*	661.87	65.90	664.60
66.22	663.88	1.67	663.70	76+50.00	13.13	663.69	66.22	663.88
66.99	663.44	0.59	663.12	77+60.45	13.59	663.51	66.99	663.44
68.26	662.95	4.14	662.75	79+22.95	10.94	663.00	68.26	662.95
69.41	662.66	2.00*	659.00	80+85.45	2.00*	659.00	69.41	662.66
68.26	662.95	8.97	662.98	82+47.95	8.97	662.98	68.26	662.95
66.79	663.47	10.44	663.50	84+10.45	10.44	663.50	66.79	663.47
68.45	663.54	8.78	663.57	85+30.00	8.78	663.57	68.45	663.54
68.45	665.14	8.78	665.17	90+30.00	8.78	665.17	68.45	665.14
68.45	666.74	8.78	666.77	95+30.00	8.78	666.77	68.45	666.74
68.45	668.34	8.78	668.37	100+30.00	8.78	668.37	68.45	668.34
68.45	669.94	8.78	669.97	105+30.00	8.78	669.97	68.45	669.94
68.14	671.59	9.10	671.62	110+30.00	7.57	671.37	68.14	671.59
68.45	672.95	11.79	672.77	114+70.00	1.21	673.02	68.45	672.95
68.45	674.55	5.89	674.51	119+70.00	10.21	674.59	68.45	674.55
67.56	676.29	9.67	676.33	124+70.00	9.67	676.33	67.56	676.29

* DRAIN OUTLETS INTO STRUCTURE (CONCRETE HEADWALL FOR PIPE UNDERDRAINS NOT REQUIRED)

PIPE UNDERDRAINS

LOCATION STATION	SIDE	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS
				EACH
HANCOCK COUNTY				
STA 1400+50.00 TO STA 1430+72.79	INSIDE RT	3029	103	7
STA 1400+50.00 TO STA 1430+97.97	OUTSIDE RT	3053	122	8
STA 1405+25.00 TO STA 1430+35.88	INSIDE LT	2512	90	6
STA 1405+25.00 TO STA 1430+10.70	OUTSIDE LT	2486	103	7
STA 1433+03.70 TO STA 1442+82.39	INSIDE LT	947	21	2
STA 1433+28.88 TO STA 1442+86.01	OUTSIDE LT	980	29	2
STA 1433+65.79 TO STA 1442+91.52	INSIDE RT	902	22	2
STA 1433+90.97 TO STA 1442+95.40	OUTSIDE RT	865	37	2
SUBTOTAL HANCOCK COUNTY		14774	527	36
MCDONOUGH COUNTY				
STA 1442+82.39 TO STA 22+21.51	INSIDE LT	3076	73	7
STA 1442+86.01 TO STA 22+21.95	OUTSIDE LT	3076	105	7
STA 1442+91.52 TO STA 22+22.35	INSIDE RT	3076	73	7
STA 1442+95.40 TO STA 22+22.80	OUTSIDE RT	3075	98	7
STA 22+21.51 TO STA 48+97.60	INSIDE LT	2676	65	5
STA 22+21.95 TO STA 48+98.66	OUTSIDE LT	2678	84	6
STA 22+22.35 TO STA 48+99.54	INSIDE RT	2678	72	5
STA 22+22.80 TO STA 49+00.79	OUTSIDE RT	2678	80	6
STA 48+97.60 TO STA 75+54.72	INSIDE LT	2658	112	8
STA 48+98.66 TO STA 75+56.33	OUTSIDE LT	2658	138	9
STA 48+99.54 TO STA 75+57.80	INSIDE RT	2659	112	8
STA 49+00.79 TO STA 75+59.41	OUTSIDE RT	2658	138	9
STA 75+54.72 TO STA 115+71.37	INSIDE LT	4015	162	12
STA 75+56.33 TO STA 115+72.11	OUTSIDE LT	4016	211	13
STA 75+57.80 TO STA 115+72.74	INSIDE RT	4018	161	12
STA 75+59.41 TO STA 115+73.38	OUTSIDE RT	4016	211	13
STA 115+71.37 TO STA 128+00.00	INSIDE LT	1229	24	2
STA 115+72.11 TO STA 128+00.00	OUTSIDE LT	1228	33	2
STA 115+72.74 TO STA 128+00.00	INSIDE RT	1230	24	2
STA 115+73.38 TO STA 128+00.00	OUTSIDE RT	1227	33	2
FRONTAGE ROAD #3 LT STA 607+75	PERIMETER DRAIN			1 *
SUBTOTAL MCDONOUGH COUNTY		54625	2009	143
PROJECT TOTAL		69399	2536	179

* FRONTAGE ROAD #3 CONCRETE HEADWALL FOR PIPE UNDERDRAINS TO CONNECT TO PERIMETER TILE OUTLET (RELOCATED BY OWNER) SEE SPECIAL PROVISIONS

REVISIED SHEET 11/10/06

REVISIONS	NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

PAVEMENT MARKING & PIPE UNDERDRAINS

SCALE: VERT. N/A
HORIZ. N/A
DATE: 11/9/05

DRAWN BY: BOS
CHECKED BY: SRD