F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(34-6,55-1)	HANCOCK/ McDONOUGH	433	26
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STATE CONTRACT NO. 68206

EROSION CONTROL BLANKET

LOCATION STATION TO STATION	SIDE	BLANKET DIMENSIONS LENGTH	BLANKET DIMENSIONS WIDTH*	EROSION CONTROL BLANKET
		FOOT	FOOT	SQ YD
HANCOCK COUNTY				
IL 336				
STA 1409+75.00 TO STA 1415+36.00	RT	561.00	10.00	623
STA 1410+00.00 TO STA 1414+00.00	LT	400.00	18.00	800
STA 1414+00.00 TO STA 1415+23.45	LT	123.45	10.00	137
STA 1416+42.00 TO STA 1420+00.00	RT	358.00	10.00	398
STA 1416+80.00 TO STA 1417+00.00	LT	20.00	10.00	22
STA 1420+00.00 TO STA 1424+00.00	RT	400.00	8.00	356
STA 1433+29.28 TO STA 1434+00.00	LT	70.72	12.00	94
STA 1434+25.00 TO STA 1438+75.00	LT	450.00	12.00	600
STA 1439+25.00 TO STA 1440+00.00	LT	75.00	8.00	67
STA 1441+00.00 TO STA 1441+75.00	LT	75.00	8.00	67
STA 1441+00.00 TO STA 1442+88.62	MEDIAN	188.62	10.00	210
STA 1442+00.00 TO STA 1442+88.62	LT	VARIES	VARIES	469
STA 1442+00.00 TO STA 1442+88.62	RT	VARIES	VARIES	394
SUBTOTAL HANCOCK COUNTY				4237
MCDONOUGH COUNTY				
IL 336				
STA 1442+88.62 TO STA 1444+00.00	LT	VARIES	VARIES	719
STA 1442+88.62 TO STA 1444+00.00	RT	VARIES	VARIES	347
STA 1442+88.62 TO STA 1449+00.00	MEDIAN	611.38	10.00	679
STA 1449+00.00 TO STA 12+27.00	MEDIAN	1469.35	12.00	1959
STA 2+50.00 TO STA 15+00.00	LT	VARIES	VARIES	11478
STA 12+27.00 TO STA 21+60.00	MEDIAN	933.00	10.00	1037
STA 12+30.00 TO STA 14+75.00	RT	245.00	20.00	544
STA 23+00.00 TO STA 30+00.00	RT	700.00	16.00	1244
STA 23+00.00 TO STA 31+00.00	MEDIAN	800.00	10.00	889
STA 31+00.00 TO STA 32+00.00	RT	100.00	16.00	178
STA 32+00.00 TO STA 48+00.00	RT	1600.00	20.00	3556
STA 72+95.00 TO STA 74+00.00	RT	105.00	10.00	117
STA 76+00.00 TO STA 80+85.00	RT	485.00	12.00	647
STA 80+85.00 TO STA 83+00.00	RT	215.00	14.00	334
STA 81+26.18 TO STA 83+00.00	LT	173.82	12.00	232
STA 117+00.00 TO STA 123+00.00	LT	600.00	14.00	906
TR 257				
STA 301+80.00 TO STA 302+50.00	LT	70.00	4.00	31
FR 02				
STA 204+26.00 TO STA 204+76.00	RT	50.00	8.00	44
STA 204+76.00 TO STA 206+77.00	RT	201.00	10.00	223
FR 03				
STA 604+17.00 TO STA 604+75.00	LT	58.00	4.00	26
TR 64				
STA 696+75.00 TO STA 698+88.35	RT	213.35	14.00	332
FRONTAGE ROAD 2 DRIVEWAY				
STA 10+00.00 TO STA 13+80.00	LT	VARIES	VARIES	5491
SUBTOTAL MCDONOUGH COUNTY				31012
PROJECT TOTAL				35249

• WIDTH INCLUDES DITCH BOTTOM AND SLOPES

PERIMETER EROSION BARRIER

LOCATION STATION TO STATION	SIDE	PERIMETER EROSION BARRIER
		FOOT
HANCOCK COUNTY		
IL 336		
STA 1400+50.00 TO STA 1409+29.76	RT	896
STA 1405+25.00 TO STA 1407+00.00	LT	178
STA 1408+00.00 TO STA 1409+28.08	LT	136
STA 1428+00.00 TO STA 1430+00.00	LT	206
STA 1429+15.18 TO STA 1431+59.78	RT	265
STA 1436+00.00 TO STA 1438+42.00	RT	218
STA 1441+00.00 TO STA 1443+00.00	RT	186
SUBTOTAL HANCOCK COUNTY		2085
MCDONOUGH COUNTY		
IL 336		
STA 12+00.00 TO STA 15+58.75	RT	382
STA 106+00.00 TO STA 113+00.00	RT	703
SUBTOTAL MCDONOUGH COUNTY		1085
PROJECT TOTAL		3170

*** SEE SHEET 29 FOR ADDITIONAL EROSION CONTROL ITEMS FOR WHITMIRE ACCESS ROAD

CONCRETE CURB AND GUTTER

LOCATION STATION TO STATION	SIDE	COMBINATION CONCRETE CURB AND GUTTER TYPE M-4.06	COMBINATION CONCRETE CURB AND GUTTER TYPE M-4.24	CONCRETE GUTTER, TYPE A (MODIFIED)	CLASS SI CONCRETE (OUTLET) SPECIAL	CONCRETE MEDIAN SURFACE (4 INCH)	PROTECTIVE COAT	COMBINATION CURB AND GUTTER REMOVAL	GUTTER REMOVAL	ISLAND PAVEMENT REMOVAL
		FOOT	FOOT	FOOT	CU YD	SQ YD	SQ YD	FOOT	FOOT	SQ YD
MCDONOUGH COUNTY										
IL 336										
STA 49+23.83 TO STA 49+41.14	RT							52		
STA 49+24.32	RT									12
STA 49+26.20	RT					108	12			
STA 87+03.06 TO STA 87+14.85	RT							42		
IL 61										
STA 397+74.92 TO STA 399+40.85	LT		201				57			
STA 399+16.95 TO STA 399+41.00	RT		62				20			
STA 399+22.73 TO STA 399+34.22	RT	15					3			
FRONTAGE ROAD 2										
STA 187+32.40 TO STA 189+21.17	LT								191	
STA 194+07.42 TO STA 194+80.00	RT				11.0		35			
STA 194+85.62 TO STA 198+22.70	LT								337	
STA 194+80.00 TO STA 199+75.88	RT			496			165			
SUBTOTAL MCDONOUGH COUNTY		15	263	496	11.0	108	292	94	528	12
PROJECT TOTAL		15	263	496	11.0	108	292	94	528	12

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

EROSION CONTROL BLANKET, PERIMETER EROSION BARRIER & CONCRETE CURB AND GUTTER

SCALE: VERT. N/A HORIZ. N/A

DATE 11/9/05

DRAWN BY BDS

CHECKED BY SRD

Plot Date: 8/20/2006
Plot Time: 12:48:43 PM
Plotted By: bdsmith
Pen Table: idot.tbl
Filename: I:\03033\cad*\construction_plans\007_schedules.dgn