

LOCATION STATION TO STATION	SEEDING								
	SEEDING, CLASS 2A ACRE	SEEDING, CLASS 4A ACRE	SEEDING, CLASS 5A ACRE	TEMPORARY EROSION CONTROL SEEDING POUND	NITROGEN FERTILIZER NUTRIENT POUND	PHOSPHOROUS FERTILIZER NUTRIENT POUND	POTASSIUM FERTILIZER NUTRIENT POUND	MULCH, METHOD 1 ACRE	MULCH, METHOD 2 ACRE
HANCOCK COUNTY									
IL 336									
STA 1400+50.00 TO STA 1430+75.93	4.99	4.12	4.12		820	820	820		9.11
STA 1433+29.29 TO STA 1442+88.74	0.40	4.15	4.15		410	410	410		4.55
FR 02									
STA 167+00.00 TO STA 169+09.93		0.09	0.09		8	8	8		0.09
SUBTOTAL HANCOCK COUNTY	1.67	8.36	8.36	5000	1238	1238	1238	25.00	13.75
HANCOCK COUNTY ROUNDED TOTAL	5.50	8.25	8.25	5000	1238	1238	1238	25.00	13.75
MCDONOUGH COUNTY									
STA 1442+88.74 TO STA 22+22.15	5.48	9.10	9.10		1312	1312	1312		14.58
STA 22+22.15 TO STA 48+99.10	7.69	4.63	4.63		1109	1109	1109		12.32
STA 48+99.10 TO STA 75+57.07	5.93	6.26	6.26		1097	1097	1097		12.19
STA 75+57.07 TO STA 115+72.45	9.04	6.46	6.46		1395	1395	1395		15.50
STA 115+72.45 TO STA 128+00.00	2.49	1.82	1.82		388	388	388		4.31
TR 257									
STA 301+18.12 TO STA 303+40.00		0.16	0.16		14	14	14		0.16
FR 02									
STA 188+58.88 TO STA 207+60.95		2.92	2.92		263	263	263		2.92
IL 61									
STA 392+00.00 TO STA 398+16.24		1.05	1.05		141	141	141		1.56
STA 393+00.00 TO STA 398+00.00	0.51								
TR 28									
STA 787+51.00 TO STA 798+39.80		0.87	0.87		78	78	78		0.87
SD 01									
STA 500+00.00 TO STA 507+36.61		0.22	0.22		20	20	20		0.22
TR 36									
STA 596+37.00 TO STA 598+50.00		0.09	0.09		8	8	8		0.09
FR 03									
STA 601+57.16 TO STA 614+87.60		2.30	2.30		207	207	207		2.30
TR 64									
STA 685+66.54 TO STA 704+50.00		0.86	0.86		77	77	77		0.86
DW 193									
STA 10+13.00 TO STA 13+80.00		0.87	0.87		78	78	78		0.87
SUBTOTAL MCDONOUGH COUNTY	31.14	37.61	37.61	15000	6187	6187	6187	75.00	68.75
MCDONOUGH COUNTY ROUNDED TOTAL	31.25	37.50	37.50	15000	6187	6187	6187	75.00	68.75
PROJECT TOTAL	36.75	45.75	45.75	20000	7425	7425	7425	100.00	82.50

FILLING EXISTING WELLS		
LOCATION STATION	OFFSET	EACH
HANCOCK COUNTY		
1431+40.09	98.04' RT	1
SUBTOTAL HANCOCK COUNTY		
1		
MCDONOUGH COUNTY		
55+01.12	6.09' LT	1
70+82.59	29.24' RT	1
73+76.38	18.32' RT	1
74+27.73	91.41' LT	1
84+93.78	2.48' LT	1
SUBTOTAL MCDONOUGH COUNTY		
5		
PROJECT TOTAL		
6		

REMOVING EXISTING SEPTIC TANK		
LOCATION STATION	OFFSET	EACH
MCDONOUGH COUNTY		
73+49.02	0' RT	1
83+84.67	121' LT	1
SUBTOTAL MCDONOUGH COUNTY		
2		
PROJECT TOTAL		
2		

CHANNEL CLEANING		
LOCATION STATION	CHANNEL CLEANING	DEPTH
	FOOT	FOOT
MCDONOUGH COUNTY		
11+70.00	115'	0' - 5.0'
18+20.00	215'	0' - 1.5'
24+50.00	195'	0' - 5.5'
72+35.00	80'	0' - 6.0'
SUBTOTAL MCDONOUGH COUNTY		
605'		
PROJECT TOTAL		
605'		

ESTIMATED QUANTITY - REFER TO THE GEOTECHNICAL REPORT

FENCE			
LOCATION STATION	OFFSET	TEMPORARY FENCE	WOVEN WIRE FENCE, 4'
		FOOT	FOOT
STA 1434+00.00 TO STA 1443+14.16	RT		854
STA 1435+37.34 TO STA 1442+67.67	LT	792	
SUBTOTAL HANCOCK COUNTY		792	854
STA 1442+67.67 TO STA 21+97.76	LT	3133	
STA 1443+14.16 TO STA 21+61.00	RT		3005
STA 22+85 TO STA 32+21	RT		981
STA 40+39.77 TO STA 48+34.00	LT		795
STA 49+60.00 TO STA 58+24.39	LT		868
STA 76+14.00 TO STA 88+79.93	LT		1267
SUBTOTAL MCDONOUGH COUNTY		3133	6916
PROJECT TOTAL		3925	7770

TEMPORARY FENCE WILL NOT BE REQUIRED IF PROPERTY OWNER HAS RELOCATED EXISTING FENCE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 SEEDING, CHANNEL CLEANING,
 FILLING EXISTING WELLS &
 REMOVING EXISTING SEPTIC TANK, AND FENCE

SCALE: VERT. N/A
 HORIZ. N/A
 DATE 11/9/05

DRAWN BY BDS
 CHECKED BY SRD

Plot Date: 8/20/2006
 Plot Time: 12:46:43 PM
 Plotted By: sdonahue
 Pen Table: idot.tbl
 Filename: I:\03033\oad\1\scene\function.plans\007_schedules.dgn