

SUMMARY OF QUANTITIES

FAP PROJECT	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	(119B-3)I	TAZEWELL	31	3
STA. TO STA.				
EXISTING CONDITIONS:				
CONTRACT NO. 68415				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		1000 FED 80% STATE 20%	SFTY-2A FED 80% STATE 20%	SFTY-3N FED 80% STATE 20%			
20300100	CHANNEL EXCAVATION	CU YD	416		416				
25000300	SEEDING, CLASS 3	ACRE	0.03		0.03				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3		3				
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	3		3				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3		3				
25100630	EROSION CONTROL BLANKET	SQ YD	138		138				
28100209	STONE RIPRAP, CLASS A5	TON	1685		1685				
28200200	FILTER FABRIC	SQ YD	712		712				
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	100		100				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	35	35					
40600300	AGGREGATE (PRIME COAT)	TON	1	1					
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	21	21					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	53	20	33				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUT JOINT	SQ YD	160	160					
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	164	164					
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	35	35					
44000100	PAVEMENT REMOVAL	SQ YD	92	92					
44000700	APPROACH SLAB REMOVAL	SQ YD	107	107					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3	3					
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1				
50102400	CONCRETE REMOVAL	CU YD	2.4		2.4				
50300225	CONCRETE STRUCTURES	CU YD	3.4		3.4				
52000110	PERFORMED JOINT STRIP SEAL	FOOT	33.0		33.0				
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	299		299				
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	2,066		2,066				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	450		450				
50800515	BAR SPLICERS	EACH	8		8				
50901050	STEEL RAILING, TYPE SM	FOOT	207		207				
51500100	NAME PLATES	EACH	1		1				
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	230		230				
58300100	PC MORTAR FAIRING COURSE	FOOT	626		626				
* 63000000	STEEL PLATE BRIDGE GUARD RAIL, TYPE A	FOOT	100	100					
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4					
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	125	125					
* 63300205	REMOVE AND REINSTALL EXISTING STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	50		50				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4		4				
67100100	MOBILIZATION	L SUM	1		1				
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1		1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		1000 FED 80% STATE 20%	SFTY-2A FED 80% STATE 20%	SFTY-3N FED 80% STATE 20%			
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1					
70106700	TEMPORARY RUMBLE STRIP	EACH	12	12					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	144	144					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,107	3,107					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,132	1,132					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	329	329					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	329	329					
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1,689	1,689					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	10	10					
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4					
* 78200510	BARRIER WALL MARKERS, TYPE A	EACH	4	4					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	473	473					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10					
X0322587	CONSTRUCTION ACCESS	EACH	1		1				
* X7200200	WIDE LOAD SIGNING	L SUM	1	1					
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	45.1		45.1				
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2		2				
Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	2		2				

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES F.A.P. RTE. 693 SECTION (119B-3)I TAZEWELL COUNTY SCALE: NONE DATE: 03/24/2006
NAME	DATE	
DRAWN BY: KBF		CHECKED BY: AJE