

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
701	(128BR11-1	TAZEWELL	29	5
STA. 77+63.98		TO STA. 78+48.02		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE		TOTAL
			X080-2A	SFTY-3N	
			STATE 100% →		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50300225	CONCRETE STRUCTURES	CU YD	6		6
50300260	BRIDGE DECK GROOVING	SQ YD	273		273
50300300	PROTECTIVE COAT	SQ YD	294		294
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	299		299
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	2646		2646
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4,640		4,640
50800515	BAR SPLICERS	EACH	88		88
50901050	STEEL RAILING , TYPE SM	FOOT	244		244
51500100	NAME PLATES	EACH	1		1
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	37.5		37.5
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4		4
63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL	FOOT	125		125
△ 63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	50		50
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4		4
67100100	MOBILIZATION	LSUM	1		1
70100405	TRAFFIC CONTROL AND PROTECTION STANDARD 701321	EACH	1		1
70104600	TRAFFIC CONTROL AND PROTECTION STANDARD 701306	L SUM	1		1

* SPECIALTY ITEM

△ REVISED 1/4/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
DATE 03-24-2006

DRAWN BY CEJ
CHECKED BY