

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
701	(1288R)-1	TAZEWELL	29	6
STA. 77+63.98		TO STA. 78+48.02		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

UNIT	X080-2A	SFTY-3N	TOTAL
------	---------	---------	-------

STATE 100% \longrightarrow

CODE NO.	ITEM	UNIT	X080-2A	SFTY-3N	TOTAL
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1
70106700	TEMPORARY RUMBLE STRIP	EACH	12		12
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	176		176
70300200	TEMPORARY PAVEMENT MARKING	FOOT	7040		7040
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2405		2405
70400100	TEMPORARY CONCRETE BARRIER	FOOT	500		500
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	500		500
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	3520		3520
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6		6
78200410	GUARDRAIL MARKERS, TYPE A	EACH	4		4
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1173		1173
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6		6
X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNITS	SQ FT	299		299
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	294		294
X0325294	PREFORMED JOINT STRIP SEAL	FOOT	40		40
Z0030255	IMPACT ATTENUATORS, TEMPORARY(FULLY REDIRECTIVE, NARROW),				
	TEST LEVEL 2	EACH		2	2
Z0030320	IMPACT ATTENUATORS, RELOCATE(FULLY REDIRECTIVE), TEST LEVEL 2	EACH		2	2

* SPECIALTY ITEM

PLOT DATE * WATER
FILE NAME * #FILE#
PLOT SCALE * SCALE#
REFERENCE * REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY CEJ
 HORIZ. CHECKED BY
 DATE 03-24-2006