

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
804	12SRURS	CHAMPAIGN	50	4

### SUMMARY OF QUANTITIES

CODE NO	ITEM	CONSTRUCTION TYPE CODE:	UNIT	LOCATION OF WORK		
				100% STATE 1000-2A TOTAL QUANTITY	URBAN STA. 24+60 TO STA. 99+28.11 QUANTITY	RURAL STA. 99+28.11 TO STA. 135+00 QUANTITY
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)		GALLON	2797.0	981.0	1816.0
40300600	SEAL COAT AGGREGATE		TON	90.0	32.0	58.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)		GALLON	7833.0	5248.0	2585.0
40600300	AGGREGATE (PRIME COAT)		TON	157.0	105.0	52.0
40600895	CONSTRUCTING TEST STRIP		EACH	1.0	0.5	0.5
40600990	TEMPORARY RAMP		SQ YD	268.0	185.0	83.0
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90		TON	6580.0	4409.0	2171.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)		GALLON	773.0	552.0	221.0
40800030	AGGREGATE (PRIME COAT)		TON	16.0	12.0	4.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING		TON	649.0	464.0	185.0
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"		SQ YD	78333.0	52478.0	25855.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL		SQ YD	7725.0	5519.0	2206.0
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT		FOOT	20.0	20.0	0.0
60255500	MANHOLES TO BE ADJUSTED		EACH	8.0	4.0	4.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A		CAL MO	3.0	1.5	1.5
67100100	MOBILIZATION		L SUM	1.0	0.5	0.5
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602		L SUM	1.0	0.5	0.5
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701		L SUM	1.0	0.5	0.5
70300100	SHORT-TERM PAVEMENT MARKING		FOOT	21247.0	10623.5	10623.5
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS		SQ FT	2604.0	1669.0	935.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"		FOOT	43719.0	24270.0	19449.0
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"		FOOT	2953.0	1868.0	1085.0
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"		FOOT	158.0	28.0	130.0
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"		FOOT	1111.0	836.0	275.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL		SQ FT	2437.0	1218.5	1218.5
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS		SQ FT	2604.0	1669.0	935.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"		FOOT	43719.0	24270.0	19449.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"		FOOT	2953.0	1868.0	1085.0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"		FOOT	158.0	28.0	130.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"		FOOT	1111.0	836.0	275.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER		EACH	735.0	431.0	304.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		EACH	773.0	450.0	323.0

\* SPECIALTY ITEMS