

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
711	(1158)B6	VERMILION	43	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# SUMMARY OF QUANTITIES

LOCATION OF WORK: FAP 711 (US 136)  
Vermillion  
County

SN 092-2040

Rural  
80% Federal  
20% State  
X028-2A  
TOTAL

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	QUANTITY
20200100	EARTH EXCAVATION	CU YD	3,977.0
20400800	FURNISHED EXCAVATION	CU YD	1,100.0
20900110	POROUS GRANULAR BACKFILL	CU YD	2,180.0
• 25000210	SEEDING, CLASS 2A	ACRE	1.0
• 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90.0
• 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90.0
• 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90.0
• 25100115	MULCH, METHOD 2	ACRE	1.0
• 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100.0
28000300	TEMPORARY DITCH CHECKS	EACH	38.0
28000400	PERIMETER EROSION BARRIER	FOOT	500.0
28000500	INLET AND PIPE PROTECTION	EACH	1.0
28100107	STONE RIPRAP, CLASS A4	SQ YD	888.0
28200200	FILTER FABRIC	SQ YD	888.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	265.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTTJOINT	SQ YD	217.0
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0,N50	TON	200.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C",N50	TON	55.0
44000700	APPROACH SLAB REMOVAL	SQ YD	264.0
44004000	PAVED DITCH REMOVAL	FOOT	350.0
44004250	PAVED SHOULDER REMOVAL	SQ YD	86.0
• 48101200	AGGREGATE SHOULDERS, TYPE B	TON	12.0

• SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE: VERT. DATE  
HORIZ. DRAWN BY  
CHECKED BY