

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
711	115B018B	VERMILION	43	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

LOCATION OF WORK: FAP 711 (US 136)
Vermilion
County

SN 092-2040

Rural
80% Federal
20% State
X028-2A
TOTAL

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	QUANTITY
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	175.0
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	117.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	5.0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0
50104400	CONCRETE HEADWALL REMOVAL	EACH	1.0
51500100	NAME PLATES	EACH	1.0
54001000	BOX CULVERT END SECTIONS	EACH	2.0
54002020	EXPANSION BOLTS 3/4 INCH	EACH	132.0
54010908	PRECAST CONCRETE BOX CULVERT 9' X 8'	FOOT	505.0
54215553	METAL END SECTIONS 18"	EACH	1.0
542D1063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	114.0
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1.0
63200310	GUARDRAIL REMOVAL	FOOT	400.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0
67100100	MOBILIZATION	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	20.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7.0
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	430.0
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3.0
• X0324952	DETOUR SIGNING	L SUM	1.0
Z0038700	PERMANENT BENCH MARKS	EACH	1.0

• SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY

PLOT DATE: 10/15/2008
 PLOT NAME: 1015B018B
 PLOT SCALE: 1/4" = 1'-0"
 USER NAME: