CONTRACT NO. 70263

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
711	(115BR)BR	VERMILION	43	8
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

POROUS GRANULAR BACKFILL - 20900110

STATION	TO	STATION	CU YD
4+32.00		5+69.00	2180.0
		TOTAL =	2180.0 CU YD

SEEDING, CLASS 2A - 25000210

STATION	TO	STATION	ACRE
3+00.00 RT		9+40.00 RT	0.7
3+75.00 LT		6+00.00 LT	0.3
		TOTAL =	1.0 ACRE

NITROGEN FERILIZER NUTRIENT - 25000400

STATION	TO	STATION	POUND
3+00.00 RT		9+40.00 RT	27.0
3+75.00 LT		6+00.00 LT	63.0
		TOTAL =	90.0 POUND

PHOSPHORUS FERILIZER NUTRIENT - 25000500

STATION	TO	STATION	POUND
3+00.00 RT		9+40.00 RT	27.0
3+75.00 LT		6+00.00 LT	63.0
		TOTAL =	90.0 POUND

POTASSIUM FERILIZER NUTRIENT - 25000600

STATION	TO	STATION	POUND
3+00.00 RT		9+40.00 RT	27.0
3+75.00 LT		6+00.00 LT	63.0
		TOTAL =	90.0 POUND

MULCH, METHOD 2 - 25100115

STATION	TO	STATION	ACRE
3+00.00 RT		9+40.00 RT	0.7
3+75.00 LT		6+00.00 LT	0.3
		TOTAL =	1.0 ACRE

TEMPORARY EROSION CONTROL SEEDING - 28000250

STATION	TO	STATION	POUND
3+00.00 RT		9+40.00 RT	30.0
3+75.00 LT		6+00.00 LT	70.0
		TOTAL =	100.0 POUND

TEMPORARY DITCH CHECKS - 28000300

STATION	O/S	EACH
3+00.00	54.0' RT	1.0
3+17.68	59.4' RT	1.0
3+37.01	65.1' RT	1.0
3+60.17	70.9' RT	1.0
3+88.04	77.0' RT	1.0
4+33.08	83.8' RT	1.0
4+70.21	90.9' RT	1.0
4+95.28	97.7' RT	1.0
5+24.18	104.8' RT	1.0
6+06.42	107.1' RT	1.0
6+26.83	102.7' RT	1.0
6+46.47	97.6' RT	1.0
6+65.69	92.6' RT	1.0
6+84.82	87.4' RT	1.0
7+03.97	82.4' RT	1.0
7+23.21	77.8' RT	1.0
7+43.18	73.7' RT	1.0
7+71.71	68.5' RT	1.0
8+03.89	62.9' RT	1.0
8+63.54	54.2' RT	1.0
8+85.14	51.5' RT	1.0
9+32.64	47.5' RT	1.0
3+75.00	96.5' LT	1.0
3+87.03	98.9' LT	1.0
3+97.69	101.5' LT	1.0
4+82.24	100.2' LT	1.0
4+90.97	92.7' LT	1.0
4+99.60	85.2' LT	1.0
5+08.22	86.3' LT	1.0
5+16.84	87.9' LT	1.0
5+25.46	89.0' LT	1.0
5+34.08	83.3' LT	1.0
5+42.70	78.5' LT	1.0
5+51.32	74.9' LT	1.0
5+59.95	71.9' LT	1.0
5+78.51	52.1' LT	1.0
5+84.42	45.9' LT	1.0
6+00.00	42.1' LT	1.0
	TOTAL =	38.0 EACH

PERIMETER EROSION BARRIER - 28000400

STATION	TO	STATION	FOOT
3+00.00 RT		5+50.00 RT	150.0
6+00.00 RT		8+00.00 RT	200.0
3+75.00 LT		4+00.00 LT	25.0
4+75.00 LT		6+00.00 LT	125.0
		TOTAL =	500.0 FOOT

INLET & PIPE PROTECTION - 28000500

STATION	O/S	EACH
5+80.94	46.9' LT	1.0
	TOTAL =	1.0 EACH

STONE RIPRAP CLASS A4 - 28100107

STATION	TO	STATION	SQ YD
ADJACENT TO LT END SECTION			337.7
ADJACENT TO RT END SECTION			205.4
6+00 RT		9+32.64 RT	344.7
		TOTAL =	887.8
		TOTAL =	888.0 SQ YD

FILTER FABRIC - 28200200

STATION	TO	STATION	SQ YD
ADJACENT TO LT END SECTION			337.7
ADJACENT TO RT END SECTION			205.4
6+00 RT		9+32.64 RT	344.7
		TOTAL =	887.8
		TOTAL =	888.0 SQ YD

HOT-MIX ASHPALT SURFACE REMOVAL-BUTT JOINT - 40600982

STATION	TO	STATION	SQ YD
4+07.39		4+37.39	108.3
5+68.61		5+98.61	108.3
		TOTAL =	216.6
		TOTAL =	217.0 SQ YD

APPOACH SLAB REMOVAL - 44000700

STATION	TO	STATION	SQ YD
4+37.39		4+85.79	131.8
5+20.21		5+68.61	131.8
		TOTAL =	263.6
		TOTAL =	264.0 SQ YD

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 10/24/2006
FILE NAME = c:\projects\d505702 (v8)\text.dgn
PLOT SCALE = 42.2525 / IN.
USER NAME = scottg