

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
808	(28X)TS-3	CHAMPAIGN	14	5

70562

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITY	LOCATION OF WORK:			
				FAP 808 U.S. 45/U.S 150 & LINCOLN AVE. 90% STATE 10% URBANA	FAP 808 U.S. 45/U.S 150 & LINCOLN AVE. 100% URBANA	FAP 808 U.S. 45/U.S 150 & LINCOLN AVE. 100% URBANA	FAP 808 U.S. 45/U.S 150 & LINCOLN AVE. 88.6% STATE 10% URBANA 1.4% CHAMPAIGN
			CONSTRUCTION TYPE CODE:	Y031-1F	Y031-3D	Y030-1E	Y031-1F
				QUANTITY	QUANTITY	QUANTITY	QUANTITY
88040160	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4.0	4.0			
88040230	SIGNAL HEAD ,POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1.0	1.0			
88040260	SIGNAL HEAD ,POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2.0	2.0			
88102830	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	4.0	4.0			
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	12.0	12.0			
88500100	INDUCTIVE LOOP DETECTOR	EACH	22.0	22.0			
88600100	DETECTOR LOOP, TYPE I	FOOT	1,355.0	1,355.0			
88700200	LIGHT DETECTOR	EACH	4.0		4.0		
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1.0		1.0		
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8.0	8.0			
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	4,300.0	4,300.0			
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1.0	1.0			
89502380	REMOVE EXISTING HANDHOLE	EACH	10.0	10.0			
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	17.0	17.0			
X0323713	RADIO INTERCONNECT SYSTEM COMPLETE, LOCAL	EACH	1.0				1.0
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	711.0	711.0			
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1,728.0			1,728.0	
XX000876	LUMINAIRE, METAL HALIDE HORIZONTAL MOUNT 250 WATT	EACH	1.0			1.0	
XX006661	UNINTERRUPTIBLE POWER SUPPLY	EACH	1.0	1.0			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	1.0			