

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MACOUPIN	24	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- FAS 728 & FAU 8136
- D 6 RESURFACING 2007-1

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
LOCATION A - IL 138 WEST			
IL 138 - MAINLINE			
STA 112+33.00 TO STA 112+63.00	30	61	101.67
W FRONTAGE RD S			99.88
RAMP A	30	26	86.67
RAMP B	30	26	86.67
RAMP C	30	26	86.67
RAMP D	30	26	86.67
LOCATION C - STAUNTON ROAD			
STAUNTON RD			
STA 51+26.00 TO STA 51+56.00 (SHOULDERS)	30	20	66.67
STA 76+66.00 TO STA 76+96.00 (SHOULDERS)	30	20	66.67
RAMP C	20	VAR	160.66
RAMP D	24	VAR	207.72
TOTAL			1,049.95

PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
LOCATION A - IL 138 WEST			
RT STA 83+68.00 TO STA 83+98.00	30	29	48.33
STA 98+33.00 TO STA 98+63.00	30	49	81.67
STA 101+37.00 TO STA 101+67.00	30	49	81.67
LOCATION C - STAUNTON ROAD			
STAUNTON ROAD			
STA 51+26.00 TO STA 51+56.00	30	48 TO 49.6	162.67
STA 76+66.00 TO STA 76+96.00	30	42.6 TO 41	139.33
FRONTAGE RD NORTH	10	VAR	82.51
FRONTAGE RD SOUTH	10	VAR	88.37
TOTAL			684.55

AGGREGATE SHOULDERS, TYPE B

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	AVE DEPTH (INCH)	AGG SHLD (TON)
LOCATION A - IL 138 WEST					
IL 138 - MAINLINE					
STA 81+20.60 TO STA 98+63.00	1,742.40	6	1,161.60	2.5	165.37
STA 103+62.50 TO STA 112+63.04	900.54	6	600.36	2.5	85.47
LOCATION C - STAUNTON ROAD					
STAUNTON ROAD					
STA 51+26.00 TO STA 76+96.00	2,570.00	6	1,713.33	2.5	243.91
TOTAL					494.75

TEMPORARY RAMP

LOCATION	LENGTH (FOOT)	ROAD WIDTH (FOOT)	TEMP RAMP (SQ YD)
LOCATION A - IL 138 WEST			
IL 138 - MAINLINE			
STA 83+68.00 TO STA 83+75.50	7.5	53	44.17
STA 98+55.50 TO STA 98+63.00	7.5	48	40.00
STA 101+37.00 TO STA 101+44.50	7.5	48	40.00
STA 112+55.50 TO STA 112+63.00	7.5	61	50.83
W FRONTAGE RD S	7.5	77	64.17
W FRONTAGE RD N	5.0	48	26.67
RAMP A	7.5	26	21.67
RAMP B	7.5	26	21.67
RAMP C	7.5	26	21.67
RAMP D	7.5	26	21.67
LOCATION B - IL 138 EAST			
IL 138 - MAINLINE			
STA 124+82.17 TO STA 124+87.17	5.0	22	12.22
STA 4+38.84 TO STA 4+33.84	5.0	22	12.22
LT PRANGE ST	5.0	19	10.56
RT PRANGE ST	5.0	31	17.22
LT ILLINOIS ST	5.0	21	11.67
RT ILLINOIS ST	5.0	26	14.44
LOCATION C - STAUNTON ROAD			
STAUNTON ROAD			
STA 51+26.00 TO STA 51+33.50	7.5	48	20.00
STA 76+88.50 TO STA 76+96.00	7.5	41	17.08
RAMP C	7.5	46	19.17
RAMP D	7.5	52	21.67
FRONTAGE RD NORTH	7.5	24	10.00
FRONTAGE RD SOUTH	7.5	24	10.00
TOTAL			528.77

PLOT DATE = 10/24/2006  
 FILE NAME = c:\p\projects\652483\shsched.dgn  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FAS 728 (IL 138) & FAU 8136 (STAUNTON ROAD)  
 SECTION D 6 RESURFACING 2007-1  
 MACOUPIN COUNTY

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_