

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
758	3BR-1	MOULTRIE	24	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE X080-2A
20200100	EARTH EXCAVATION	CU YD	35	35
20400800	FURNISHED EXCAVATION	CU YD	239	239
25000200	SEEDING CLASS 2	ACRE	0.5	0.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	46	46
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	46	46
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	46	46
25100115	MULCH, METHOD 2	ACRE	0.5	0.5
25100630	EROSION CONTROL BLANKET	SQ YD	710	710
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50	50
28000300	TEMPORARY DITCH CHECKS	EACH	1	1
28000400	PERIMETER EROSION BARRIER	FOOT	430	430
28100107	STONE RIPRAP, CLASS A4	SQ YD	76	76
28200200	FILTER FABRIC	SQ YD	76	76
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1	1
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	42	42
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N50	TON	59	59
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	3	3
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	468	468
48101200	AGGREGATE SHOULDERS, TYPE B	TON	152	152
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1
50102400	CONCRETE REMOVAL	CU YD	0.8	0.8
50105200	REMOVE EXISTING CULVERTS	EACH	1	1
50300225	CONCRETE STRUCTURES	CU YD	1.0	1.0
50300260	BRIDGE DECK GROOVING	SQ YD	167	167
50300300	PROTECTIVE COAT	SQ YD	183	183
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	179	179
50301200	CONCRETE WEARING SURFACE	SQ YD	179	179

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE X080-2A
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21' DEPTH)	SO FT	1546	1546
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2510	2510
50901005	STEEL BRIDGE RAIL, TYPE 5M	FOOT	97	97
50901050	STEEL RAILING, TYPE 5M	FOOT	97	97
51500100	NAME PLATES	EACH	1	1
54200223	PIPE CULVERTS, CLASS D, TYPE 1, 18'	FOOT	80	80
54213453	END SECTIONS, 18'	EACH	2	2
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	325.0	325.0
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	2	2
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED)	EACH	2	2
63200310	GUARDRAIL REMOVAL	FOOT	652	652
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	473	473
* 78200400	GUARDRAIL REFLECTORS	EACH	9	9
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14	14
20038700	PERMANENT BENCH MARKS	EACH	1	1

* DENOTES SPECIALTY ITEM

PLOT DATE : 10/29/2008
 PLOT SCALE : 1"=500'
 USER NAME : kagrb

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE 2/06

DRAWN BY MLO
CHECKED BY PBB

Rev.