

# SUMMARY OF QUANTITIES

CONTRACT NO. 76566				
F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9177	44-1BR	ST. CLAIR	29	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL	X080-2A	-SFTY-3N-	
XZ029997	REMOVE EXISTING ATTENUATOR BASE	SQ YD	92	92		
<del>20200500</del>	<del>EARTH EXCAVATION (WIDENING)</del>	<del>CU YD</del>	<del>90</del>	<del>90</del>		
20300100	CHANNEL EXCAVATION	CU YD	150	150		
<del>35501320</del>	<del>HOT-MIX ASPHALT BASE COURSE 9"</del>	<del>SQ YD</del>	<del>728</del>	<del>728</del>		
35800100	PREPARATION OF BASE	SQ YD	243	243		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.4	0.4		
40600300	AGGREGATE (PRIME COAT)	TON	2	2		
<del>40600990</del>	<del>TEMPORARY RAMP</del>	<del>SQ YD</del>	<del>130</del>	<del>130</del>		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	85	85		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	41	41		
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	587	587		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	118	118		
44000100	PAVEMENT REMOVAL	SQ YD	653	653		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL 2"	SQ YD	757	757		
<del>44004250</del>	<del>PAVED SHOULDER REMOVAL</del>	<del>SQ YD</del>	<del>368</del>	<del>368</del>		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2	2		
50102400	CONCRETE REMOVAL	CU YD	8.9	8.9		
50200100	STRUCTURE EXCAVATION	CU YD	10.4	10.4		
50300225	CONCRETE STRUCTURES	CU YD	18.1	18.1		
50300260	BRIDGE DECK GROOVING	SQ YD	302	302		
50300300	PROTECTIVE COAT	SQ YD	309	309		
△ X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	309	309		
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	2776	2776		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7600	7600		
50800515	BAR SPLICERS	EACH	98	98		
△ 50901050	STEEL RAILING, TYPE SM	FOOT	63	63		
51500100	NAME PLATES	EACH	2	2		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	25	25		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	3		
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70101030	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1		
70106000	CHANGEABLE MESSAGE SIGN	CAL MO	1	1		
<del>70102672</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701602, SPECIAL</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>		
<del>70300100</del>	<del>SHORT TERM PAVEMENT MARKING</del>	<del>FOOT</del>	<del>96</del>	<del>96</del>		

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL	X080-2A	-SFTY-3N-	
<del>70300210</del>	<del>TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS</del>	<del>SQ FT</del>	<del>306</del>	<del>306</del>		
<del>70300220</del>	<del>TEMPORARY PAVEMENT MARKING - LINE 4"</del>	<del>FOOT</del>	<del>4571</del>	<del>4571</del>		
<del>70300240</del>	<del>TEMPORARY PAVEMENT MARKING - LINE 6"</del>	<del>FOOT</del>	<del>530</del>	<del>530</del>		
<del>70300280</del>	<del>TEMPORARY PAVEMENT MARKING - LINE 24"</del>	<del>FOOT</del>	<del>104</del>	<del>104</del>		
<del>70301000</del>	<del>WORK ZONE PAVEMENT MARKING REMOVAL</del>	<del>SQ FT</del>	<del>2070</del>	<del>2070</del>		
<del>70400500</del>	<del>TEMPORARY CONCRETE BARRIER (STATE OWNED)</del>	<del>FOOT</del>	<del>270</del>	<del>270</del>		
<del>70400600</del>	<del>RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)</del>	<del>FOOT</del>	<del>260</del>	<del>260</del>		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	894	894		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	44	44		
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS & SYMBOLS	SQ FT	122	122		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	592	592		
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	22	22		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3	3		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3	3		
* 78100300	REPLACEMENT REFLECTOR	EACH	8	8		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1		
<del>78300100</del>	<del>PAVEMENT MARKING REMOVAL</del>	<del>SQ FT</del>	<del>360</del>	<del>360</del>		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6		
X0323992	HELICAL GROUND ANCHORS	EACH	4	4		
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	42	42		
<del>Z0030240</del>	<del>IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2</del>	<del>EACH</del>	<del>2</del>		<del>2</del>	
<del>Z0030255</del>	<del>IMPACT ATTENUATORS, TEMPORARY (FULLY-REDIRECTIVE, NARROW), TEST LEVEL 2</del>	<del>EACH</del>	<del>1</del>		<del>1</del>	
<del>Z0030340</del>	<del>IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2</del>	<del>EACH</del>	<del>2</del>		<del>2</del>	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
Z0073700	TEMPORARY WALL BRACING SYSTEM	L SUM	1	1		

\* SPECIALTY ITEMS

Rev. 1-3-06

Rev.