

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9177	44-1BR	ST. CLAIR	29	5
STA. _____ TO STA. _____		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		

EARTHWORK SCHEDULE

LOCATION	CHANNEL EXCAVATION
STATION TO STATION	CU YD
CHANNEL	
STA 0+20 TO STA 0+40	16
STA 0+40 TO STA 0+60	30
STA 0+60 TO STA 0+80	26
STA 0+80 TO STA 1+00	27
STA 1+00 TO STA 1+20	33
STA 1+20 TO STA 1+40	18
SUBTOTAL	150

GUARDRAIL SCHEDULE

LOCATION	STEEL PLATE BEAM GUARDRAIL TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 6A	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL, TYPE 2	TERMINAL MARKER - DIRECT APPLIED	GUARDRAIL MARKERS, TYPE A
	FOOT	EACH	EACH	EACH	EACH	EACH
NW QUADRANT	25	1		1		2
NE QUADRANT		1		1		2
SW QUADRANT		1		1		2
SE QUADRANT		1	1		1	2
TOTAL	25	4	1	3	1	8

RESURFACING SCHEDULE

LOCATION	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE	PREPARATION OF BASE	INCIDENTAL HOT-MIX ASPHALT SURFACING
STATION TO STATION	TON	TON	TON	SQ YD	TON
SN 082-0096					
STA 98+50 TO STA 99+48	0.08	0.4	26.8		
BRIDGE OMISSION					
STA 100+52 TO STA 101+07	0.05	0.3	15.2		
CROSSOVERS					
STA 99+08 TO STA 99+48	0.06	0.3		128.0	21.6
STA 100+52 TO STA 100+85	0.06	0.3		115.0	19.4
SN 082-0097					
STA 198+50 TO STA 199+48	0.09	0.4	26.8		
BRIDGE OMISSION					
STA 200+52 TO STA 201+11	0.06	0.3	16.2		
TOTAL	0.4	2	85	243	41

RAISED REFLECTIVE PAVEMENT MARKERS SCHEDULE

LOCATION	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER ONE-WAY OPAQUE	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) ONE-WAY OPAQUE
STATION TO STATION	EACH	EACH	EACH
SN 082-0096			
STA 98+50 TO STA 99+54	1	1	
STA 99+54 TO STA 100+46	1		1
STA 100+46 TO STA 101+07	1		1
SN 082-0097			
STA 198+50 TO STA 199+54	1	1	
STA 199+54 TO STA 200+46	1		1
STA 200+46 TO STA 201+11	1	1	
TOTAL	6	3	3

PAVEMENT MARKING SCHEDULE

LOCATION	POLYUREA PAVEMENT MARKING LETTERS & SYMBOLS	POLYUREA PAVEMENT MARKING - 4"			POLYUREA PAVEMENT MARKING LINE - 24"	THERMOPLASTIC PAVEMENT MARKING - 4"			THERMOPLASTIC PAVEMENT MARKING LINE - 24"
		SKIP-DASH CENTERLINE	EDGE LINE			SKIP-DASH CENTERLINE	EDGE LINE		
			WHITE	YELLOW LT			WHITE RT	WHITE	
STATION TO STATION	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
SN 082-0096									
STA 98+50 TO STA 99+54					30	136	104		
STA 99+54 TO STA 100+46	122	20	184	92	22			44	
STA 100+46 TO STA 101+07					20	83	61		
SN 082-0097									
STA 198+50 TO STA 199+54					30	134	104		
STA 199+54 TO STA 200+46		20	184	92					
STA 200+46 TO STA 201+11					20	87	65		
SUB-TOTAL		40	368	184	100	440	334		
TOTAL	122		592		22	874		44	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAU ROUTE 9177  
 SECTION 44-1BR  
 ST. CLAIR COUNTY

PLOT DATE = 12/15/2006  
 FILE NAME = c:\pav\pms\m02\022\p1en\p1.m02\022a.rwdgn  
 PLOT SCALE = 1/4" = 1' IN.  
 REFERENCE = 888E#