

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	0711 N-1	DUPAGE	54	5
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

CODE NO.	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE		
				ROADWAY 70% FED 30% STATE 1000-2A	TRAFFIC SIGNAL 70% FED 20% STATE 10% ITASCA Y031-1F	INTERCONNECT 70% FED 30% STATE Y031-1F
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	2		2	
* 87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1		1	
* 87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1		1	
* 87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1		1	
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12		12	
* 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4		4	
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	30		30	
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15		15	
* 87900200	DRILL EXISTING HANDHOLE	EACH	1			1
* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	6		6	
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	5		5	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	437		437	
** 88700200	LIGHT DETECTOR	EACH	2		2	
** 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1	
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	4		4	
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	9247			9247
* 89502380	REMOVE EXISTING HANDHOLE	EACH	1		1	
* K1005863	TREE ROOT PRUNING	EACH	5	5		
X0321598	MANHOLES, TYPE A, 6' DIAMETER WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	77.1	77.1		
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	4780			4780
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	7	7		
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	2783	2783		
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	2783	2783		
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	4	4		
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2		

CODE NO.	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE		
				ROADWAY 70% FED 30% STATE 1000-2A	TRAFFIC SIGNAL 70% FED 15% STATE 15% ITASCA Y031-1F	INTERCONNECT 70% FED 30% STATE Y031-1F
X7015005	CHANGEABLE MESSAGE SIGN	CAL DAY	150	150		
X7030100	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III	FOOT	11163	11163		
* X8050015	SERVICE INSTALLATION, POLE MOUNT	EACH	1		1	
* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	4828			4828
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	523		523	
** X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3C, TWISTED, SHIELDED	FOOT	304		304	
* 88030020	SIGNAL HEAD, L.E.D., 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4		4	
* 88030050	SIGNAL HEAD, L.E.D., 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1	
* 88030100	SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		1	
* 88030110	SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2		2	
* 88030210	SIGNAL HEAD, L.E.D., 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1	
* 88030240	SIGNAL HEAD, L.E.D., 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1		1	
* 88102710	PEDESTRIAN SIGNAL HEAD, L.E.D., 1-FACE, BRACKET MOUNTED	EACH	2		2	
* 88102740	PEDESTRIAN SIGNAL HEAD, L.E.D., 2-FACE, BRACKET MOUNTED	EACH	2		2	
* X8950210	REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	EACH	1			1
* XX002856	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM	L SUM	1			1
XX005314	BITUMINOUS DRIVEWAY REMOVAL	SQ YD	84	84		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
△ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1		

* SPECIALTY ITEMS
 △ NON PARTICIPATING ITEMS, 100% STATE
 ** 100% VILLAGE OF ITASCA PARTICIPATION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.U. ROUTE 1321 (IL. ROUTE 19)
 IL. ROUTE 19
 SUMMARY OF QUANTITIES
 SCALE: N.T.S.
 DATE 11/21/06
 DRAWN BY ES
 CHECKED BY JIP

PLOT DATE = 11/21/06
 PLOT TIME = 11:51:15
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = JIP