F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-	06-00054-00-RS	DUPAGE	18	2
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83877

SUMMARY OF QUANTITIES

ITEM	ITEMS	UNIT	PRESIDENT STREET I000-2A QUANTITY	PRESIDENT STREET NON-PARTICIPATING QUANITY	ARMITAGE AVENUE I000-2A QUANTITY	ARMITAGE AVENUE NON-PARTICIPATING QUANITY	TOTAL QUANTITY
20101300	TREE PRUNING (1 TO 10 INCHES DIAMETER)	EACH	5	0	5	0	10
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5	0	5	0	10
20800150	TRENCH BACKFILL	CU YD	0	0	0	234	234
21101615	TOPSOIL FURNISH AND PLACE, 4"	SY	924	0	2298	0	3222
25200110	SODDING, SALT TOLERANT	SY	924	0	2298	0	3222
25200200	SUPPLEMENTAL WATERING	UNIT	60	0	150	0	210
35101600	AGGREGATE BASE COURSE, TYPE B, 4"	SY	727	0	1004	0	1731
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	100	0	100	0	200
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2324	0	1177	0	3501
40600300	AGGREGATE (PRIME COAT)	TON	46	0	24	0	70
40600895	CONSTRUCTING TEST STRIP	EACH	1	0	1	0	2
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3341	0	1693	0	5034
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SY	727	0	1004	0	1731
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SF	940	0	2646	0	3586
42400800	DETECTABLE WARNINGS	SF	277	0	252	0	529
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SY	23242	0	11774	0	35016
44000200	DRIVEWAY PAVEMENT REMOVAL	SY	727	0	1004	0	1731
44000600	SIDEWALK REMOVAL	SF	940	0	2646	0	3586
44001700	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2551	0	2200	3795	8546
44002213	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/4"	SY	0	0	0	296	296
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	5800	0	2725	0	8525
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	0	0	0	222	222
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	0	0	0	166	166
55100400	STORM SEWER REMOVAL 10"	FOOT	0	0	0	42	42
55100500	STORM SEWER REMOVAL 12"	FOOT	0	0	0	135	135
55100700	STORM SEWER REMOVAL 15"	FOOT	0	0	0	84	84
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	2	0	0	0	2
60202710	CATCH BASINS, TYPE A, 4'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	0	0	0	6	6
60209510	CATCH BASINS, TYPE C, WITH SPECIAL FRAME AND GRATE	EACH	0	1	0	4	5
60218400	MANHOLES, TYPE A, 4'-DIAMETER TYPE 1 FRAME, CLOSED LID	EACH	0	0	0	2	2
60242400	INLETS, SPECIAL	EACH	0	0	0	4	4
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	0	0	1	0	1
67100100	MOBILIZATION	L SUM	0.5	0	0.5	0	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L. SUM	0.5	0	0.5	0	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L. SUM	0.5	0	0.5	0	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L. SUM	0.5	0	0.5	0	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5800	0	2725	0	8525
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SF	109	0	0	0	109
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9428	0	0	0	9428
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	720	0	650	0	1370
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	315	0	0	0	315
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	54	0	144	0	198
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	100	0	100	0	200
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1145	0	508	0	1653
XX000667	SUB-BASE GRANULAR MATERIAL, TYPE B, 2"	SY	105	0	294	0	399
XX004774	BRICK DRIVEWAY REMOVAL AND REPLACEMENT	SF	77	0	0	0	77
XX006392	CLASS D PATCHES, 6" (SPECIAL)	SY	2324	0	1178	0	3502
Z0017500	DRAINAGE & UTILITY STRUCTURE ADJUSTMENT (SPECIAL)	EACH	24	0	3	0	27
Z0018100	DRAINAGE STRUCTURE ADJUSTMENT (SPECIAL)	EACH	0	0	1	0	1
Z0018200	DRAINAGE STRUCTURE RECONSTRUCTION (SPECIAL)	EACH	1	0	0	0	1
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	2	0	0	0	2
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	0	1	0	9	10
Δ Z0076600	TRAINEES	HOUR					500

* SPECIALTY ITEMS

Δ Y080

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITES

SCALE N.T.S. DRAWN BY BEH

DATE 11/3/2006 CHECKED BY LMF

11/3/2006 N:\GLENDALEHEIGHTS\0451C36\CIVIL\0451C36_01.DUA